



KONICA MINOLTA

bizhub 160f

User Manual



The essentials of imaging



Contents

Contents

1 Introduction

1.1	Safety information	1-3
	Warning and precaution symbols	1-4
	Meaning of symbols	1-4
	Disassemble and modification	1-5
	Power cord	1-6
	Power source	1-7
	Power plug	1-8
	Grounding	1-9
	Installation	1-10
	Ventilation	1-11
	Actions in response to troubles	1-12
	Consumables	1-13
	When moving the machine	1-14
	Before successive holidays	1-14
1.2	Regulation notices	1-15
	CE Marking (Declaration of conformity)	1-15
	For U.S.A. Users	
	FCC Part 15-Radio frequency devices	1-15
	For Canada Users	
	Interference-Causing Equipment Standard (ICES-003 Issue 3) ...	1-17
	For users in countries subject to class B regulations	1-17
	For users in countries not subject to class B regulations	1-17
	Laser safety	1-17
	Internal laser radiation	1-18
	CDRH regulation	1-19
	For European users	1-19
	For Denmark users	1-20
	For Finland, Sweden users	1-20
	For Norway users	1-21
	Laser safety label	1-22
	Ozone release	1-23
	Acoustic noise	1-23
1.3	Energy Star®	1-24
	Energy Star® partner	1-24
	What is an Energy Star® product?	1-24
1.4	Trademarks and registered trademarks	1-24

1.5	Explanation of manual conventions	1-25
	Safety advices	1-25
	Sequence of action	1-25
	Tips	1-26
	Special text markings	1-26
1.6	Explanation of basic concepts and symbols	1-27
	Paper feeding	1-27
	Width and length	1-28

2 Precaution

2.1	Installation precautions	2-3
	Installation site	2-3
	Power source	2-3
	Space requirements	2-4
2.2	Operation precautions	2-5
	Operating environment	2-5
	Proper use	2-5
	Transporting the machine	2-6
	Care of machine supplies	2-6
2.3	Legal restrictions on copying	2-7

3 Before making copies or faxing

3.1	Available features	3-3
3.2	Components and their functions	3-4
3.3	Parts names and their functions	3-5
	Main unit	3-5
	Automatic document feeder	3-7
	Inside the machine	3-8
	Adjusting the angle of the copy tray	3-9
	Options	3-10
3.4	Control panel	3-12
	Names of control panel parts and their functions	3-12
	Display indications – in copy mode	3-15
	Display indications – in fax mode	3-16
	Symbol list	3-17
3.5	Turning the machine on/off	3-18
	Turning the machine on	3-18
	Turning the machine off	3-19
3.6	Initial mode	3-20

3.7	Useful functions	3-21
	Panel resetting	3-21
	Auto panel reset	3-21
	Energy save mode	3-22
	Auto print start	3-22
	Auto tray switching	3-22
3.8	Entering Text	3-23
	Key operation	3-23
	List of characters	3-23
	Charging Input Mode	3-23
	Inputting Example	3-24
3.9	Copy paper	3-26
	Paper specifications	3-26
	Precautions for loading paper	3-27
	Unsuitable paper	3-27
	Loading paper	3-28
	Loading paper into tray 1	3-30
	Loading paper into the bypass tray	3-31
	Loading paper into tray 2 (option)	3-32
3.10	Loading originals	3-33
	Two ways of loading the original	3-33
	Specific types of originals	3-33
	Loading originals in the automatic document feeder	3-33
	Precautions for loading paper into the automatic document feeder	3-33
	Loading originals into the automatic document feeder	3-34
	Placing the original on the original glass	3-35
	Positioning a sheet original	3-36
	Positioning highly transparent originals	3-37
	Positioning books	3-38
3.11	Checking the machine status	3-40
3.11.1	TOTAL PAGE	3-41
	Checking a TOTAL PAGE count	3-41
3.11.2	TX/RX RESULT	3-42
	Checking the TX/RX RESULT	3-42
3.11.3	PRINT REPORT	3-43
	Printing a PRINT REPORT	3-43
	TX Result report	3-44
	RX Result report	3-44
	Activity report	3-45
	Memory data list	3-45
	Memory image print	3-45
	One-touch list	3-46

Speed dial list	3-46
Key setting list	3-46
Machine status	3-46
Configuration page	3-46

3.12 Print area	3-47
------------------------------	-------------

4 Making copies

4.1 Basic copies	4-3
Making a basic copy	4-3
4.2 Paper selection	4-5
Selecting the paper tray manually	4-5
Specifying the size and type of manually fed paper	4-6
4.3 Zoom ratio	4-10
Zoom ratio settings	4-10
Specifying the zoom ratio	4-11
4.4 Image Density	4-12
Image density setting	4-12
Specifying the image density	4-13
4.5 2in1 copies	4-14
2in1 copy function	4-14
Specifying settings for 2in1 copies	4-14
4.6 Finishing copies	4-15
Finishing modes	4-15
Specifying sorting	4-16

5 Faxing

5.1 Dialing	5-3
Using direct dialing to communicate with overseas destinations ..	5-3
To fax by entering the fax number directly using the 10-key pad ..	5-3
To fax using one-touch dialing	5-5
To fax using speed dialing	5-6
To fax using group dialing	5-7
To fax using chain dialing	5-8
To fax using program dialing	5-9
To fax using the phone book	5-10
To search the phone book	5-11
To redial the last recipient called	5-13
5.2 Transmission settings	5-14
Adjusting the fax resolution	5-14
To specify the resolution	5-14

5.3	Basic Faxing	5-15
	To fax using the automatic document feeder	5-15
	To fax documents positioned on the original glass	5-17
	If the memory becomes full while scanning fax documents	5-18
5.4	Checking transmission results	5-19
	To check the transmission result	5-19

6 Fax transmission/Reception methods

6.1	Transmission methods	6-3
6.1.1	Memory transmission	6-3
	To specify memory TX	6-3
6.1.2	Direct transmission	6-5
6.1.3	Manual transmission	6-6
	To send a fax manually	6-6
6.1.4	Batch transmission	6-8
	To fax using batch transmission	6-8
6.1.5	Broadcast transmission	6-9
	To fax using broadcast transmission	6-9
6.1.6	Timer transmission	6-12
	To fax using timer transmission	6-12
6.1.7	Mailbox transmission	6-14
	To fax using mailbox transmission	6-14
6.1.8	Relay initiation transmission	6-16
	To fax using relay initiation transmission	6-16
6.1.9	Polling Transmission	6-18
	To set up polling transmission	6-18
	To delete a document from the polling transmission setup	6-19
6.1.10	Canceling (Deleting) a Document Queued in the Memory for Transmission	6-21
	To cancel a queued document	6-21
6.2	Reception methods	6-23
6.2.1	Manual reception	6-23
	To receive a fax manually	6-23
6.2.2	Memory reception	6-23
6.2.3	Mailbox reception	6-24
	To retrieve a document from a mailbox	6-24

6.2.4	Polling Reception	6-25
	To receive a fax using polling reception	6-25
6.3	Using F codes	6-27
6.3.1	Using Mailboxes	6-28
	Specifying mailboxes	6-28
	F code mailbox transmission/reception	6-28
6.3.2	Specifying F codes	6-29
	When sending faxes	6-29
	Programming F codes	6-29

7 Using the utility mode

7.1	Machine settings	7-4
	Selecting the MACHINE SETTING menu	7-6
	Specifying AUTO PANEL RESET	7-7
	Specifying ENERGY SAVE MODE	7-8
	Specifying DENSITY (ADF)	7-8
	Specifying DENSITY (BOOK)	7-9
	Specifying PRINT DENSITY	7-9
	Specifying LCD CONTRAST	7-10
	Specifying LANGUAGE	7-10
	Specifying LAMP OFF TIME	7-11
	Specifying BUZZER VOLUME	7-11
	Specifying INITIAL MODE	7-12
7.2	Paper source settings	7-13
	Selecting the PAPER SOURCE SETUP menu	7-13
	Specifying TRAY1 PAPER	7-14
	Specifying TRAY SETTING	7-16
7.3	User management settings	7-17
	Selecting the USER MANAGEMENT menu	7-17
7.4	Admin. management settings	7-18
	Selecting the ADMIN. MANAGEMENT menu	7-19
	Specifying REMOTE MONITOR	7-20
7.5	Copy settings	7-21
	Selecting the COPY SETTING menu	7-22
	Specifying PAPER PRIORITY	7-22
	Specifying DENSITY PRIORITY	7-23
	Specifying DENSITY LEVEL (A)	7-23
	Specifying DENSITY LEVEL (M)	7-24
	Specifying OUTPUT PRIORITY	7-24
	Specifying RESOLUTION	7-25

7.6	Fax registration settings	7-26
	Selecting the FAX REGISTRATION menu	7-27
	Specifying ONE-TOUCH DIAL	7-28
	To program a one-touch dial key	7-28
	To change/delete a programmed one-touch dial key	7-30
	Specifying SPEED DIAL	7-32
	To program a speed dial number	7-32
	To change/delete a programmed speed dial number	7-34
	Specifying GROUP DIAL	7-36
	To program a group of fax numbers	7-36
	To change/delete a programmed group of fax numbers	7-38
	Specifying PROGRAM DIAL	7-40
	To set program dialing	7-40
	To change/delete a programmed broadcast transmission	7-42
	To change/delete a programmed timer transmission	7-43
	To change/delete a programmed mailbox transmission	7-45
	To change/delete a programmed polling reception	7-47
	To change/delete a programmed relay initiation transmission	7-49
	Specifying BATCH TX	7-51
	To set batch transmitting	7-51
	To change the batch transmission setting	7-53
	To delete the batch transmission setting	7-54
	Specifying MAILBOX	7-55
	To register a mailbox	7-55
	To delete a mailbox	7-56
7.7	TX operation settings	7-57
	Selecting the TX OPERATION menu	7-58
	Specifying SCAN CONTRAST	7-58
	Specifying RESOLUTION	7-59
	Specifying DEFAULT TX	7-60
	Specifying HEADER	7-60
7.8	RX operation settings	7-61
	Selecting the RX OPERATION menu	7-63
	Specifying MEMORY RX MODE	7-64
	To cancel memory reception	7-65
	Specifying NO. of RINGS	7-65
	Specifying REDUCTION RX	7-66
	Specifying RX PRINT	7-66
	Specifying RX MODE	7-66
	Specifying FORWARD	7-67
	Specifying FOOTER	7-68
	Specifying SELECT TRAY	7-68
	Specifying CLOSED NETWORK	7-69

7.9	Communication settings	7-70
	Selecting the COMM. SETTING menu	7-70
	Specifying TONE/PULSE	7-71
	To specify the telephone dialing system	7-71
	Specifying LINE MONITOR	7-72
	Specifying PSTN/PBX	7-73
	To specify the telephone wiring system	7-73
7.10	Reporting settings	7-74
	Selecting the REPORTING menu	7-75
	Specifying ACTIVITY REPORT	7-75
	Specifying RESERV.REPORT	7-76
	Specifying TX RESULT REPORT	7-76
	Specifying RX RESULT REPORT	7-76
7.11	Initial user data settings	7-77
	Selecting the INITIAL USER DATA menu	7-77
	Specifying DATE&TIME	7-78
	Specifying USER FAX NO.	7-78
	Specifying USER NAME	7-79

8 When a message appears

8.1	When the message PAPER EMPTY appears	8-3
	PAPER EMPTY message	8-3
	Loading paper into tray 1	8-4
	Loading paper into the bypass tray	8-4
	Loading paper into tray 2 (option)	8-5
8.2	When the message TONER EMPTY appears	8-6
	TONER EMPTY message	8-6
	Replacing the toner cartridge	8-7
8.3	When the message D/C LIFE appears	8-11
	Replacing the drum cartridge	8-12
8.4	When the message PAPER MISFEED appears	8-15
	PAPER MISFEED message	8-15
	Clearing a paper misfeed in the paper trays	8-15
8.5	When the message PAPER JAM appears	8-18
	PAPER JAM message	8-18
	Clearing a paper misfeed in the machine	8-18
8.6	When the message ORIGINAL DOC. JAM appears	8-22
	ORIGINAL DOC. JAM message	8-22
	Clearing a paper misfeed in automatic document feeder	8-22

8.7	When the message PAPER SIZE ERROR appears	8-24
	PAPER SIZE ERROR message	8-24
	Paper size error for tray 1	8-24
	Paper size error for the bypass tray	8-25
8.8	When the message MACHINE TROUBLE appears	8-27
8.9	What does each message mean?	8-28
8.10	When incorrect copies are produced	8-30
8.11	The machine is not functioning as designed	8-33
8.12	When faxing is not performed correctly	8-34
	Faxes cannot be sent	8-34
	Faxes cannot be received	8-35
	Calls cannot be sent	8-36

9 Miscellaneous

9.1	Specifications	9-3
	bizhub 160f	9-3
	Automatic document feeder	9-4
	Paper feed unit PF-501	9-5
9.2	List of utility/function menu commands	9-6
	Utility menu commands	9-6
	Function menu commands	9-8
9.3	Care of the machine	9-9
	Cleaning	9-9
	Housing cover	9-9
	Original glass	9-9
	Original pad	9-10
	Control panel	9-10
9.4	Function combination matrix	9-11
	Conditions for combined functions	9-11
	Conditions for combined functions	9-11
9.5	Glossary	9-12
9.6	Paper size and zoom ratio tables	9-13
	Paper sizes	9-13
	Zoom ratios	9-14

10 Index





Introduction

1 Introduction

1.1 Safety information

This section contains detailed instructions on the operation and maintenance of this machine. To achieve optimum utility of this device, all operators should carefully read and follow the instructions in this manual.

Please read the following section before connecting the machine to the supply. It contains important information related to user safety and preventing equipment problems.

Please keep this manual in a handy place near the machine.

Make sure you observe all of the precautions appear in each section of this manual.

KM_Ver.01E_F

**Note**

Some parts of the contents of this section may not correspond with the purchased product.

Warning and precaution symbols

The following indicators are used on the warning labels or in this manual to categorize the level of safety warnings.

WARNING

Ignoring this warnings could cause serious injury or even death.







→ Do not ignore this safety advices.

CAUTION

Ignoring this cautions could cause injury or damage to property.

→ Do not ignore this safety advices.

Meaning of symbols



Symbol	Meaning	Example	Meaning
	A triangle indicates a danger against which you should take precaution.		This symbol warns against possible causes of burns.
	A diagonal line indicates a prohibited course of action.		This symbol warns against dismantling the device.
	A black circle indicates an imperative course of action.		This symbol indicates you must unplug the device.

Disassemble and modification

WARNING

Ignoring this warnings could cause serious injury or even death.

→ Do not ignore this safety advices.

Warning	Symbol
<ul style="list-style-type: none">Do not attempt to remove the covers and panels which have been fixed to the product. Some products have a high-voltage part or a laser beam source inside that could cause an electrical shock or blindness.	
<ul style="list-style-type: none">Do not modify this product, as a fire, electrical shock, or breakdown could result. If the product employs a laser, the laser beam source could cause blindness.	




Power cord



WARNING

Ignoring this warnings could cause serious injury or even death.

→ Do not ignore this safety advices.





Warning	Symbol
<ul style="list-style-type: none"> Use only the power cord supplied in the package. If a power cord is not supplied, only use the power cord and plug that is specified in POWER CORD INSTRUCTION. Failure to use this cord could result in a fire or electrical shock. 	
<ul style="list-style-type: none"> Use the power cord supplied in the package only for this machine and NEVER use it for any other product. Failure to observe this precaution could result in a fire or electrical shock. 	
<ul style="list-style-type: none"> Do not scratch, abrade, place a heavy object on, heat, twist, bend, pull on, or damage the power cord. Use of a damaged power cord (exposed core wire, broken wire, etc.) could result in a fire or breakdown. Should any of these conditions be found, immediately turn OFF the power switch, unplug the power cord from the power outlet, and then call your authorized service representative. 	

Power source

WARNING

Ignoring this warnings could cause serious injury or even death.


→ Do not ignore this safety advices.

Warning	Symbol
<ul style="list-style-type: none"> Use only the specified power source voltage. Failure to do that could result in a fire or electrical shock. 	
<ul style="list-style-type: none"> Connect power plug directly into wall outlet having the same configuration as the plug. Use of an adapter leads to the product connecting to inadequate power supply (voltage, current capacity, grounding), and may result in fire or shock. If proper wall outlet is not available, the customer shall ask qualified electrician for the installation. 	
<ul style="list-style-type: none"> Do not use a multiple outlet adapter nor an extension cord in principle. Use of an adapter or an extension cord could cause a fire or electrical shock. Contact your authorized service representative if an extension cord is required. 	
<ul style="list-style-type: none"> Consult your authorized service representative before connecting other equipment on the same wall outlet. Overload could result in a fire. 	

CAUTION

Ignoring this cautions could cause injury or damage to property.

→ Do not ignore this safety advices.

Caution	Symbol
<ul style="list-style-type: none"> The outlet must be near the equipment and easily accessible. Otherwise you can not pull out the power plug when an emergency occurs. 	

Power plug



WARNING

Ignoring this warnings could cause serious injury or even death.

→ Do not ignore this safety advices.

Warning	Symbol
<ul style="list-style-type: none"> Do not unplug and plug in the power cord with a wet hand, as an electrical shock could result. 	
<ul style="list-style-type: none"> Plug the power cord all the way into the power outlet. Failure to do this could result in a fire or electrical shock. 	



CAUTION

Ignoring this cautions could cause injury or damage to property.

→ Do not ignore this safety advices.


Caution	Symbol
<ul style="list-style-type: none"> Do not tug the power cord when unplugging. Pulling on the power cord could damage the cord, resulting in a fire or electrical shock. 	
<ul style="list-style-type: none"> Remove the power plug from the outlet more than one time a year and clean the area between the plug terminals. Dust that accumulates between the plug terminals may cause a fire. 	

Grounding

WARNING

Ignoring this warnings could cause serious injury or even death.

→ Do not ignore this safety advices.


Warning	Symbol
<ul style="list-style-type: none">• Connect the power cord to an electrical outlet that is equipped with a grounding terminal.	

Installation

WARNING

Ignoring this warnings could cause serious injury or even death.






→ Do not ignore this safety advices.

Warning	Symbol
<ul style="list-style-type: none"> Do not place a flower vase or other container that contains water, or metal clips or other small metallic objects on this product. Spilled water or metallic objects dropped inside the product could result in a fire, electrical shock, or breakdown. Should a piece of metal, water, or any other similar foreign matter get inside the product, immediately turn OFF the power switch, unplug the power cord from the power outlet, and then call your authorized service representative. 	

CAUTION

Ignoring this cautions could cause injury or damage to property.

→ Do not ignore this safety advices.


Caution	Symbol
<ul style="list-style-type: none"> After installing this product, mount it on a secure base. If the unit moves or falls, it may cause personal injury. 	
<ul style="list-style-type: none"> Do not place the product in a dusty place, or a site exposed to soot or steam, near a kitchen table, bath, or a humidifier. A fire, electrical shock, or breakdown could result. 	
<ul style="list-style-type: none"> Do not place this product on an unstable or tilted bench, or in a location subject to a lot of vibration and shock. It could drop or fall, causing personal injury or mechanical breakdown. 	
<ul style="list-style-type: none"> Do not let any object plug the ventilation holes of this product. Heat could accumulate inside the product, resulting in a fire or malfunction. 	
<ul style="list-style-type: none"> Do not use flammable sprays, liquids, or gases near this product, as a fire could result. 	

Ventilation

 **CAUTION**

Ignoring this cautions could cause injury or damage to property.

→ Do not ignore this safety advices.



Caution	Symbol
<ul style="list-style-type: none">• Always use this product in a well ventilated location. Operating the product in a poorly ventilated room for an extended period of time could injure your health. Ventilate the room at regular intervals.	

Actions in response to troubles

WARNING

Ignoring this warnings could cause serious injury or even death.


→ Do not ignore this safety advices.

Warning	Symbol
<ul style="list-style-type: none"> Do not keep using this product, if this product becomes inordinately hot or emits smoke, or unusual odor or noise. Immediately turn OFF the power switch, unplug the power cord from the power outlet, and then call your authorized service representative. If you keep on using it as is, a fire or electrical shock could result. 	
<ul style="list-style-type: none"> Do not keep using this product, if this product has been dropped or its cover damaged. Immediately turn OFF the power switch, unplug the power cord from the power outlet, and then call your authorized service representative. If you keep on using it as is, a fire or electrical shock could result. 	

CAUTION

Ignoring this cautions could cause injury or damage to property.

→ Do not ignore this safety advices.


Caution	Symbol
<ul style="list-style-type: none"> The inside of this product has areas subject to high temperature, which may cause burns. When checking the inside of the unit for malfunctions such as a paper misfeed, do not touch the locations (around the fusing unit, etc.) which are indicated by a "Caution HOT" caution label. 	

Consumables

WARNING

Ignoring this warnings could cause serious injury or even death.



→ Do not ignore this safety advices.

Warning	Symbol
<ul style="list-style-type: none"> Do not throw the toner cartridge or toner into an open flame. The hot toner may scatter and cause burns or other damage. 	

CAUTION

Ignoring this cautions could cause injury or damage to property.

→ Do not ignore this safety advices.



Caution	Symbol
<ul style="list-style-type: none"> Do not leave a toner unit or drum unit in a place within easy reach of children. Licking or ingesting any of these things could injure your health. 	
<ul style="list-style-type: none"> Do not store toner units and PC drum units near a floppy disk or watch that are susceptible to magnetism. They could cause these products to malfunction. 	

When moving the machine

CAUTION

Ignoring this cautions could cause injury or damage to property.

→ Do not ignore this safety advices.


Caution	Symbol
<ul style="list-style-type: none"> Whenever moving this product, be sure to disconnect the power cord and other cables. Failure to do this could damage the cord or cable, resulting in a fire, electrical shock, or breakdown. 	
<ul style="list-style-type: none"> When moving this product, always hold it by the locations specified in the User's Guide or other documents. If the unit falls it may cause severe personal injury. The product may also be damaged or malfunction. 	

Before successive holidays

CAUTION

Ignoring this cautions could cause injury or damage to property.

→ Do not ignore this safety advices.

Caution	Symbol
<ul style="list-style-type: none"> Unplug the product when you will not use the product for long periods of time. 	

1.2 Regulation notices

CE Marking (Declaration of conformity)

This product complies with the following EU directives:
89/336/EEC, 73/23/EEC and 93/68/EEC directives.

This declaration is valid for the region of the European Union.

CAUTION

Interference with radio communications.

- This device must be used with shielded interface cables. The use of non-shielded cable is likely to result in interference with radio communications and is prohibited under EU directives.

For U.S.A. Users

FCC Part 15-Radio frequency devices

FCC: Declaration of conformity

Product type	Multi function product
Product name	bizhub 160/161
Options	

This device complies with Part 15 of the FCC Rules

Operation is subject to the following two conditions:

- This device may not cause harmful interference, and this device must accept any interference received, including interference that may cause undesired operation.

This equipment has been tested and found to comply with the limits for a Class B digital device, pursuant to Part 15 of the FCC Rules. These limits are designed to provide reasonable protection against harmful interference in a residential installation. This equipment generates, uses and can radiate radio frequency energy and, if not installed and used in accordance with the instructions, may cause harmful interference to radio communications. However, there is no guarantee that interference will not occur in a particular installation. If this equipment does cause harmful interference to radio or television reception, which can be determined by turning the equipment off and on, the user is encouraged to try to correct the interface by one or more of the following measures:

- Reorient or relocate the receiving antenna.
- Increase the separation between the equipment and receiver.
- Connect the equipment into an outlet on a circuit different from that to which the receiver is connected.
- Consult the dealer or an experienced radio/TV technician for help.



WARNING

Any changes made by the purchaser or user without first contacting the manufacturer will be subject to penalty under FCC regulations.

- The design and production of this unit conform to FCC regulations, and any changes or modifications must be registered with the FCC and are subject to FCC control.
-



CAUTION

Interference to radio communications.

- This device must be used with shielded interface cables. The use of non-shielded cable is likely to result in interference with radio communications and is prohibited under FCC rules.
-

For Canada Users**Interference-Causing Equipment Standard (ICES-003 Issue 3)**

This Class B digital apparatus complies with Canadian ICES-003.

Cet appareil numérique de la classe B est conforme à la norme NMB-003 du Canada.

For users in countries subject to class B regulations

 **CAUTION****Interference with radio communications.**

- This device must be used with shielded interface cables. The use of non-shielded cable is likely to result in interference with radio communications and is prohibited under CISPR 22 rules and local rules.
-

For users in countries not subject to class B regulations

 **WARNING****Interference with radio communications.**

- This is a class A product. In a domestic environment, this product may cause radio interference in which case the user may be required to take adequate measures.
 - This device must be used with shielded interface cables. The use of non-shielded cable is likely to result in interference with radio communications and is prohibited under CISPR 22 rules and local rules.
-

Laser safety

This is a digital machine which operates using a laser. There is no possibility of danger from the laser provided the machine is operated according to the instructions in this manual.

Since radiation emitted by the laser is completely confined within a protective housing, the laser beam cannot escape from the machine during any phase of user operation.

This machine is certified as a class 1 laser product. In other words, the machine does not produce hazardous laser radiation.

Internal laser radiation

Specifications	
Maximum average radiation power	36.903 μ W at the laser aperture of the print head unit
Wavelength	770-800 nm


This product employs a class 3b laser diode that emits an invisible laser beam.

The laser diode and the scanning polygon mirror are incorporated in the print head unit.

WARNING

Incorrect handling may result in hazardous radiation exposure.

- The print head unit is not a field-serviceable item.
- Therefore, the print head unit should not be opened under any circumstances.



CDRH regulation

This machine is certified as a class 1 laser product under radiation performance standard according to the Food, Drug and Cosmetic Act of 1990. Compliance is mandatory for laser products marketed in the United States and is reported to the Center for Devices and Radiological Health (CDRH) of the U.S. Food and Drug Administration of the U.S. Department of Health and Human Services (DHHS). This means that the device does not produce hazardous laser radiation.

The label shown on page 1-22 indicates compliance with the CDRH regulations and must be attached to laser products marketed in the United States.

CAUTION

Incorrect handling may result in hazardous radiation exposure.

- Use of controls, adjustments or performance of procedures other than those specified in this manual may result in hazardous radiation exposure.

This is a semiconductor laser. The maximum power of the laser diode is 15 mW and the wavelength is 770-800 nm.

For European users

CAUTION

Incorrect handling may result in hazardous radiation exposure.

- Use of controls, adjustments or performance of procedures other than those specified in this manual may result in hazardous radiation exposure.

This is a semiconductor laser. The maximum power of the laser diode is 15 mW and the wavelength is 770-800 nm.

For Denmark users

ADVARSEL

Usynlig laserstråling ved åbning, når sikkerhedsafbrydere er ude af funktion.

- Usynlig laserstråling ved åbning, når sikkerhedsafbrydere er ude af funktion. Undgå udsættelse for stråling. Klasse 1 laser produkt der opfylder IEC60825 sikkerheds kravene.
-

Dette er en halvlederlaser. Laserdiodens højeste styrke er 15 mW og bølglængden er 770-800 nm.

For Finland, Sweden users

LOUKAN 1 LASERLAITE
KLASS 1 LASER APPARAT

VAROITUS

Tämä on puolijohdelaser.

- Laitteen Käyttäminen muulla kuin tässä käyttöohjeessa mainitulla tavalla saattaa altistaa käyttäjän turvallisuusluokan 1 ylittävälle näkymättömälle lasersäteilylle.
-

Tämä on puolijohdelaser. Laserdiodin suurin teho on 15 mW ja aallonpituus on 770-800 nm.

VARNING

Det här är en halvledarlaser.

- Om apparaten används på annat sätt än i denna bruksanvisning specificerats, kan användaren utsättas för osynlig laserstrålning, som överskrider gränsen för laserklass 1.
-

Det här är en halvledarlaser. Den maximala effekten för laserdioden är 15 mW och våglängden är 770-800 nm.



VAROITUS

Avattaessa ja suojalukitus ohitettaessa olet alttiina näkymättömälle lasersäteilylle.

→ Älä katso säteeseen.



VARNING

Osynlig laserstrålning när denna del är öppnad och spärren är urkopplad.

→ Betrakta ej strålen.

For Norway users



ADVARSEL!


Dette en halvleder laser.

→ Dersom apparatet brukes på annen måte enn spesifisert i denne brukersanvisning, kan brukeren utsettes for usynlig laserstråling som overskrider grensen for laser klass 1.

Dette en halvleder laser. Maksimal effekt till laserdiode er 15 mW og bølglengde er 770-800 nm.

Laser safety label

A laser safety label is attached to the outside of the machine as shown below.



Ozone release

CAUTION

A negligible amount of ozone is generated during normal operation of this machine.

An unpleasant odor may, however, be created in poorly ventilated rooms during extensive machine operations. For a comfortable, healthy, and safe operating environment, it is recommended that the room be well ventilated.

→ Locate the machine in a well-ventilated room.

ATTENTION

Une quantité d'ozone négligable est dégagée pendant le fonctionnement de l'appareil quand celui-ci est utilisé normalement.

Cependant, une odeur désagréable peut être ressentie dans les pièces dont l'aération est insuffisante et lorsque une utilisation prolongée de l'appareil est effectuée. Pour avoir la certitude de travailler dans un environnement réunissant des conditions de confort, santé et de sécurité, il est préférable de bien aérer la pièce ou se trouve l'appareil.

→ Placer l'appareil dans une pièce largement ventilée.


Acoustic noise

For European users

Maschinenlärminformations-Verordnung 3. GPSGV: Der höchste Schalldruckpegel beträgt 70 dB(A) oder weniger gemäss EN ISO 7779.

1.3 Energy Star®

Energy Star® partner



As an Energy Star® partner, we have determined that this machine meets the Energy Star® guidelines for energy efficiency.

What is an Energy Star® product?

An Energy Star® product has a special feature that allows it to automatically switch to a “low-power mode” after a period of inactivity. An Energy Star® product uses energy more efficiently, saves you money on utility bills and helps protect the environment.

1.4 Trademarks and registered trademarks

KONICA MINOLTA, KONICA MINOLTA Logo, and The essentials of imaging are registered trademarks or trademarks of KONICA MINOLTA HOLDINGS, INC.

PageScope and bizhub are registered trademarks or trademarks of KONICA MINOLTA BUSINESS TECHNOLOGIES, INC.

Netscape Communications, the Netscape Communications logo, Netscape Navigator, Netscape Communicator, and Netscape are trademarks of Netscape Communications Corporation.

PageScope Box Operator:

This software is based in part on the work of the Independent JPEG Group.

Compact-VJE

Copyright 1986-2003 VACS Corp.

1.5 Explanation of manual conventions

The marks and text formats used in this manual are described below.

Safety advices



DANGER

Failure to observe instructions highlighted in this manner may result in fatal or critical injuries in fact of electrical power.

→ Observe all dangers in order to prevent injuries.



WARNING

Failure to observe instructions highlighted in this manner may result in serious injuries or property damage.

→ Observe all warnings in order to prevent injuries and to ensure safe use of the copier.



CAUTION

Failure to observe instructions highlighted in this manner may result in slight injuries or property damage.

→ Observe all cautions in order to prevent injuries and to ensure safe use of the copier.

Sequence of action

1 The number 1 as formatted here indicates the first step of a sequence of actions.

2 Subsequent numbers as formatted here indicate subsequent steps of a sequence of actions.

? Text formatted in this style provides additional assistance.

→ Text formatted in this style describes the action that will ensure the desired results are achieved.

An illustration inserted here shows what operations must be performed.

Tips



Note

Text highlighted in this manner contains useful information and tips to ensure safe use of the copier.



Reminder

Text highlighted in this manner contains information that should be reminded.



Detail

Text highlighted in this manner contains references for more detailed information.

Special text markings

[Copy] key

The names of keys on the control panel are written as shown above.

MACHINE SETTING


Display texts are written as shown above.

1.6 Explanation of basic concepts and symbols

The use of words and symbols in this manual are explained below.

Paper feeding

During printing, paper is supplied from the right side of the copier and fed into the copy tray on top with the printed surface of the page facing down. The paper feed direction is shown by the arrows in the diagram below.




Width and length

Whenever paper dimensions are mentioned in this manual, the first value always refers to the width of the paper (shown as “A” in the illustration) and the second to the length (shown as “B”).

A: Width

B: Length





Precaution

2 Precaution

Observe the following precautions to maintain the machine in its best possible condition.

2.1 Installation precautions

Installation site

To ensure utmost safety and prevent possible malfunctions, install the machine in a location that meets the following requirements:

- A location away from curtains, etc. that may catch fire and burn easily
- A location that is not exposed to water or other liquids
- A location free from direct sunlight
- A location out of the direct airflow of an air conditioner or heater, and not exposed to extremely high or low temperatures
- A well-ventilated location
- A location that is not exposed to high humidity
- A location that is not extremely dusty
- A location not subjected to undue vibrations
- A stable and level location
- A location where ammonia or other organic gases are not generated
- A location that does not put the operator in the direct airflow of exhaust from the machine
- A location that is not near any kind of heating devices

Power source


The power source requirements are as follows.

- Voltage fluctuation:
AC 110 V - 127 V -10%, +6%, or AC 220 V - 240 V \pm 10%
- Frequency fluctuation:
Within \pm 2.5 Hz

Use a power source with as few voltage or frequency fluctuations as possible.

Space requirements

To ensure easy machine operation, supply replacement, and maintenance, adhere to the recommended space requirements detailed below.



Note

In order to enable easy machine maintenance and replacement of consumables, maintain an adequate amount of space around the machine.

When lifting the machine, be sure to grab the handles on the left and right sides from the rear of the machine. If the machine is lifted from its front, it may become unbalanced and fall.

2.2 Operation precautions

Operating environment

The environmental requirements for correct operation of the machine are as follows:

- Temperature:
10°C to 30°C (50°F to 86°F) with fluctuations of no more than 10°C (18°F) within an hour
- Humidity:
15% to 85% with fluctuations of no more than 20% within an hour

Proper use

To ensure the optimum performance of the machine, follow the precautions listed below:

- Never place heavy objects on the original glass or subject it to shocks.
- Never open any machine doors or turn off the machine while it is making copies/printing, as a paper misfeed could result.
- Never bring any magnetized object, or use flammable sprays or liquids, near the machine.
- Always make sure that the power plug is completely plugged into the electrical outlet.
- Always make sure that the machine's power plug is visible and not hidden by the machine.
- Always unplug the machine from the electrical outlet if the machine is not to be used for a long period of time.
- Always provide good ventilation when making a large number of continuous copies/printed pages.

WARNING

A negligible amount of ozone is generated during normal operation of this machine. An unpleasant odor may, however, be detected in poorly ventilated rooms during extensive machine operations.

- For a comfortable operating environment, it is recommended that the room be well ventilated.
-

WARNING

The area around the fusing unit is extremely hot.

- In order to reduce the risk of burns, do not touch any area other than those indicated in the manual. Be especially careful not to touch parts marked with warning labels, and their surrounding areas.
-

Transporting the machine

If you need to transport the machine over a long distance, consult your service representative.

Care of machine supplies

Use the following precautions when handling the machine supplies (toner, paper, etc.).

- Store the supplies in a location that meets the following requirements:
 - Free from direct sunlight
 - Away from any heating apparatus
 - Not subjected to high humidity
 - Not extremely dusty
- Paper that has been removed from its wrapper but not loaded in the machine should be stored in a sealed plastic bag in a cool, dark place.
- Use only toner that has been manufactured specifically for this machine. Never use other types of toner.
- Keep all supplies out of the reach of children.



WARNING

Be careful not to spill toner inside the machine or get toner on your clothes or hands.

- If your hands become soiled with toner, immediately wash them with soap and water.
-

2.3 Legal restrictions on copying

Certain types of documents must not be copied with the purpose or intent to pass copies of such documents off as the originals.

The following is not a complete list, but is meant to be used as a guide to responsible copying.

Financial instruments

- Personal checks
- Travelers checks
- Money orders
- Certificates of deposit
- Bonds or other certificates of indebtedness
- Stock certificates

Legal documents

- Food stamps
- Postage stamps (canceled or uncanceled)
- Checks or drafts drawn by government agencies
- Internal revenue stamps (canceled or uncanceled)
- Passports
- Immigration papers
- Motor vehicle licenses and titles
- House and property titles and deeds

General

- Identification cards, badges, or insignias
- Copyrighted works without permission of the copyright owner

In addition, it is prohibited under any circumstances to copy domestic or foreign currencies, or works of art, without permission of the copyright owner.

When in doubt about the nature of a document, consult with legal counsel.




A large, bold, black number '3' is centered within a gray rectangular background. The number is slightly offset to the right within the rectangle.

**Before making copies or
faxing**



3 Before making copies or faxing

3.1 Available features

The main copy settings available with this machine are listed below. For details on their operation, refer to the pages indicated.


Copy settings	Example
<p>Copies</p> <ul style="list-style-type: none"> • 1-sided copies (p. 4-3) • 2in1 copies (p. 4-14) 	
<p>Zoom ratio</p> <ul style="list-style-type: none"> • Reduced/Full size/Enlarged (p. 4-10) 	
<p>Finishing</p> <ul style="list-style-type: none"> • Sort (p. 4-15) 	

3.2 Components and their functions

Components and their functions	Illustration
<p>Main unit bizhub 160f</p>	
<p>Paper feed unit PF-501 (option) Capable of holding up to 500 sheets of paper.</p>	
<p>Expanded memory unit EM-101 (option) Increases the machine's memory (32 MB Memory). By increasing the machine's memory, more pages can be scanned.</p>	
<p>Mechanical counter MC-502 (option) Displays the total number of pages printed until the current time.</p>	
<p>Network interface card NC-501 (option) By installing the Network Interface Card NC-501 into this machine, network printing from Windows or a NetWare network environment is possible.</p>	
<p>Scanner Unit SU-502 (option) By installing the Scanner Unit SU-502 (option) together with the Network Interface Card NC-501, the network scanning and Internet faxing functions can be performed.</p>	


3.3 Parts names and their functions

Main unit




No.	Part name	Description
1	Automatic document feeder	Automatically feeds one document sheet at a time for scanning.
2	Original glass	Place your original on this glass to allow the machine to scan it. The original is to be placed face down. (p. 3-35)
3	Front cover	Open when replacing the toner cartridge or drum cartridge, or clearing a paper misfeed. (p. 8-6)
4	Tray 1	Holds up to 250 sheets of paper and easily adjusts to different paper sizes. Special paper can be used. (p. 3-26)

No.	Part name	Description
5	Bypass tray	Use for manual feeding of paper. Holds up to 10 sheets of paper. Special paper can be used. (p. 3-31)
6	Tray 1 door	If legal-size paper is installed, open this door.
7	Copy tray	Holds copies fed out face down from the machine. The copy tray can be adjusted to one of three angles. Adjust the copy tray to the angle appropriate for its application. (p. 3-9)
8	Control panel	Use to start a copy cycle and make necessary settings. (p. 3-12)
9	Exposure lamp	This lamp irradiates the document when it is scanned. The time until the exposure lamp goes off can be specified. For details on specifying the setting, refer to "Selecting the MACHINE SETTING menu" on page 7-6.
10	Original scales	Use to align the original. (p. 3-35)
11	Power switch	Use to turn the machine on and off. (p. 3-18)
12	External telephone jack (TEL PORT)	Used for connecting a line to a telephone.
13	Telephone line jack for line 1 (LINE PORT 1)	Used for connecting to a standard telephone line.
14	USB port	For more details, refer to the user's guide for the printer controller.
15	Parallel port	For more details, refer to the user's guide for the printer controller.
16	Fuser cover	Open when clearing the misfed paper.

Automatic document feeder

No.	Part name	Description
1	Document feeder tray	Load the originals to be copied face up on this tray. Up to 50 document sheets can be loaded at one time. (p. 3-34)
2	Document feeder cover (doc. feed cover)	Open when clearing an original that has been misfeed. (p. 8-22)
3	Document guide plate	Slide the guide plate to the size of the originals. (p. 3-34)
4	Document exit tray	Receives originals which have been scanned by the machine.


Inside the machine

No.	Part name	Description
1	Imaging cartridge	Generates the copy image. The imaging cartridge is constructed of both the drum cartridge and the toner cartridge set into place.

Adjusting the angle of the copy tray


The copy tray can be adjusted to one of three angles. Adjust the tray to the angle appropriate for the desired application.

1. Normal operation (standard position)
2. When back curled paper is fed out
3. When clearing a paper misfeed or replacing the drum cartridge or toner cartridge




Note

Adjust the tray extension and paper stopper to fit the size of the paper.



Options



Paper Feed Unit PF-501

No.	Part name	Description
1	Tray2	Holds up to 500 sheets of paper. (p. 3-32)

Mechanical Counter MC-502


No.	Part name	Description
2	Counter	Displays the total number of pages printed until the current time.

Network Interface Card NC-501

No.	Part name	Description
3	Network connector (10 Base-T/100 Base TX)	By installing the Network Interface Card NC-501 into this machine, network printing from Windows or a NetWare network environment is possible.

3.4 Control panel


Names of control panel parts and their functions



No.	Part name	Description
1	[Utility] key	Press to enter utility mode. (p. 7-3)
2	[Printer] key	Press to enter printer mode. For details, refer to the user's guide for the printer controller.
3	Error lamp	The indicator lights up in orange if an error or malfunction occurs. (p. 8-3)
4	Display	Shows the number of copies to be made, the zoom ratio, and other setting data.
5	[No/C] key	<ul style="list-style-type: none"> Press to reset the number of copies to "1". Press to clear the various settings. Press to return to the previous screen. Press to specify the various settings. Erases the entered numbers and letters.
6	[Yes] key	<ul style="list-style-type: none"> Press to validate the setting just made. Press to specify the various settings.
7	10-key pad	<ul style="list-style-type: none"> Use to enter the number of copies to be made and any other numeric data. Used to enter text such as a name. In the fax mode, use the [*] key for tone transmission (with pulse dialing) and use the [#] key for accessing an outside line.


No.	Part name	Description
8	[Scan] key	Press to enter scan mode. The indicator lights up in green to indicate that the machine is in scan mode. (Available only when the Scanner Unit SU-502 is installed.)
9	[Fax] key	Press to enter fax mode. The indicator lights up in green to indicate that the machine is in fax mode.
10	[Copy] key	Press to enter copy mode. The indicator lights up in green to indicate that the machine is in copy mode.
11	[Stop] key	<ul style="list-style-type: none"> • Press to stop a print cycle. • Press to stop a scanning sequence. • Stops the fax transmission or reception. • The indicator flashes in orange when the machine is paused or while copying.
12	[Panel reset] key	Press to reset all copy functions and settings to their defaults.
13	[123/ABC] key	Press to switch the 10-key pad between typing in numbers and typing in letters.
14	[Start] key	<ul style="list-style-type: none"> • Press to start a scanning or print cycle. • Starts a fax transmission. • Press to specify the various settings. • The indicator lights up in green when the machine can accept copy jobs.
15	[▲] [▼] key	<ul style="list-style-type: none"> • Press to change the zoom ratio in the range between $\times 0.25$ and $\times 4.00$ in $\times 0.01$ increments. • Press to scan through the various settings and information, in order. • Press to specify the various settings.
16	[Zoom] key	Press to select a zoom ratio from among those fixed ratios available as standard.
17	[Paper] key	Press to select the paper tray that contains the desired paper.
18	[◀] [▶] key	<ul style="list-style-type: none"> • Press to adjust the image density. • Press to specify the various settings.
19	[Auto/Photo] key	Press to change the image density mode.
20	[Sort] key	Press to select the sort function.
21	[2in1] key	Press to select the 2in1 function.
22	[Status] key	Press to view the counters and transmission results. In addition, the list of settings specified for each function and the reports can be printed. (p. 3-40)
23	Memory TX lamp	Lights up when the memory transmission function is selected.
24	Auto RX lamp	Lights up when the automatic reception function is selected.
25	[Resolution] key	Used to select the image quality (transmission resolution).
26	[Speaker] key	Press to answer the call. Press again to hang up.
27	[Phone book] key	Used to display the information programmed for one-touch dialing, group dialing and speed dialing.
28	[Redial/Pause] key	<ul style="list-style-type: none"> • Redials the last number called. • While dialing, used to generate a pause when transferring from an internal to an external line or receiving information services.

No.	Part name	Description
29	[Speed dial] key	Used to dial previously programmed fax numbers represented by 3-digit numbers.
30	[Function] key	<p>Used to select a function.</p> <ul style="list-style-type: none"> • BROADCAST (broadcast transmission), TIMER TX (timer transmission), MAILBOX TX (mailbox transmission), PRINT MAILBOX RX (retrieve mailbox faxes), POLLING TX (polling transmission), POLLING RX (polling reception), RELAY INITIATE (relay initiation transmission), CANCEL RESERV. (cancel queued job), TX MODE (transmission mode), INTERNET FAX RX (with the Scanner Unit SU-502 installed) <p>For details, refer to "Fax transmission/Reception methods" on page 6-3.</p>
31	One-touch dial keys	Used to dial previously programmed fax numbers.

Display indications – in copy mode











No.	Display indication	Description
1	Document type	Displays the document type currently specified for the image density.
2	Zoom ratio	Displays the currently specified zoom ratio.
3	Number of copies	Displays the currently specified number of copy pages and number of copy sets.
4	Image density	Displays the currently specified image density.
5	Paper	Displays the currently selected paper tray, paper size and paper type.

Display indications – in fax mode



No.	Display indication	Description
1	Messages	Displays messages such as operating instructions.
2	Mode or function name	<ul style="list-style-type: none"> Displays the current menu, function or settings. Error messages are displayed when errors occur.
3	Time	The current time is displayed during standby.
4	Resolution	The setting resolution is displayed during standby.
5	Symbol	Indicates the currently selected mode or function settings.
6	Memory	The remaining memory is displayed during standby.

Symbol list


Symbol		Description
	Bypass tray	Paper is loaded in the bypass tray.
	Custom paper size	The paper setting for the bypass tray is a custom paper size.
	Dialing	A fax number is being dialed.
	Ringing	The machine is being called.
	Sending	The document is being sent.
	Receiving	A document is being received.
	In standby for timer transmission	A document is queued for timer transmission.
	In standby for polling transmission	A document is queued for polling transmission.
	In standby for mailbox reception	A document is queued for mailbox reception.
	In standby for memory reception or polling reception	A document is queued for memory reception or polling reception.

3.5 Turning the machine on/off

Turning the machine on

- Press the | (on) side of the power switch.

When the machine is turned on, the [Start] key indicator lights up in orange to indicate that the machine is ready to begin printing.



Note

When the [Start] key indicator lights up in orange, the machine can be set for the auto print start function by loading a document into the automatic document feeder or by placing a document on the original glass, and pressing the [Start] key.

Pressing the [Start] key at this time will not immediately start the print cycle. You will have to wait for less than 25 seconds (at an ambient temperature of 23°C (73.4°F))



Detail


The machine automatically enters the energy save mode 15 min after the last operation is performed. The time until the machine enters energy save mode can be specified. For details, refer to "Specifying ENERGY SAVE MODE" on page 7-8.


Turning the machine off

CAUTION

Incorrect handling can cause paper misfeed or lost of data.


- Do not turn off the machine while a print cycle is being performed, as a paper misfeed will result. Before attempting to turn off the machine, always be sure that the current print cycle has been completed.
- Do not turn off the machine while it is scanning or sending or receiving data, otherwise all scanned data or transmission data will be deleted.

- Press the  (off) side of the power switch.
Turning off the machine will initialize all settings except those for previously programmed jobs and for the utility mode.



3.6 Initial mode

When the machine is turned on, the initial mode screen appears in the display of the control panel. The initial mode screen appears at the beginning of all operations.



Factory default settings are:

- Number of copies 1
- Image density TEXT Auto
- Zoom ratio 100% (full size)
- Paper Tray 1
- Finishing Non-sort

The default settings can be customized from the utility mode.



Detail

For details, refer to "Using the utility mode" on page 7-3.

3.7 Useful functions

Panel resetting

Press the [Panel reset] key to return all modes and functions (zoom ratio, number of copies, etc.) to their defaults. All selected settings are canceled.

The [Panel reset] key comes in handy for canceling all selected settings at one time.

To avoid accidentally using settings from the previous copy job, press the [Panel reset] key to return all functions and settings to their defaults before specifying any settings for your current job.

Auto panel reset

Even if the [Panel reset] key is not pressed, the machine automatically resets all functions and settings to their defaults 1 min after a print cycle has been completed or a key operation is performed.

The length of time before the machine automatically resets itself can be set between 1 min and 5 min in addition to 30 seconds. The auto panel reset function can even be disabled.



Detail

For details, refer to "Specifying AUTO PANEL RESET" on page 7-7.

Energy save mode

Instead of turning off the machine, it can be set into a standby state (energy save mode).

If the machine is not used for a set length of time, it will automatically enter the energy save mode. The default length of time is 15 min.

To cancel the energy save mode, press any key on the control panel.

The length of time before the machine enters the energy save mode can be set between 1 min and 240 min.



Detail

For details, refer to "Specifying ENERGY SAVE MODE" on page 7-8.

Auto print start

If a document is loaded and the [Start] key is pressed during the period after the machine has been turned on but before it is ready to make print, the machine will automatically start the print cycle as soon as it completes the warm-up cycle.

Auto tray switching

If the tray runs out of paper while printing, the machine will automatically switch to a different paper source and continue printing provided that the new tray contains paper of the same type and size in the same orientation.

If the optional paper feed cassette is installed, a maximum of 750 pages can be continuously printed.

Auto tray switching can be disabled.

Tray1 → Tray2 (Paper Feed Unit)

Tray2 (Paper Feed Unit) → Tray1



Detail

For details, refer to "Paper source settings" on page 7-13.

3.8 Entering Text

When specifying the user name or programming one-touch dial keys with the recipient name, letters, accented characters, numbers and symbols can be entered.

Key operation

The 10-key pad will be used to enter numbers and letters, symbols.

List of characters

List of characters available with each key of the 10-key pad

10-key pad	Available characters*
1	. (period) @ _ (underscore) - (hyphen) 1
2	ABC2abcÄäÅåÆæÀÀÇç
3	DEF3defÉéè
4	GHI4ghíîï
5	JKL5jkl
6	MNO6mnoÑñÖöØøò
7	PQRS7pqrsß
8	TUV8tuvÜüúú
9	WXYZ9wxyz
*	+&/*=!?()% [] ^ ' ' { } [] \$, ; < > " ' £
0	(space) 0
#	#

* To switch the input mode of the 10-key pad between numbers and letters, press the [123/ABC] key.

Changing Input Mode

Each press of the [123/ABC] key switches the input mode between numbers and letters.


[1]: Numbers can be typed in.

[A]: Letters can be typed in.

Inputting Example

To enter the name “NJ Office”

The cursor () flashes alternately with the character at its current location.



Correcting text and input precautions:

- To erase all entered text, press the [Panel reset] key.
- To delete only part of the entered text, use the [◀] and [▶] keys to move the cursor () to the character that you wish to delete, and then press the [No/C] key.
- To change an entered character, use the [◀] and [▶] keys to move the cursor () below the character that you wish to change, and then press the [No/C] key. Next, enter the new character. The character at the cursor's position is replaced with the new character.
- If the same 10-key pad is needed to enter two characters in a row, press the [▶] key after selecting the first character. (Refer to the above example.)
- To enter a space, press 10-key pad [0].

3.9 Copy paper

Paper specifications

The following table specifies the type and size of paper to be used with each tray together with its capacity.

Tray 1	Specifications						
Paper type	<ul style="list-style-type: none"> Plain paper, recycled paper (60 g/m² to 90 g/m²) Exclusive paper: card (91 g/m² to 163 g/m²), OHP transparencies, envelopes 						
Paper size	<ul style="list-style-type: none"> A4 L, B5 L, A5 L, 16K L, Legal L, Letter L, Half Letter L, FLS (210 mm × 330 mm) Custom size Paper width: 90 mm to 216 mm Paper length: 140 mm to 356 mm 						
Capacity	<ul style="list-style-type: none"> Plain paper, recycled paper: 250 sheets (80 g/m²) Exclusive paper <table style="margin-left: 20px;"> <tr> <td>card:</td> <td>10 sheets</td> </tr> <tr> <td>OHP transparencies</td> <td>5 sheets</td> </tr> <tr> <td>envelopes</td> <td>1 sheet</td> </tr> </table> 	card:	10 sheets	OHP transparencies	5 sheets	envelopes	1 sheet
card:	10 sheets						
OHP transparencies	5 sheets						
envelopes	1 sheet						

Tray 2	Specifications
Paper type	Plain paper, recycled paper (60 g/m ² to 90 g/m ²)
Paper size	A4 L, Letter L*
Capacity	500 sheets (80 g/m ²)

* Two tray types are available for tray 2. Select the desired tray type at the time of purchase.

Bypass tray	Specifications						
Paper type	<ul style="list-style-type: none"> Plain paper, recycled paper (60 g/m² to 90 g/m²) Exclusive paper: card (91 g/m² to 163 g/m²), OHP transparencies, envelopes, label sheets 						
Paper size	<ul style="list-style-type: none"> A4 L, B5 L, A5 L, 16K L, Legal L, Letter L, Half Letter L, FLS (210 mm × 330 mm) Custom size Paper width: 90 mm to 216 mm, Paper length: 140 mm to 356 mm 						
Capacity	<ul style="list-style-type: none"> Plain paper, recycled paper: 10 sheets (80 g/m²) Exclusive paper <table style="margin-left: 20px;"> <tr> <td>card:</td> <td>1 sheet</td> </tr> <tr> <td>OHP transparencies</td> <td>1 sheet</td> </tr> <tr> <td>envelopes</td> <td>1 sheet</td> </tr> </table> 	card:	1 sheet	OHP transparencies	1 sheet	envelopes	1 sheet
card:	1 sheet						
OHP transparencies	1 sheet						
envelopes	1 sheet						

L: Lengthwise

Precautions for loading paper

Please adhere to the following precautions:

- Be sure to observe the paper specifications (paper type, paper size, and capacity) for each tray, otherwise a paper misfeed could result.
- When paper is loaded into the bypass tray, a message appears, indicating that the paper size be specified. Specify the size and type of paper that is loaded. Paper loaded into the bypass tray is given priority during feeding.
- The size of FLS is preset to 330 mm × 210 mm. To change the FLS size, contact a service representative.





Unsuitable paper



The following types of paper should not be used, otherwise decreased print quality, paper misfeeds or damage to the machine may occur.

- Overhead projector transparencies that have already been fed through the machine
Even if the transparency is still blank, do not reuse it.
- Paper that has been printed on by a heat-transfer printer or an inkjet printer
- Paper that is either extremely thick or extremely thin
- Folded, curled, wrinkled, or torn paper
- Paper that has been left unwrapped for a long period of time
- Damp paper
- Perforated paper or paper with punched holes
- Extremely smooth or extremely rough paper, or paper with an uneven surface
- Paper that has been treated, such as carbon-backed, heat-sensitive or pressure-sensitive paper
- Paper that has been decorated with foil or embossing
- Paper of a non-standard shape (not rectangular)
- Paper that is bound with glue, staples or paper clips
- Paper with labels attached
- Paper with ribbons, hooks, buttons, etc. attached

Loading paper

While loading paper, be sure to observe the following precautions.

Precautions	Illustration
<p>If the paper is curled, flatten it before loading it.</p>	
<p>Do not load so much paper that the top of the stack is higher than the ▼ mark or exceeds the specified number of sheets.</p>	
<p>Push the paper guides firmly up against the edges of the paper.</p>	
<p>When loading additional paper, remove any paper remaining in the drawer, place it on top of the new paper, and then align the paper in the stack well before loading it into the drawer.</p>	


Precautions	Illustration
<p>When loading envelopes, load them with the flap facing down, as shown in the illustration at the right.</p> <p>Before loading envelopes, press them down to make sure that all air is removed, and make sure that the folds of the flaps are firmly pressed, otherwise the envelopes may become wrinkled or a paper misfeed may occur.</p> <p>Only 1 envelope at a time can be loaded in tray 1 and the bypass tray.</p>	<p data-bbox="706 185 820 209">Bypass tray</p>  <p data-bbox="706 547 766 571">Tray 1</p> 

**Note**


We recommend replenishing the paper only after all of the paper in the drawer has been used.

Loading paper into tray 1


- 1 Remove the bypass tray.



- 2 Load the paper into the tray so that the front side of the paper (the side facing up when the package was unwrapped) faces up.




- 3 Slide the paper guides against the edges of the paper. If legal-size paper is installed, open the door of tray 1.



- 4 Attach the bypass tray in its original position.

When legal-size paper is installed




Detail


If paper with a different size or type is loaded, various settings must be specified. If the settings are not correctly specified, paper size error may occur. For details, refer to "Specifying TRAY SETTING" on page 7-16.

Loading paper into the bypass tray

- 1 Load the paper so that the front side of the paper (the side facing up when the package was unwrapped) faces up.




- 2 Slide the paper guides against the edges of the paper.

**Detail**


When paper is loaded into the bypass tray, the paper size and type must be specified, otherwise paper size error may occur. For details, refer to "Specifying the size and type of manually fed paper" on page 4-6.

Loading paper into tray 2 (option)


- 1 Pull out the drawer for tray 2.



- 2 Remove the drawer cover, and then press down on the paper-lifting plate until it locks into place.



- 3 Load the paper into the drawer so that the front side of the paper (the side facing up when the package was unwrapped) faces up.



- 4 Attach the drawer cover, and then return the drawer for tray 2 to its original position.

3.10 Loading originals

Two ways of loading the original

The original may be loaded in the automatic document feeder or placed directly on the original glass. Choose the appropriate method according to the type of the original.

Specific types of originals

Original loading	Original type	Original size
Automatic document feeder	Sheet originals Weight of originals: 35 g/m ² to 128 g/m ²	A4 L, B5 L, A5 L, Legal L, Letter L, Half Letter L <ul style="list-style-type: none"> • Original width: 138 mm to 216 mm • Original length: 130 mm to 356 mm
Original glass	Max. weight of sheet originals, books, or three-dimensional objects: 2 kg	Maximum: Legal

L: Lengthwise

Loading originals in the automatic document feeder

The automatic document feeder automatically feeds originals one page after another so that the machine can scan the data on each page. After the machine finishes scanning the data, the automatic document feeder ejects the page into the exit tray. To ensure the best possible performance of the automatic document feeder, use only originals of the specified type.

Precautions for loading paper into the automatic document feeder

The following types of originals are not suitable for use in the automatic document feeder, as a misfeed or damaged original could result. Place such types of originals on the original glass.

- Typing paper, paraffin paper, and other thin paper
- Cards
- Originals larger than Legal L or smaller than Half Letter
- OHP transparencies, translucent paper
- Wrinkled, dog-eared, curled, or torn originals
- Clipped or stapled originals
- Coated originals such as carbon-backed paper
- Up to 19 A4-size document pages can be scanned and stored in the memory at one time. However, if the optional expansion memory is installed, up to 180 scanned pages can be stored.


Loading originals into the automatic document feeder

CAUTION


Paper jam in fact of overloaded automatic document feeder.

- A maximum of 50 document pages can be loaded.
- Do not load so many pages that the top of the stack is higher than the ▼ mark.
- Be sure to adjust the document guides so that they are against the edges of the document, otherwise the document may not be fed in straight.

- 1 Place the stack of originals face up on the automatic document feeder tray.




- 2 Slide the front adjustable document guide plate to the size of the originals.



- 3 Specify the desired copy settings. For details, refer to “Making a basic copy” on page 4-3 and “Basic Faxing” on page 5-15.

- 4 Press the [Start] key. This will start the print cycle.



Placing the original on the original glass

The method for positioning the original differs depending on the type of original being used.

Care should be taken when positioning the following types of originals.

- ***An original of a non-standard size:***
The document size cannot be detected automatically. Press the [Paper] key or the [Zoom] key, and then select the desired paper size (p. 4-5) or zoom ratio (p. 4-10).
- ***A highly transparent original (OHP transparencies, translucent paper, etc.):***
Place a blank sheet of paper of the same size over the original.
- ***A book or other three-dimensional object:***
Let the machine scan the contents of the original with the original cover or the automatic document feeder raised. Do not attempt to push the original glass with excessive force, as a malfunction could result. The maximum load resistance of the original glass is 2 kg.



CAUTION


Bright light can blind your eyes.

- While scanning a thick book or other three-dimensional object with the automatic document feeder open, do not look directly at the bright light that may shine through the original glass. Although the light that shines through the original glass is bright, it is not a laser beam and, therefore, is not as dangerous.
-

Positioning a sheet original


Use the following procedure to position plain paper or an original that is not suitable for use in the automatic document feeder.

- 1 Raise the automatic document feeder.



- 2 Place the original face down on the original glass.

- 3 Position the original on the original glass so that the corner of the original aligns with the arrow in the upper-left corner of the original scales.



- 4 Gently lower the automatic document feeder.

- 5 Specify the desired copy settings. For details, refer to “Making a basic copy” on page 4-3 and “Basic Faxing” on page 5-15.


- 6 Press the [Start] key.

This will start the print cycle.

Positioning highly transparent originals


When making a copy from OHP transparencies, translucent paper, or other highly transparent original, position the original as detailed below.

- 1 Raise the automatic document feeder.




- 2 Place the original face down on the original glass.

- 3 Position the original on the original glass so that the corner of the original aligns with the arrow in the upper-left corner of the original scales.



- 4 Place a blank sheet of paper of the same size over the original.

- 5 Gently lower the automatic document feeder.



- 6 Specify the desired copy settings. For details, refer to “Making a basic copy” on page 4-3 and “Basic Faxing” on page 5-15.

- 7 Press the [Start] key.
This will start the print cycle.

Positioning books

When copying an open book or magazine, position the original as detailed below.


- 1 Raise the automatic document feeder.

WARNING


Broken original glass by incorrect handling.

- Do not place books weighing more than 2 kg on the original glass. In addition, do not press down extremely hard on the original, otherwise the machine may be damaged.

- 2 Place the original face down on the original glass.



- 3 Position the original on the original glass so that the corner of the original aligns with the arrow in the upper-left corner of the original scales.



CAUTION

Bright light can blend your eyes.

- While scanning a thick book or other three-dimensional object with the automatic document feeder open, do not look directly at the bright light that may shine through the original glass. Although the light that shines through the original glass is bright, it is not a laser beam and, therefore, is not as dangerous.

- 4 Gently lower the automatic document feeder or original cover.

- 5 Specify the desired copy settings.
For details, refer to “Making a basic copy” on page 4-3 and “Basic Faxing” on page 5-15.
- 6 Press the [Start] key.
This will start the print cycle.

3.11 Checking the machine status


The total number of pages copied and scanned since this machine was installed can be checked.

Menu	Item	Description
TOTAL PAGE	TOTAL COUNT	Displays the total number of pages copied since this machine was installed.
	TOTAL SCAN	Displays the total number of pages scanned since this machine was installed. However, the scanned number of pages in copy are not included.
	TX PAGES	Displays the total number of pages faxed since this machine was installed.
	RX PAGES	Displays the total number of pages received since this machine was installed.
TX/RX RESULT	TX RESULT REPORT	Displays the transmission result report.
	RX RESULT REPORT	Displays the reception result report.
PRINT REPORT	TX RESULT REPORT	Prints the transmission result report.
	RX RESULT REPORT	Prints the reception result report.
	ACTIVITY REPORT	Prints the transmission/reception result report.
	MEMORY DATA LIST	Prints the list of documents stored in the memory.
	MEMORY IMAGE PRINT	Prints the reduced image of the first page of the document stored in the memory.
	ONE-TOUCH LIST	Prints the recipients programmed in the one-touch dial keys.
	SPEED DIAL LIST	Prints the recipients programmed for the speed dial numbers.
	KEY SETTING LIST	Prints the settings specified for one-touch dial keys.
	MACHINE STATUS	Prints the current machine status.
	CONFIGURATION PAGE	Prints the current machine configuration.


3.11.1 TOTAL PAGE

Checking a TOTAL PAGE count

- 1 Press the [Status] key.




- 2 Press the [Yes] key.



- 3 Press the [▲] and [▼] keys to check a total page count.


- TOTAL COUNT
- TOTAL SCAN
- TX PAGES
- RX PAGES




3.11.2 TX/RX RESULT

Checking the TX/RX RESULT

- 1 Press the [Status] key 2 times.



- 2 Press the [Yes] key.




- 3 Press the [] and [] keys to display the desired transmission results to check them.

- ? What does TX and RX indicate?
TX indicates sent faxes.
RX indicates received ones.

- ? Do you want to return to the main screen?
 Press the [No/C] key twice while the transmission results are displayed, the main screen appears.

- ? Do you want to print the transmission result report?


Press the [Start] key. After the transmission result report is printed, the main screen appears.




3.11.3 PRINT REPORT

Printing a PRINT REPORT


- 1 Press the [Status] key 3 times.




- 2 Press the [Yes] key.



- 3 Press the [] and [] keys to select the report/list that you wish to print.
– CONFIGURATION PAGE



- 4 Press the [Yes] key.
After the specified report/list is printed, the main screen appears again.



...

Note

The reception/transmission result reports can be checked on screen. For details on viewing the transmission result, refer to "Checking the TX/RX RESULT" on page 3-42.

TX Result report

The document number, recipient name, date sent, starting time of transmission, number of document pages, time required, mode, and transmission result are printed.

SESSION	FUNCTION	No.	DESTINATION STATION	DATE	TIME	PAGE	DURATION	MODE	RESULT
0001	TX	001	AAA NEWYORK 012345678	APR.19	18:00	010	00:02'21"	G3	NG
			NG PAGE:1.3.5.7						

RX Result report

The document number, caller name, date received, starting time of reception, number of pages received, time required, mode, and reception result are printed.

SESSION	FUNCTION	No.	DESTINATION STATION	DATE	TIME	PAGE	DURATION	MODE	RESULT
0001	RX	001	AAA TOKYO 098765432	APR.19	18:00	001	00:02'21"	ECM	NG
			0021:ERROR DURING RX						

Activity report

The operation number, document number, date of operation, starting time of transmission/reception, type of operation (transmission or reception), recipient/caller name, number of pages sent/received, mode, and transmission/reception result are printed.

The machine can also be set to print this report automatically after every 60 transmissions/receptions.

No.	SESSION	DATE	TIME	TX/RX	DESTINATION STATION	PAGE	DURATION	MODE	RESULT
01	0001	APR.19	16:32	TX---	AAA NEWYORK 012345678	006	00:01'16"	ECM	OK
02	0002	APR.19	18:00	---RX	AAA TOKYO 098765432	001	00:02'21"	ECM	NG
03	0002	APR.19	18:00	---RX	AAA TOKYO 098765432	012	00:02'48"	ECM	OK
04	0003	APR.19	19:12	TX---	HEAD OFFICE 024682468	001	00:00'56"	ECM	OK

Memory data list

This is a list of documents stored in the memory and waiting to be sent, and documents specified for timer transmission, batch transmission or polling reception.

The document number, type of operation being performed, time, recipient/caller name, and number of document pages are printed.

Memory image print

A reduced image of the first page of the document stored in the memory and waiting to be sent in addition to the document number, type of operation being performed, recipient/caller name, date, time, and number of document pages are printed.

One-touch list

The recipients programmed in the one-touch dial keys are printed in numerical order of the keys.

OT-NO.	DESTINATION STATION	DESTINATION NUMBER	BATCH TIME	SPEED	SET DATE
OT-01	AAA NEWYORK	012345678		33.6	JAN.20.2001
OT-02	AAA TOKYO	098765432		14.4	JAN.20.2001
OT-03	HEAD OFFICE	024682468	16:00	33.6	FEB.12.2001
OT-04	NJ OFFICE	0P02345678 SUB:#1234		14.4	FEB.12.2001

Speed dial list

The recipients programmed for the speed dial numbers are printed in numerical order.

SP-NO.	DESTINATION STATION	DESTINATION NUMBER	SPEED	SET DATE
SP-001	AMSTERDAM OFFICE	0P09876543	33.6	JAN.20.2001
SP-002	KOREA OFFICE	0P01357913	14.4	JAN.20.2001
SP-003	ABCDEF	024682468	33.6	FEB.12.2001
SP-004	POST OFFICE	0224466880 SUB:#5678	14.4	FEB.12.2001

Key setting list

The group dialing and program dialing settings specified for one-touch dial keys are printed in numerical order of the keys.

Machine status

The current machine settings are printed.

Configuration page

The list of the printer settings is printed.

3.12 Print area


Any part of the image within the area indicated below is not copied.

A margin 4 mm (at full size) from the leading edge of the paper (A)

A margin 4 mm (at full size) from the trailing edge of the paper (B)

A margin 4 mm (at full size) on both sides of the paper (C)

For details on using the copier to print from a computer when the printer controller is installed, refer to the user's guide for the printer controller.





Making copies


4 Making copies

4.1 Basic copies


The following procedure describes how to place an original and make a basic copy of it.

Making a basic copy


- 1 Position the original.
For details, refer to “Loading originals” on page 3-33.




- 2 Select the paper tray.
For details, refer to “Paper selection” on page 4-5.




- 3 Specify the zoom ratio.
For details, refer to “Zoom ratio” on page 4-10.



- 4 Specify the image density.
For details, refer to “Image Density”
on page 4-12.




- 5 Using the 10-key pad, enter the
number of copies to be made. Any
number from 1 to 99 can be entered.



- 6 Press the [Start] key.
This will start the copy cycle.

- To stop the copy cycle in mid-operation, press the [Stop] key.
- To cancel the copy job, press the [No/C] key or the [Panel reset] key.
- To restart the copy cycle, press the [Start] key.



4.2 Paper selection

The tray containing the paper you want to use can be manually selected, if an optional paper feed unit is installed.


When the desired paper is loaded into the bypass tray and the paper size and type are specified, paper loaded into the bypass tray is given priority during feeding.

Selecting the paper tray manually

Before selecting the paper tray manually:


- ✓ If paper is loaded into the bypass tray, first remove it.
- ✓ If tray 1 is selected, the paper size and paper type must first be specified. For details, refer to “Selecting the PAPER SOURCE SETUP menu” on page 7-13.

- 1 Position the original.
For details, refer to “Loading originals” on page 3-33.
- 2 Press the [Paper] key until the tray loaded with the desired paper is selected.
- 3 Specify the desired copy settings.
For details, refer to “Making a basic copy” on page 4-3.
- 4 Using the 10-key pad, enter the number of copies to be made, and then press the [Start] key.
This will start the copy cycle.




Specifying the size and type of manually fed paper


- 1 Position the original.
For details, refer to “Loading originals” on page 3-33.
- 2 Load paper into the bypass tray.
For details, refer to “Loading paper into the bypass tray” on page 3-31.
 - ? How many paper can be loaded into the bypass tray
 - The bypass tray can be loaded with a maximum of 1 envelope, 1 OHP transparency, 1 card, or 10 sheets of plain paper.
- 3 The message shown at the right appears. Press the [No/C] key.



- 4 Press the [◀] and [▶] keys until the desired paper type is selected.
 - ? Do you want to copy on OHP transparencies?
 - The only paper sizes that can be loaded are A4 ◻ (Lengthwise) and Letter ◻ (Lengthwise).
 - ? Do you want to return to the previous message?
 - Press the [No/C] key.




- 5 Press the [Yes] key.



- 6 Press the [◀] and [▶] keys to select a standard size of paper that is loaded.
or
press the [▼] key to enter a custom size of paper that is loaded.


- ? Do you want to use a standard paper size (A5, B5, A4 ...)?
→ Select a standard paper size.
→ Continue with step 10.
- ? Do you want to enter a custom paper size?
→ Select **CUSTOM**.
→ Perform steps 7 through 10.
- ? Do you want to return to the previous message?
→ Press the [No/C] key.




- 7 Using the 10-key pad, enter the width (X) of the paper. The width can range from 90 mm to 216 mm.

? Do you want to clear the entered value?


→ Press the [No/C] key



- 8 Press the [Yes] key.




- 9** Using the 10-key pad, enter the length (Y) of the paper. The length can range from 140 mm to 356 mm.



- 10** Press the [Yes] key.

- 11** Specify the desired copy settings.
For details, refer to "Making a basic copy" on page 4-3.



- 12** Using the 10-key pad, enter the number of copies to be made.

- ?** Do you want to change the number of copies to be made?
→ Remove the paper from the bypass tray and then reload it.
→ Repeat steps 11 and 12.

- 13** Press the [Start] key
This will start the copy cycle.

4.3 Zoom ratio


By specifying a zoom ratio, the copy can be enlarged or reduced.

Zoom ratio settings

Zoom ratio settings	Description
Fixed ratios	<p>The following optimum zoom ratios are available for making copies from commonly used original sizes to standard paper sizes:</p> <ul style="list-style-type: none"> • × 0.25 • × 0.50 • × 0.70 (A4 → A5) • × 0.81 (B5 → A5) • × 1.15 (B5 → A4) • × 1.41 (A5 → A4) • × 2.00 • × 4.00
Ratios set using the zoom [.] and [+] keys	<p>Touching the [.] or [+] key increases or decreases the zoom ratio in × 0.01 increments. The ratio can range from × 0.25 to × 4.00.</p>
Full size	<p>This setting makes a copy the same size as the original (× 1.00).</p>

Specifying the zoom ratio

- 1 Position the original.
For details, refer to “Loading originals” on page 3-33.
- 2 Press the [Zoom] key until the desired fixed ratio is selected. Each press of the [Zoom] key changes the setting.
 - ? Do you want to specify a zoom ratio other than a fixed ratio.
 - Press the [▼] and [▲] keys until the desired zoom ratio is specified. Pressing these keys change the ratio in $\times 0.01$ increments.
 - To quickly specify the desired zoom ratio, select the nearest fixed ratio, and then press the [▼] and [▲] keys until the desired zoom ratio is specified.
- 3 Specify the desired copy settings.
For details, refer to “Making a basic copy” on page 4-3.
- 4 Using the 10-key pad, enter the number of copy to be made.
- 5 Press the [Start] key
This will start the copy cycle.



4.4 Image Density

Image density setting

The image density setting can be adjusted in two broad modes, “Text” and “Photo”:

- **Text mode**
 - The image density can be adjusted either automatically (Auto) or manually in nine steps.
 - The image density is adjusted automatically according to the original from which a copy is to be made.
 - The image density can be adjusted manually to one of nine levels. To reduce bleed-throughs when copying newspapers and magazines, press the [◀] key to select a lighter setting. To reproduce faint colors in brighter parts of the image, press the [▶] key to select a darker setting. Selecting a darker setting could result in a background image being reproduced on the copy, while selecting a lighter setting could make the copy image itself too light: Select the appropriate level according to your original.
- **Photo mode**


Select “Photo” when making a copy from an original having large halftone images, such as photos.

Specifying the image density

1 Position the original.
For details, refer to “Loading originals” on page 3-33.

2 Press the [Auto/Photo] key on the control panel to select the desired mode. Each press of the [Auto/Photo] key changes the setting as shown at the right.

- If text mode is selected, **TEXT** is displayed.
- If the auto setting is selected, **[A]** is displayed.
- If photo mode is selected, **PHOTO** is displayed. In the photo mode, the auto setting cannot be selected.




3 If you want to adjust the image density manually, press the [◀] or [▶] key to select the desired setting.

The displays for manually selected image densities are shown at the right.

4 Specify the desired copy settings.
For details, refer to “Making a basic copy” on page 4-3.

5 Using the 10-key pad, enter the number of copies to be made.


6 Press the [Start] key
This will start the copy cycle.



4.5 2in1 copies


2in1 copy function

Two sheets of single-sided documents can be copied onto one double-sided sheet. The optional automatic document feeder is required.




Specifying settings for 2in1 copies

- 1 Position the original as shown in the illustration at the right.



- 2 Press the [2in1] key, and then check that the indicator lights up.



- 3 Specify the desired copy settings. For details, refer to “Making a basic copy” on page 4-3.




- 4 Using the 10-key pad, enter the number of copies to be made.

- 5 Press the [Start] key
This will start the copy cycle.

4.6 Finishing copies


Finishing modes

When printing two or more sets, each set can be printed (sorted) in order. In order to sort the printed pages, the automatic document feeder is required.

Finishing modes	
<p>Non-sort The copies are stacked on top of each other as they are made.</p>	<p style="text-align: center;">Copying 1 sets</p> 
	<p style="text-align: center;">Copying 3 sets</p> 
<p>Sort Documents containing multiple pages can be copied and automatically separated into the individual sets</p>	<p style="text-align: center;">Copying 3 sets</p> 

Specifying sorting

- 1 Load the originals in the automatic document feeder.
- 2 Press the [Sort] key, and then check that the indicator lights up. If the sort indicator is not lit, the non-sort setting is selected.
- 3 Using the 10-key pad, enter the number of copies to be made.
- 4 Specify the desired copy settings.
For details, refer to “Making a basic copy” on page 4-3.
- 5 Press the [Start] key
This will start the copy cycle.



A large, bold, black number '5' is centered within a gray rectangular background.

Faxing

5 Faxing

This machine is a G3 fax. Faxes can only be sent or received with this machine if the recipient's or sender's machine complies with the G3 standard.

5.1 Dialing

The recipient's fax number can be dialed using any of the seven different dialing methods described below.


The procedures described below assume that the fax is being sent using the automatic document feeder.

Using direct dialing to communicate with overseas destinations

If the country code and destination number are entered after the international code, you may hear a busy tone during dialing and transmission may not be possible. In such cases, press the [Redial/Pause] key twice after entering the international code to insert an approx. -6-second pause, and then enter the rest of the number. If this still fails to connect the call, perform manual transmission (p. 6-6).

To fax by entering the fax number directly using the 10-key pad

- 1 Press the [Fax] key to enter fax mode.
- 2 Load the document into the automatic document feeder.
- 3 If necessary, change the resolution setting (p. 5-14).
- 4 Using the 10-key pad, enter the fax number of the recipient. F codes (SUB and SID) can also be entered. For details, refer to "Using F codes" on page 6-27.



- ? Have you entered the number correctly?
 - The fax number can contain a maximum of 30 digits.
 - The keys that can be used to enter the fax number are: the number keys (0 through 9), *, #, Space, and Pause
 - If the [Redial/Pause] key is pressed while entering the fax number, a 3-second pause is added. A pause appears as "P" in the display.
 - If you wish to change the fax number, press the [No/C] key, and then enter the correct number.

- If the machine is connected to a PBX line and the outside line access number has been specified in the communication settings (p. 7-73), enter “#” to dial the outside line access number automatically.

- 5 Press the [Start] key to begin scanning and sending the fax.

To fax using one-touch dialing

If one-touch dial keys have already been programmed with fax numbers, the fax number of a recipient can be specified by pressing just the corresponding one-touch dial key.

- 1 Press the [Fax] key to enter fax mode.
- 2 Load the document into the automatic document feeder.
- 3 If necessary, change the resolution setting (p. 5-14).

- 4 Press the one-touch dial key ([01] through [15]) programmed with the fax number that you wish to send the fax to.

01	02	03	04	05
06	07	08	09	10
11	12	13	14	15

- 5 Press the [Start] key.
The machine automatically starts scanning the document and sending the fax.

ONE-TOUCH DIAL 01
☒=AAA TOKYO (TX=START)




Detail

For details on programming the one-touch dial keys, refer to "Specifying ONE-TOUCH DIAL" on page 7-28.

To fax using speed dialing

If speed dial numbers have already been programmed, the fax number of a recipient can be specified quickly by entering the corresponding speed dial number.

- 1 Press the [Fax] key to enter fax mode.
- 2 Load the document into the automatic document feeder.
- 3 If necessary, change the resolution setting (p. 5-14).
- 4 Press the [Speed dial] key, and then use the 10-key pad to enter the 3-digit speed dial number.
 - ? Has the wrong speed dial number been entered?
 - Press the [No/C] key, and then enter the correct number.
- 5 Press the [Start] key to begin scanning and sending the fax.



Detail


For details on programming speed dial numbers, refer to “Specifying SPEED DIAL” on page 7-32.

To fax using group dialing


If one-touch dial keys have already been programmed with a group of fax numbers, the fax numbers of all recipients in the group can be specified by pressing just the corresponding one-touch dial key.

- 1 Press the [Fax] key to enter fax mode.
- 2 Load the document into the automatic document feeder.
- 3 If necessary, change the resolution setting (p. 5-14).

- 4 Press the one-touch dial key ([01] through [15]) programmed with the group of fax numbers that you wish to send the fax to.



- 5 Press the [Start] key.
The machine automatically starts scanning the document and sending the fax.



Detail


For details on programming one-touch dial keys with a group of fax numbers, refer to "Specifying GROUP DIAL" on page 7-36.

To fax using chain dialing


Faxes can be sent to recipients that are specified using any combination of one-touch dial keys, speed dial numbers, direct input using the 10-key pad, and the [Redial] key.

As an example, the following procedure describes how to specify recipients using one-touch keys, then using the 10-key pad.


- 1 Load the document into the automatic document feeder.
- 2 Press the [Speaker] key.



- 3 Press the desired one-touch key, and then press the [Start] key.



- 4 After the message **PRESS START KEY** appears, use the 10-Key Pad to enter the recipient's fax number.




- 5 Press the [Start] key.


To fax using program dialing

If one-touch dial keys have already been programmed with fax numbers and a transmission/reception function (such as timer transmission or polling reception), that function can be carried out by pressing just the corresponding one-touch dial key.

- 1 Press the [Fax] key to enter Fax mode.
- 2 Load the document into the automatic document feeder. (This step is not necessary with polling reception.)
- 3 If necessary, change the resolution setting (p. 5-14). (This step is not necessary with polling reception.)
- 4 Press the one-touch dial key ([12] through [15]) programmed with the desired function.



- 5 Press the [Start] key.
The programmed function automatically begins.
- ? Do you want to cancel the timer transmission?
- To cancel a timer transmission, select **CANCEL RESERV.** from the "FUNCTION" menu (p. 6-21).




Detail

For details on setting program dialing, refer to "Specifying PROGRAM DIAL" on page 7-40.

To fax using the phone book

The phone book contains all programmed one-touch dialing and speed dialing numbers, allowing you to search for and select the recipient that you wish to send the fax to.

- 1 Press the [Fax] key to enter fax mode.
- 2 Load the document into the automatic document feeder.
- 3 If necessary, change the resolution setting (p. 5-14).
- 4 Press the [Phone book] key.




- 5 Using the [◀] and [▶] keys, select either **LIST** or **SEARCH**, and then press the [Yes] key.

- If **LIST** was selected:

The list of programmed one-touch dialing and speed dialing numbers is displayed. Using the [▲] and [▼] keys, select the desired recipient.

- If **SEARCH** was selected:

A screen appears, allowing you to enter the text to be searched for. Search for the desired recipient by entering part (or all) of the name programmed. For details on performing the search, refer to "To search the phone book" on page 5-11.




- 6 Press the [Start] key to begin scanning and sending the fax.

To search the phone book


1 Press the [Phone book] key.

2 Using the [◀] and [▶] keys, select **SEARCH**, and then press the [Yes] key.



A screen appears, allowing you to enter the text to be searched for.

3 Using the 10-key pad, enter the first few characters of the name programmed for the desired recipient.




- Enter the name programmed in the one-touch dial key or the speed dial number. (For details on entering text, refer to “Entering Text” on page 3-23.)
- From 1 to 10 characters can be entered.

4 Press the [Yes] key.


The number of names beginning with the text entered in step 3 is displayed.

To select a recipient from the displayed search results, skip to step 7.




- ? Are there no one-touch dialing or speed dialing numbers with names beginning with the entered text?
- After “(0)” is displayed, the screen allowing you to enter the search text appears.

5 To narrow down the search results even further, press the [Yes] key, and then enter more search text.



6 Press the [Yes] key.

7 Using the [▲] and [▼] keys, select the desired recipient.




- ? Does the desired recipient name not appear in the search results?
- Press the [No/C] key twice to return to the screen allowing you to enter the search text, and then try searching for different text.

- 8 Press the [Start] key to begin scanning and sending the fax.



To redial the last recipient called

- 1** Press the [Fax] key to enter fax mode.
- 2** Load the document into the automatic document feeder.
- 3** If necessary, change the resolution setting (p. 5-14).
- 4** Press the [Redial/Pause] key.
The fax number of the last recipient called is displayed.
- 5** Press the [Start] key to begin scanning and sending the fax.



5.2 Transmission settings

Adjusting the fax resolution

Selecting one of the following resolutions to match the type of document to be faxed (documents containing a lot of small print, detailed illustrations or photos) will produce a sharper result.

Document type	Resolution setting
Documents with normal print	Standard
Documents containing small print, such as newspapers Documents containing detailed illustrations	Fine, Super fine
Documents containing text and objects with varying shades, such as photos	Standard + Half tone, Fine + Half Tone
Documents containing objects with varying shades, such as photos	Fine + Half tone, Super fine + Half tone

To specify the resolution

- 1 Load the document into the automatic document feeder.
- 2 Press the [Resolution] key on the control panel to select the resolution mode.
- 3 Using the [◀] and [▶] keys, select the fax resolution, and then press the [Yes] key.



Note


Depending on the recipient's fax machine, faxes sent with the Super fine or Super fine + Half tone setting may not be sent as specified, and instead are sent with the Fine or Half tone setting.

If the Half Tone or Super fine + Half tone setting is specified, the fax may be sent with a decreased resolution depending on the quality of the recipient's fax machine or whether the document size is larger than the paper loaded in the recipient's fax machine.


5.3 Basic Faxing

To fax using the automatic document feeder

- 1 Press the [Fax] key to enter fax mode.




- 2 Load the document face up into the automatic document feeder.
- 3 Adjust the document guide plates to fit the size of the document.
- 4 If necessary, change the resolution setting (p. 5-14).



- 5 Using the 10-key pad, enter the fax number of the recipient.

- The fax number of a previously programmed recipient can also be specified. Refer to “Dialing” on page 5-3.



- 6 Press the [Start] key to begin scanning and sending the fax.

Once transmission is finished, a beep is sounded.

If the fax could not be sent, the transmission result report is printed (p. 7-76).

? Do you want to stop the transmission?

→ To stop the transmission, press the [Stop] key.

? Do you want to cancel a scanned document queued for transmission or a fax waiting to be redialed?

→ Select **CANCEL RESERV.** from the “FUNCTION” menu (p. 6-21).

**Note**


About 224 A4-size document pages can be scanned and stored in the memory at one time. If the optional expansion memory (32 MB Memory for Fax) is installed, as many as 1024 document pages can be stored.

**Reminder**


While faxing, if the recipient's fax machine is busy or does not answer or if, for any other reason, such as a transmission error, the fax is not sent correctly, the transmission result report is printed.

To fax documents positioned on the original glass

- 1 Press the [Fax] key to enter fax mode.




- 2 Lift open the automatic document feeder.
- 3 Position the document to be faxed face down on the original glass.



- 4 Align the document on the scales above and to the left of the original glass.

- 5 If necessary, change the resolution setting (p. 5-14).

- 6 Using the 10-key pad, enter the fax number of the recipient, and then press the [Yes] key.



- The fax number of a previously programmed recipient can also be specified. Refer to "Dialing" on page 5-3.

- 7 Press the [Start] key to display a message confirming the size of the loaded document page. If the indicated page size is correct, press the [Yes] key. To scan multiple document pages, continue loading pages and pressing the [Yes] key until all pages are scanned. After scanning all document pages to be faxed, press the [Start] key to begin sending the fax.

Once transmission is finished, a beep is sounded.

If the fax could not be sent, the transmission result report is printed (p. 7-76).

? Do you want to stop the transmission?

→ To stop the transmission, press the [Stop] key.

If the memory becomes full while scanning fax documents

If the memory becomes full while scanning a document for memory transmission, only the pages that have been scanned are sent.


With a queued transmission (a fax transmission requested while another fax transmission job is being performed) or timer transmission, if the memory becomes full while scanning the document, a message appears, allowing you to select whether to send just the scanned pages or cancel the transmission. If the transmission is canceled, the data for the scanned pages is deleted. After the other fax transmission or reception is finished, check the amount of memory available, and then try sending the fax again.

5.4 Checking transmission results


The transmission result information for a maximum of 60 sent and received documents is saved.

To check the transmission result


- 1 Press the [Status] key.




- 2 Press the [▼] key.



- 3 Press the [Yes] key.



- 4 Using the [▲] and [▼] keys, display the desired transmission results to check them.



? What does TX and RX indicate?

→ TX indicates sent faxes.

RX indicates received ones.

? Do you want to return to the main screen?

→ Press the [No/C] key twice while the transmission results are displayed, the main screen appears.

? Do you want to print the transmission result report?

→ Press the [Start] key. After the transmission result report is printed, the main screen appears.



6

Fax transmission/ Reception methods

6 Fax transmission/Reception methods

6.1 Transmission methods

6.1.1 Memory transmission

With memory transmission, the document is scanned, then stored in the memory for transmission (queued transmission).

Memory transmission is selected as the default transmission mode.




Detail


For details on sending faxes through memory transmission, refer to "Basic Faxing" on page 5-15.

To specify memory TX


- 1 Press the [Fax] key to enter fax mode.



- 2 Load the document into the automatic document feeder.
- 3 If necessary, change the resolution setting (p. 5-14).



- 4 Press the [Memory TX] key.
- 5 Check that the memory TX lamp lights up. If the memory TX lamp is not lit, the direct transmission is selected.



6 Using the 10-key pad, enter the fax number of the recipient.

- The fax number of a previously programmed recipient can also be specified. For details, refer to “Dialing” on page 5-3.



7 Press the [Start] key to begin scanning and sending the fax.

Once transmission is finished, a beep is sounded.

If the fax could not be sent, the transmission result report is printed (p. 7-76).

? Do you want to stop the transmission?

→ To stop the transmission, press the [Stop] key.

6.1.2 Direct transmission

If the memory TX lamp is not lit, the direct transmission is selected. One page of the document at a time can be scanned, according to the transmission status. This ensures that even documents with many pages can be sent.



Note

When faxing using direct transmission, the document should be loaded into the automatic document feeder. Transmission is not possible by positioning the document on the original glass.

If direct transmission is specified while a fax is being sent or received, the transmission will be queued.

With direct transmission, multiple recipients cannot be specified.

Direct transmission and timer transmission cannot be performed at the same time.

6.1.3 Manual transmission

If the machine is connected to a telephone and the same line is used for phoning and faxing, the document can simply be sent after talking with the recipient over the phone.

This is useful, for example, if you wish to tell the recipient that you are sending a fax.



Note

If the recipient's fax machine is set to receive faxes automatically (automatic reception), a beep is sounded without the recipient answering the phone; however, at that time, the telephone cannot be used for talking. If the fax is to be sent after talking on the telephone, use the automatic document feeder.

Manual transmission is possible if a telephone (either purchased or rented) is connected to the TEL port of this machine.




Note

Even when pulse dialing is being used, entering "" produces signals for tone dialing.*

To send a fax manually

- 1 Load the document into the automatic document feeder.
- 2 If necessary, change the resolution setting (p. 5-14).
- 3 Pick up the telephone receiver.
Check that the dial tone can be heard.
- 4 Specify the fax number of the recipient.
 - Use the telephone to dial the fax number.
 - The fax number of the recipient can also be specified using the keys in the control panel of this machine (p. 5-3).
- 5 After finishing talking on the phone, the recipient should press the necessary key to start receiving the fax.



Once the recipient's fax machine is ready, a beep is sounded.

- 6 Press the [Start] key to begin scanning and sending the fax.
- 7 Replace the telephone receiver.
 - ? Do you want to stop the transmission?
→ Press the [Stop] key.

**Note**


If the [Speaker] key is pressed instead of picking up the telephone receiver, the speaker can be used for manual transmission in the same way as described above.

6.1.4 Batch transmission

Multiple documents can be stored in the memory and faxed together at a specified time. In order to use this function, the corresponding utility mode function must first be used to program a one-touch dial key with the batch transmission settings (transmission time) (p. 7-28).

To fax using batch transmission

- 1 Load the document into the automatic document feeder.
- 2 If necessary, change the resolution setting (p. 5-14).
- 3 Press the one-touch dial key programmed with the desired batch transmission settings.
- 4 Press the [Start] key to begin scanning the document.



The document is automatically sent at the specified time.

- ? Do you want to cancel a batch transmission?
→ Select **CANCEL RESERV.** from the FUNCTION menu (p. 6-21).

6.1.5 Broadcast transmission

The same document can be sent to multiple recipients at one time.

A maximum of 231 recipients can be specified for the same transmission.

The recipients can be specified by using the one-touch dial keys, the speed dial numbers or group dialing, by selecting from the phone book, or by entering the fax number using the 10-key pad.



Note

A maximum of 16 recipients can be specified by entering the fax number using the 10-key pad.

A maximum of 15 recipients can be programmed with a one-touch dial key and a maximum of 200 recipients can be programmed with a speed dial number.




Note


With the result report printed after the transmission is finished, you can check whether the fax was sent to all recipients.

To fax using broadcast transmission

- 1 Position the document.
- 2 If necessary, change the resolution setting (p. 5-14).
- 3 Press the [Function] key.



- 4 Press the [1] key from the 10-key pad.
or
Press the [Function] key once to select **BROADCAST**, and then press the [Yes] key.



- 5 Specify the fax number of the recipient.
Repeat the appropriate operations described below until all recipients have been specified.

? Do you want to use one-touch dial keys?

→ Press the one-touch dial key programmed with the desired fax number.

NO.001=ONE-TOUCH 01

→ Press the [Yes] key, and then specify the next recipient.

NO.001=AAA TOKYO
OK=YES (Fin.=START)

? Do you want to use speed dial numbers?

→ Press the [Speed Dial] key, and then use the 10-key pad to enter the 3-digit speed dial number programmed with the desired fax number.

NO.002=SPEED 011

→ Press the [Yes] key, and then specify the next recipient.

NO.002=AAA OSAKA
OK=YES (Fin.=START)

? Do you want to use group dialing?

→ Press the one-touch dial key programmed with the desired group of fax numbers.

→ Press the [Yes] key, and then specify the next recipient.

? Do you want to select from the phone book?

→ Press the [Phone Book] key, and then select either **LIST** or **SEARCH** to select the desired fax number.

For details, refer to "To fax using the phone book" on page 5-10.

→ Press the [Yes] key, and then specify the next recipient.

? Do you want to enter the number using the 10-key pad?

→ Enter the fax number of the recipient.

NO.003=0123456_
SUB=▼

→ Press the [▼] key. F codes (SUB and SID) can also be entered.

→ Press the [Yes] key, and then specify the next recipient.

? Has the wrong fax number been specified?

→ Press the [No/C] key to delete the current selection. This is valid only before the recipient is set by pressing the [Yes] key.

- 6 Press the [Start] key.

A message appears, allowing you to select whether or not to check the recipients.

- 7 To check the recipients, press the [Yes] key. If you do not wish to check the recipients, continue with step 9.



CHECK DESTINATIONS?
OK=YES (TX=START)

The recipients specified in step 5 are displayed in the order that they were selected.

- 8 Check the recipient, and then press the [Yes] key.


After all recipients have been checked, **Fin.=START** appears in the display.

? Do you want to delete the displayed recipient?

→ Press the [No/C] key.



NO.001=AAA TOKYO
OK=YES (DEL=NO)



NO.001 DELETED



NO.005=_
Fin.=START [1]

- 9 Press the [Start] key to begin scanning and sending the fax.

6.1.6 Timer transmission

A document can be scanned and stored in the memory to be sent at a specified time. This function is convenient for sending documents with a large number of pages at discounted calling times.



Note

The time is set for a 24-hour period.

If the machine is not programmed with the current time (p. 7-78), the fax cannot be sent at the specified time.

A timer transmission cannot be performed at the same time as a direct transmission.




Note


Timer transmission can be combined with broadcast transmission, mailbox transmission, polling reception, or relay initiation transmission.

To fax using timer transmission

- 1 Position the document.
- 2 If necessary, change the resolution setting (p. 5-14).
- 3 Press the [Function] key.




- 4 Press the [2] key from the 10-key pad.
or
Press the [Function] key twice to select **TIMER TX**, and then press the [Yes] key.



A screen appears, allowing you to specify the transmission time.

- 5 Using the 10-key pad, enter the desired transmission time, and then press the [Yes] key.




TIMER=21:00
OK=YES

? Do you want to correct the time?

→ Press the [No/C] key, and then enter the correct time.

- 6 Specify the fax number of the recipient. For details, refer to “Dialing” on page 5-3.



☎=0123456_
SUB=▼ [1]

- 7 Press the [Start] key.

The machine scans the document, then enters transmission standby mode.

6.1.7 Mailbox transmission

The fax can be sent to a recipient's mailbox.

This is perfect for sending an important document to a specific person.




Note


Mailbox transmission is compatible with F code transmission. Machines compatible with F codes can be specified as recipients for mailbox transmission.

To fax using mailbox transmission

- 1 Position the document.
- 2 If necessary, change the resolution setting (p. 5-14).
- 3 Press the [Function] key.




- 4 Press the [3] key from the 10-key pad.
or
Press the [Function] key 3 times to select **MAILBOX TX**, and then press the [Yes] key.



- 5 Specify the recipient, and then press the [Yes] key. For details, refer to "Dialing" on page 5-3

A screen appears, allowing you to specify the mailbox ID.



6 Using the 10-key pad, enter the mailbox ID of the recipient.

- Enter the mailbox ID (SUB) (20 digits or less) registered for the recipient.
 - If the recipient is specified using a one-touch dial key or a speed dial number also programmed with a SUB, the SUB is displayed as the mailbox ID. If necessary, change the mailbox ID.
- ? Do you want to correct the mailbox ID?
→ Press the [No/C] key, and then enter the new number.




MAILBOX ID=1234
OK=YES

7 Press the [Yes] key.

8 Using the 10-key pad, enter the password.

- Enter the password (20 digits or less) if a password has been set for the recipient's mailbox.
- ? Do you want to correct the password?
→ Press the [No/C] key, and then enter the new number.



PASSWORD=5678
(TX=START)

9 Press the [Start] key to begin scanning and sending the fax.

6.1.8 Relay initiation transmission

Documents can be sent from this machine (transmitting station) to another fax machine (acting as a relay station), which then sends the documents to multiple recipients (receiving stations). By relaying the documents through a fax machine closer to the remote recipients, the transmission time and cost for the transmitting station are reduced.

In order to fax using relay initiation transmission, a relay box must first be programmed at the relay station.



Note

Relay initiation transmission is compatible with F code transmission.


Only machines that are compatible with relay broadcast transmission should be specified as relay stations. This machine can be specified as a relay station.

Relay initiation transmission and mailbox transmission cannot be performed at the same time.


In order to fax using relay initiation transmission, a relay box ID must first be programmed at the relay station (p. 7-49).

To fax using relay initiation transmission

- 1 Position the document.
- 2 If necessary, change the resolution setting (p. 5-14).
- 3 Press the [Function] key.




- 4 Press the [7] key from the 10-key pad.
or
Press the [Function] key 7 times to select **RELAY INITIATE**, and then press the [Yes] key.



- 5 Specify the relay station, and then press the [Yes] key. For details, refer to “Dialing” on page 5-3.

A screen appears, allowing you to specify the relay box ID.




S=0123456_
OK=YES

- 6 Using the 10-key pad, enter the relay box ID.

- Enter the mailbox ID (SUB) (20 digits or less) registered for the recipient.

? Do you want to correct the ID?

→ Press the [No/C] key, and then enter the new number.



RELAY BOX ID=1234_
OK=YES

- 7 Press the [Yes] key.


A screen appears, allowing you to specify the password.

- 8 Using the 10-key pad, enter the password.

- Enter the password (20 digits or less) if a password has been set at the relay station.

? Do you want to correct the password?

→ Press the [No/C] key, and then enter the new number.



PASSWORD=5678
(TX=START)

- 9 Press the [Start] key to begin scanning and sending the fax.

6.1.9 Polling Transmission

Documents scanned and saved in the memory can be retrieved by the recipient.



Note

Polling transmission is compatible with F code transmission.


A maximum of 30 polling transmissions can be programmed.

If the memory is full, polling transmission cannot be set.


With polling transmission, the recipient incurs the cost of the call.

To set up polling transmission


- 1 Position the document.
- 2 If necessary, change the resolution setting (p. 5-14).
- 3 Press the [Function] key.



- 4 Press the [5] key from the 10-key pad.
or
Press the [Function] key 5 times to select **POLLING TX**, and then press the [Yes] key.




- 5 Using the [◀] and [▶] keys, select either **SINGLE** or **MULTI**, and then press the [Yes] key.



- To allow only one polling transmission request, then delete the document from the memory, select **SINGLE**.
- To allow multiple polling transmission requests, select **MULTI**. The document is stored in the memory until it has been deleted.


- 6 Using the 10-key pad, enter the 4-digit polling ID, and then press the [Yes] key.



POLL ID=1234
OK=YES

- If you do not wish to set a polling ID, skip to step 8.
- The polling ID can be set to any number between 0000 and 9999.
- If there is only one polling transmission document, it is not necessary to specify a polling ID and password.

- 7 Using the 10-key pad, enter the 4-digit password.



PASSWORD=5678
(TX=START)

- If you do not wish to set a password, continue with step 8.
- The password can be set to any number between 0000 and 9999.

- 8 Press the [Start] key.

The machine scans the document, then enters standby mode.

To delete a document from the polling transmission setup

- 1 Press the [Function] key.




Function

- 2 Press the [5] key from the 10-key pad.

or

Press the [Function] key 5 times to select **POLLING TX**, and then press the [Yes] key.



FUNCTION
SEL.0-8/or FUNCTION

5 POLLING TX


If polling transmission has been set, a screen appears, allowing you to specify the polling ID.

- 3 Using the [◀] and [▶] keys, select either **SINGLE** or **MULTI**, and then press the [Yes] key.



*SINGLE MULTI
◀, ▶ & YES

- 4 Using the 10-key pad, enter the polling ID, and then press the [Yes] key.



POLL ID=1234
OK=YES

- 5 Press the [No/C] key to delete from the memory the document set for polling transmission.

? Do you want to keep the polling transmission setting?

→ Press the [Yes] key.



REGISTERED! KEEP?
OK=YES (DEL=NO)

POLL TX DOC. DELETED


- 6 Press the [No/C] key twice to return to the main screen.

6.1.10 Canceling (Deleting) a Document Queued in the Memory for Transmission

Of the documents stored in the memory and waiting to be sent, a specific document can be selected and deleted.

To cancel a queued document


- 1 Press the [Function] key.



- 2 Press the [8] key from the 10-key pad.

or

Press the [Function] key 8 times to select **CANCEL RESERV.**, and then press the [Yes] key.



The details (specified transmission time/type of transmission) of the jobs queued in the memory are displayed.

? Have no jobs been queued in the memory?

→ The message **NONE** appears.

- 3 Using the [▲] and [▼] keys, select the job to be deleted.

- The following types of job are displayed.

MEMORY: Memory transmission

B-CAST: Broadcast transmission

TIMER: Timer transmission

M.B. TX: Mailbox transmission


POLL-TX: Polling transmission

POLL-RX: Polling reception

RELAY: Relay initiation transmission

FORWARD: Fax forwarding

- To check the recipient of the currently displayed transmission job, press the [▶] key. After checking, press the [Yes] key to return to the previous screen.



- 4 Press the [Yes] key to delete the displayed job.
FUNCTION menu appears in the display.

A screenshot of a device's display showing a confirmation message. The text is arranged in two lines: the first line reads "*02 [:] MEMORY" and the second line reads "CANCELED*". The text is enclosed in a double-line rectangular border.

- 5 To delete another queued job, repeat steps 2 and 4.
- 6 If you are finished deleting jobs, press the [No/C] key to return to the main screen.

6.2 Reception methods

6.2.1 Manual reception

This machine normally receives faxes automatically. However, if a telephone is connected and the same line is used for phoning and faxing, the document can simply be received after talking with the caller over the phone.




Note

Manual reception is possible if a telephone is connected to the TEL port of this machine.

To receive faxes manually, use the corresponding utility mode function to select the manual reception mode (p. 7-64).

To receive a fax manually

- 1 After the telephone rings, pick up the receiver to talk with the caller.
- 2 After talking and the caller's fax machine sounds long beeps, press the [Start] key.
The machine starts receiving the fax.
 Were the long beeps not sounded by the caller's fax machine?
→ If the caller's fax machine is set to send automatically, the long beeps may not be sounded.
- 3 If the telephone receiver is replaced, the fax reception is finished and the machine sounds a beep.

6.2.2 Memory reception

This machine automatically prints faxes that it has received. However, when receiving confidential faxes, the received document can be stored in the memory and printed at a specified time or when memory reception is turned off.



Detail

Memory reception is set using the corresponding utility mode function. For details on changing the setting, refer to "Specifying MEMORY RX MODE" on page 7-64.

6.2.3 Mailbox reception

If mailbox numbers and F codes (mailbox IDs and passwords) have already been programmed on this machine, this function can be used to receive only those faxes with an identical mailbox ID and password specified by the caller.

Since the received fax can only be retrieved after entering the corresponding mailbox ID, confidential faxes can safely be sent and received.




Detail


For details on programming the mailboxes, refer to "Specifying MAIL-BOX" on page 7-55.

To retrieve a document from a mailbox

- 1 Press the [Function] key.




- 2 Press the [4] key from the 10-key pad.
or
Press the [Function] key 4 times to select **PRINT MAILBOX RX**, and then press the [Yes] key.



A screen appears, allowing you to enter the mailbox ID.

- 3 Using the 10-key pad, enter the 4-digit mailbox ID, and then press the [Yes] key.



6.2.4 Polling Reception

Using polling reception, documents set up in other fax machines can be received.




Note


Polling reception is compatible with F code transmission.

To receive a fax using polling reception


- 1 Press the [Function] key.




- 2 Press the [6] key from the 10-key pad.
or
Press the [Function] key 6 times to select **POLLING RX**, and then press the [Yes] key.




- 3 Specify the fax number to be called. For details, refer to step 5 of “To fax using broadcast transmission” on page 6-9.



- 4 To enter the polling ID and password, press the [▼] key.
 - If there is no need to enter a polling ID and password, skip to step 7.



- 5 Using the 10-key pad, enter the polling ID (20 digits or less), and then press the [Yes] key.



- 6 Using the 10-key pad, enter the password (20 digits or less), and then press the [Yes] key.

```
PASSWORD=2222
OK=YES
```

- 7 To specify multiple fax numbers, repeat steps 3 through 6.
- If you do not wish to specify other fax numbers, continue with step 8.

```
NO.002=
(Fin.=START)
```

- 8 Press the [Start] key.

A message appears, allowing you to select whether or not to check the fax numbers to be called.

- 9 To check the numbers to be called, press the [Yes] key.

- If you do not wish to check the numbers to be called, skip to step 11.

```
CHECK DESTINATIONS?
OK=YES (RX=START)
```

- 10 The fax numbers specified in step 3 are displayed in the order that they were selected.

Check the fax numbers, and then press the [Yes] key.

After all fax numbers have been checked, **Fin.=START** appears in the display.

? Do you want to delete the displayed fax number?

→ Press the [No/C] key.

```
NO.001=AAA TOKYO
OK=YES (DEL=NO)
```

```
*NO.001 DELETED*
```

```
NO.002=
(Fin.=START)
```

- 11 Press the [Start] key.

6.3 Using F codes

This machine is compatible F code transmissions.

F codes are mailbox functions, such as SUB (sub-addresses), SEP (selective polling), SID and PWD (passwords), regulated by the G3 standards of the ITU-T (International Telecommunication Union). Mailbox transmission and reception is possible only with similar machines compatible with F code transmission. Using the 10-key pad, the following F codes can be set, depending on the use.

F codes

- SUB:
Specify when transmitting while using F codes.
- SID:
Specify when limiting the recipient/caller with a password.
- SEP:
Specify when calling another fax machine to receive a document set up in it (polling reception).



Note


The F code function is only available with fax machines that have this function as well. Ask your partner, if their machine can process F code transmissions.

If one-touch dial keys or speed dial numbers are programmed with F codes (SUB and SID), the appropriate F code can quickly be transmitted to the recipient/caller.

6.3.1 Using Mailboxes

Specifying mailboxes

Mailboxes can be used if they are set up using the corresponding Utility mode function. For details, refer to “Mailbox reception” on page 6-24.



F code mailbox transmission/reception

A maximum of 5 mailboxes can be set up. Since a mailbox ID is required in order to retrieve documents received in the different mailboxes, confidential faxes can safely be sent and received.

For details, refer to “Specifying MAILBOX” on page 7-55.

If one-touch dial keys or speed dial numbers are programmed with F codes, the appropriate F code can quickly be transmitted.

For details, refer to “Mailbox transmission” on page 6-14.

6.3.2 Specifying F codes

When sending faxes

F codes can be specified when the 10-key pad is being used to enter the fax number of a recipient while sending a fax.

- 1 Using the 10-key pad, enter the fax number of the recipient.

A screenshot of a fax machine's display. The top line shows a telephone handset icon followed by the number "0123456_" and a cursor. The bottom line shows "SUB=" followed by a cursor and a "[1]" indicator.

- 2 Press the [▼] key, and then use the 10-key pad to enter the SUB.

- A number up to 20 digits long can be entered for the SUB.
- To enter an SID, continue with step 3.
- If an SID will not be entered, continue with step 4.

A screenshot of a fax machine's display. The top line shows "SUB=9876_" and a cursor. The bottom line shows "SID=" followed by a cursor and "(TX=START)".

- 3 Press the [▼] key, and then use the 10-key pad to enter the SID.

- A number up to 20 digits long can be entered for the SID.

A screenshot of a fax machine's display. The top line shows "SID=5555_" and a cursor. The bottom line shows "(TX=START)".

- 4 Press the [Start] key to begin scanning and sending the fax.

Programming F codes

F codes can be specified when programming one-touch dial keys or speed dial numbers.



Detail

For details, refer to "Fax registration settings" on page 7-26.

A large, bold, black number '7' is centered within a gray square. The square is positioned to the left of the main title.

Using the utility mode

7 Using the utility mode

There are fifteen menus in the utility mode.

No.	Name	Description
1	MACHINE SETTING	Used to specify settings for the machine's operating environment.
2	PAPER SOURCE SETUP	Used to specify the size and type of paper loaded in tray1. In addition, auto tray switching can be enabled for each tray.
3	USER MANAGEMENT	Used to specify settings after the drum cartridge is replaced.
4	ADMIN.MANAGEMENT	Used to specify setting for the administrator.
5	COPY SETTING	Used to specify the default settings for each copy function.
6	FAX REGISTRATION	Used to specify the default setting for each fax function.
7	TX OPERATION	Used to specify the default setting for TX operation.
8	RX OPERATION	Used to specify the default setting for RX operation.
9	COMM. SETTING	Used to specify the default setting for communicating environment.
10	REPORTING	Used to specify the default setting for each report function.
11	INITIAL USER DATA	Used to specify setting for the initializing user data.
12	NETWORK SETTING	Available only if the optional network interface card NC-501 is installed. For details, refer to the User's Guide for the network interface card (NC-501).
13	E-MAIL SETTING 1	Available only if the optional scanner unit SU-502 is installed. For details, refer to the User's Guide for the scanner unit SU-502.
14	E-MAIL SETTING 2	
15	SCAN SETTING	

7.1 Machine settings

From the MACHINE SETTING menu, various settings for the machine's operating environment can be specified. Refer to the following table for details on each function.

No.	Name	Description
1	AUTO PANEL RESET	Whether the auto panel reset function is disable or the time (0.5 min, 1 min, 2 min, 3 min, 4 min, or 5 min) until the machine is reset after finishing copying/printing or after performing the last operation can be selected. If the auto panel reset function is enabled, all functions are automatically reset to their default settings. <ul style="list-style-type: none"> • Default setting: 1 min.
2	ENERGY SAVE MODE	If the machine performs no operations for a set length of time, it will automatically enter the energy save mode. The length of time until the machine enters energy save mode can be set between 1 and 240 min (in 1 min increments). <ul style="list-style-type: none"> • Default setting: 15 min.
3	DENSITY (ADF)	The scanning density when using the automatic document feeder can be adjusted. <p>Mode 1: For printing lighter copies of dark documents to avoid darkening of copies.</p> <p>Mode 2: For printing copies with same density as documents.</p> <ul style="list-style-type: none"> • Default setting: Mode 1.
4	DENSITY (BOOK)	The density when scanning from the original glass can be adjusted. <p>Mode 1: For printing copies with same density as documents.</p> <p>Mode 2: For printing lighter copies of dark documents to avoid darkening of copies.</p> <ul style="list-style-type: none"> • Default setting: Mode 1.
5	PRINT DENSITY	The copy/print density can be adjusted to one of six levels between -3 and +2. With the normal print density at 0, choose a smaller number for a lighter print or choose a higher number for a darker print. <ul style="list-style-type: none"> • Default setting: 0 (Normal).
6	LCD CONTRAST	The brightness of the display can be set to one of four levels between -1 and +2. <ul style="list-style-type: none"> • Default setting: 0 (Normal).
7	LANGUAGE	The display language can be selected. <ul style="list-style-type: none"> • Default setting: English.
8	LAMP OFF TIME	The time until the exposure lamp goes off can be adjusted. <p>Mode 1: When four hours have passed since the last operation was performed</p> <p>Mode 2: When the machine enters energy save mode</p> <ul style="list-style-type: none"> • Default setting: Mode 1.
9	BUZZER VOLUME	This function can be used to set the volume of alarms and the beep sounded when a key is pressed. <ul style="list-style-type: none"> • Default setting: LOW.

No.	Name	Description
0	INITIAL MODE	This function can be used to set the mode (Copy mode or Fax mode) that the machine starts up in or returns to after the Control Panel is reset. <ul style="list-style-type: none">• Default setting: COPY.

Selecting the MACHINE SETTING menu

1 Press the [Utility] key.
MACHINE SETTING appears.

2 From the 10-key pad, press the key [0] to [9] for the machine setting function that you wish to set.


The machine setting functions are as follows:

- 1 AUTO PANEL RESET
- 2 ENERGY SAVE MODE
- 3 DENSITY (ADF)
- 4 DENSITY (BOOK)
- 5 PRINT DENSITY
- 6 LCD CONTRAST
- 7 LANGUAGE
- 8 LAMP OFF TIME
- 9 BUZZER VOLUME
- 0 INITIAL MODE

? Do you want to quit changing the machine settings?


→ Press the [No/C] key. **STOP SETTING?** appears.

→ Press the [Yes] key to quit changing the settings.




Specifying AUTO PANEL RESET

- 1 Select **AUTO PANEL RESET** in the **MACHINE SETTING** menu.
For details, refer to page 7-6.
- 2 Press the [◀] and [▶] keys to select either **ON** or **OFF**, and then press the [Yes] key.
 - ? Do you want to disable the panel reset function?
 - Select **OFF**. The auto panel reset function is disabled. **MACHINE SETTING** appears again.




- 3 Press the [◀] and [▶] keys to select the desired time period (min).
- 4 Press the [Yes] key.




Specifying ENERGY SAVE MODE

- 1 Select **ENERGY SAVE MODE** in the **MACHINE SETTING** menu.
For details, refer to page 7-6.
- 2 Use the 10-key pad to specify the desired length of time until the copier enters energy save mode. The timer can be set between 1 min and 240 min.
 - ? Do you want to clear the entered value?
 - Press the [No/C] key and enter the correct value.
- 3 Press the [Yes] key.




Specifying DENSITY (ADF)

- 1 Select **DENSITY (ADF)** in the **MA-CHINE SETTING** menu.
For details, refer to page 7-6.
- 2 Press the [◀] and [▶] keys to select either **MODE 1** or **MODE 2**.
- 3 Press the [Yes] key.




Specifying DENSITY (BOOK)

- 1 Select **DENSITY (BOOK)** in the MACHINE SETTING menu.
For details, refer to page 7-6.
- 2 Press the [◀] and [▶] keys to select either **MODE 1** or **MODE 2**.
- 3 Press the [Yes] key.




Specifying PRINT DENSITY

- 1 Select **PRINT DENSITY** in the MACHINE SETTING menu.
For details, refer to page 7-6.
- 2 Press the [◀] and [▶] keys to select one of the seven print density levels between **LIGHT** and **DARK**.
- 3 Press the [Yes] key.




Specifying LCD CONTRAST

- 1 Select **LCD CONTRAST** in the MACHINE SETTING menu.
For details, refer to page 7-6.
- 2 Press the [◀] and [▶] keys to select one of the four display contrast levels between **LIGHT** and **DARK**.
- 3 Press the [Yes] key.




Specifying LANGUAGE

- 1 Select **LANGUAGE** in the MACHINE SETTING menu.
For details, refer to page 7-6.
- 2 Press the [▲] and [▼] keys to select the desired language.
- 3 Press the [Yes] key.




Specifying LAMP OFF TIME

- 1 Select **LAMP OFF TIME** in the MACHINE SETTING menu.
For details, refer to page 7-6.
- 2 Press the [◀] and [▶] keys to select either **MODE 1** or **MODE 2**.
- 3 Press the [Yes] key.




Specifying BUZZER VOLUME

- 1 Select **BUZZER VOLUME** in the MACHINE SETTING menu.
For details, refer to page 7-6.
- 2 Press the [◀] and [▶] keys to set the buzzer volume to **HIGH**, **LOW** or **OFF**.
- 3 Press the [Yes] key.



Specifying INITIAL MODE

- 1 Select **INITIAL MODE** in the **MA-CHINE SETTING** menu.
For details, refer to page 7-6.
- 2 Press the [◀] and [▶] keys to select either **COPY** or **FAX**.
- 3 Press the [Yes] key.



7.2 Paper source settings

From the PAPER SOURCE SETUP menu, the various settings for each paper tray can be specified.

No.	Name	Description
1	TRAY1 PAPER	The type and size of paper loaded in tray 1 can be specified. <ul style="list-style-type: none"> • Default setting: PLAIN, A4 (Lengthwise).
2	TRAY SETTING	Whether or not auto tray switching is enabled for each paper tray can be specified. (p. 3-22) <ul style="list-style-type: none"> • Default setting: CONTINUOUS.

Selecting the PAPER SOURCE SETUP menu


- 1 Press the [Utility] key twice.
PAPER SOURCE SETUP appears.

- 2 From the 10-key pad, press the key [1] or [2] for the paper source setup function that you wish to set.

The paper source setup functions are as follows:


- 1 TRAY1 PAPER
- 2 TRAY SETTING

- ?** Do you want to quit setting up the paper sources?
 → Press the [No/C] key. **STOP SETTING?** appears. Press the [Yes] key to quit changing the settings.




Specifying TRAY1 PAPER


- 1 Select **TRAY1 PAPER** in the PAPER SOURCE SETUP menu. For details refer to page 7-13.
- 2 Press the [◀] and [▶] keys until the type of paper loaded is selected.
 - ? Do you want to copy on OHP transparencies?
 - The only paper sizes that can be loaded are A4 □ (Lengthwise) and Letter □ (Lengthwise).
- 3 Press the [Yes] key.




- 4 Press the [◀] and [▶] keys to select a standard size of paper that is loaded.
 - or*
 - press the [▼] key to enter a custom size of paper that is loaded.
 - ? Do you want to use a standard paper size (A5, B5, A4 ...)?
 - Select a standard paper size.
 - Continue with step 8.
 - ? Do you want to enter a custom paper size?
 - Select CUSTOM.
 - Perform steps 5 through 7.
 - ? Do you want to return to the previous message?
 - Press the [No/C] key.



- 5 Using the 10-key pad, enter the width (X) of the loaded paper. The paper width can range from 90 mm to 216 mm.
- ? Do you want to clear the entered value?
→ Press the [No/C] key.
- 6 Press the [Yes] key.



- 7 Using the 10-key pad, enter the length (Y) of the loaded paper. The paper width can range from 140 mm to 356 mm.
- ? Do you want to clear the entered value?
→ Press the [No/C] key.
- 8 Press the [Yes] key.




Specifying TRAY SETTING


A tray can be selected only if the optional paper feed cassette is installed.

- 1 Select **TRAY SETTING** in the PAPER SOURCE SETUP menu.
For details refer to page 7-13.

- 2 Press the [▲] and [▼] key to select a tray.




- 3 Press the [Yes] key.



- 4 Press the [◀] and [▶] keys to select either **FIXED** or **CONTINUOUS**.
 - **FIXED:**
Auto tray switching disabled
 - **CONTINUOUS:**
Auto tray switching enabled

- 5 Press the [Yes] key.



7.3 User management settings

From the USER MANAGEMENT menu, the various functions which must be specified after the drum cartridge is replaced are available.

No.	Name	Description
1	CHANGE D/C	This function is used to specify when the drum cartridge will need to be replaced.



Detail

For details, refer to "Replacing the drum cartridge" on page 8-12.


Selecting the USER MANAGEMENT menu

- 1 Press the [Utility] three times.
USER MANAGEMENT appears.



- 2 Press the [Yes] key.
CHANGE D/C appears.

- 3 Press the [Yes] key.



7.4 Admin. management settings

From the ADMIN. MANAGEMENT menu, various functions for controlling the use of the machine can be set. In order to set an ADMIN. MANAGEMENT function, the administrator access number must be entered.

No.	ADMIN. MANAGE- MENT	Description
1	REMOTE MONITOR	This function can be used to set whether or not the machine can be accessed and the status of the machine can be checked from the service center. For details, consult with the service representative.




Note

The registering and setup of the administrator access number should be performed by the service representative. For details, contact the service representative.

The administrator of this machine should be sure not to lose the administrator access number.


Selecting the ADMIN. MANAGEMENT menu

- 1 Press the [Utility] key four times.
ADMIN. MANAGEMENT appears.
- 2 Press the [Yes] key.
- 3 From the 10-key pad, press the key [1] for the **ADMIN. MANAGEMENT** function that you wish to set.



The admin. management functions are as follows:
1 REMOTE MONITOR


- 4 Using the 10-key pad, enter the 6-digit administrator access number, and then press the [Yes] key.

**Note**


*If, at any time, you wish to quit setting an ADMIN. MANAGEMENT function, press the [No/C] key. When the message **STOP SETTING?** appears, press the [Yes] key to quit.*

Specifying REMOTE MONITOR

- 1 Select **REMOTE MONITOR** in the ADMIN. MANAGEMENT menu. For details refer to page 7-17.
- 2 Press the [◀] and [▶] keys to select either **LIMITED** or **FULL** or **OFF**.



- 3 Press the [Yes] key.
 - If **LIMITED** or **OFF** was selected, the ADMIN.MANAGEMENT menu appears again.
 - If **FULL** was selected, a screen appears allowing you to enter the password. Using the 10-key pad, enter the 4-digit password, and then press the [Yes] key.



7.5 Copy settings

When the machine is turned on or the [Panel reset] key is pressed, the machine is automatically reset to its initial mode. By changing the default settings, you can change the initial mode. Refer to the following table for the default settings for each function.

No.	Name	Description
1	PAPER PRIORITY	The tray that is given priority can be set to either "TRAY1" or "TRAY2". <ul style="list-style-type: none"> • Default setting: TRAY1.
2	DENSITY PRIORITY	The density that is selected when the machine is turned on or the [Panel reset] key is pressed can be set to "AUTO", "MANUAL" or "PHOTO". <ul style="list-style-type: none"> • Default setting: AUTO.
3	DENSITY LEVEL (A) (A): Auto	The default Auto density level setting can be set to "LIGHT (-1)", "NORMAL (0)" or "DARK (+1)". <ul style="list-style-type: none"> • Default setting: NORMAL (0).
4	DENSITY LEVEL (M) (M): Manual	The default manual density level setting can be set to one of nine levels between -4 and +4, with the normal print density at 0. If a smaller number (toward -) is selected, the print becomes lighter. If a larger number (toward +) is selected, the print becomes darker. <ul style="list-style-type: none"> • Default setting: NORMAL (0).
5	OUTPUT PRIORITY	The finishing setting that is selected when the machine is turned on or the [Panel reset] key is pressed can be set to "NON" or "SORT". <ul style="list-style-type: none"> • Default setting: NON.
6	RESOLUTION	The default resolution when scanning with the automatic document feeder can be set to "600 dpi × 300 dpi" or "600 dpi × 600 dpi". <ul style="list-style-type: none"> • Default setting: 600 dpi × 300 dpi.

Selecting the COPY SETTING menu

- 1 Press the [Utility] key five times.

COPY SETTING appears.


- 2 From the 10-key pad, press the key [1] to [6] for the copy setting function that you wish to set.

The copy setting functions are as follows:

- 1 PAPER PRIORITY
- 2 DENSITY PRIORITY
- 3 DENSITY LEVEL (A)
- 4 DENSITY LEVEL (M)
- 5 OUTPUT PRIORITY
- 6 RESOLUTION


? Do you want to quit changing the copy settings?

- Press the [No/C] key. **STOP SETTING?** appears. Press the [Yes] key to quit changing the settings.




Specifying PAPER PRIORITY

- 1 Select **PAPER PRIORITY** in the COPY SETTING menu. For details refer to page 7-22.
- 2 Press the [◀] and [▶] keys to select either **TRAY1** or **TRAY2**.
- 3 Press the [Yes] key.




Specifying DENSITY PRIORITY

- 1 Select **DENSITY PRIORITY** in the COPY SETTING menu.
For details refer to page 7-22.
- 2 Press the [◀] and [▶] keys to select either **AUTO**, **MANUAL** or **PHOTO**.
- 3 Press the [Yes] key.




Specifying DENSITY LEVEL (A)

- 1 Select **DENSITY LEVEL (A)** in the COPY SETTING menu. For details refer to page 7-22.
- 2 Press the [◀] and [▶] keys to select one of the three print density levels between **LIGHT** and **DARK**.
- 3 Press the [Yes] key.




Specifying DENSITY LEVEL (M)

- 1 Select **DENSITY LEVEL (M)** in the COPY SETTING menu. For details refer to page 7-22.
- 2 Press the [◀] and [▶] keys to select one of the nine print density levels between **LIGHT** and **DARK**.
- 3 Press the [Yes] key.




Specifying OUTPUT PRIORITY

- 1 Select **OUTPUT PRIORITY** in the COPY SETTING menu. For details refer to page 7-22.
- 2 Press the [◀] and [▶] keys to select either **NON** or **SORT**.
- 3 Press the [Yes] key.



Specifying RESOLUTION

- 1** Select **RESOLUTION** in the COPY SETTING menu.
For details refer to page 7-22.
- 2** Press the [◀] and [▶] keys to select either **600 × 300** or **600 × 600**.
- 3** Press the [Yes] key.



7.6 Fax registration settings

From the FAX REGISTRATION menu, various settings can be specified in order to take advantage of this machine's many fax functions.

No.	FAX REGISTRATION	Characteristic/Description
1	ONE-TOUCH DIAL	This function can be used to program one-touch dial keys with fax numbers, allowing the recipient to be specified easily and accurately without the need to manually enter the number using the 10-key pad. A maximum of 15 settings can be programmed. This dialing method is convenient for programming numbers where faxes are frequently sent to.
2	SPEED DIAL	This function can be used to program speed dial numbers with fax numbers, allowing the recipient to be specified easily and accurately without the need to manually enter the number using the 10-key pad. A maximum of 200 fax numbers can be programmed.
3	GROUP DIAL	This function can be used to program a single one-touch dial key with a maximum of 50 different fax numbers as one group. Programming a one-touch dial key with a group of fax numbers is convenient when documents are frequently sent to a set group of multiple recipients.
4	PROGRAM DIAL	This function can be used to program one-touch dial keys with fax numbers and a transmission/reception function (such as timer transmission or polling reception), allowing that function to be carried out by pressing just the corresponding one-touch dial key.
5	BATCH TX	This function can be used to specify the batch transmission setting (transmission time) for a one-touch dial key programmed with recipient fax numbers, so multiple documents can be stored in the memory and sent out together at the specified time.
6	MAILBOX	This function can be used to specify mailbox IDs in order to receive faxes with mailbox reception only if the mailbox ID sent by the caller matches the mailbox ID set on this machine.

Selecting the FAX REGISTRATION menu

- 1 Press the [Utility] key six times.
FAX REGISTRATION appears.
- 2 From the 10-key pad, press the key [1] through [6] for the fax registration function that you wish to set.


The fax registration functions are as follows:

- 1 ONE-TOUCH DIAL
- 2 SPEED DIAL
- 3 GROUP DIAL
- 4 PROGRAM DIAL
- 5 BATCH TX
- 6 MAILBOX



Note

*If, at any time, you wish to quit programming, changing or deleting a fax registration function, press the [No/C] key. When the message **STOP REGISTRATION?** appears, press the [Yes] key to quit.*



Specifying ONE-TOUCH DIAL

If the one-touch dial keys are programmed with fax numbers, the recipient can be specified easily and accurately without the need to manually enter the number using the 10-key pad.

A maximum of 15 numbers can be programmed.

To program a one-touch dial key

- 1** Select the **ONE-TOUCH DIAL** in the FAX REGISTRATION menu.
For details, refer to page 7-27.



- 2** Press the one-touch dial key that you wish to program.



- 3** Enter the name of the programmed number.


- For details on entering text, refer to "Entering Text" on page 3-23.
- Text up to 20 characters long can be entered for the name.



- 4** Press the [Yes] key.

- 5** Using the 10-key pad, enter the fax number of the recipient.

- The fax number can contain a maximum of 30 digits.
For details on the characters that can be entered. Refer to "To fax by entering the fax number directly using the 10-key pad" on page 5-3.
- To enter a SUB, continue with step 7.
- If a SUB will not be entered, press the [Yes] key after entering the fax number, and then skip to step 10.
- If you wish to change the fax number, press the [No/C] key, and then enter the correct number.
- For details on F codes (SUB and SID), refer to "Using F codes" on page 6-27.



- 6** Press the [▼] key, and then use the 10-key pad to enter the SUB.
- A number up to 20 digits long can be entered for the SUB.
 - To enter an SID, continue with step 8.
 - If an SID will not be entered, skip to step 9.

```
SUB=1234_
OK=YES      (SID=▼)
```

- 7** Press the [▼] key, and then use the 10-key pad to enter the SID.
- A number up to 20 digits long can be entered for the SID.

```
SID=5678_
OK=YES
```

- 8** Press the [Yes] key.

- 9** Using the [◀] and [▶] keys, select the desired modem speed.

```
SET MODEM SPEED
```

- 10** Press the [Yes] key.

The settings are registered. To program another one-touch dial key, repeat steps 3 through 11.

```
*33.6      14.4      9.6
◀,▶ & YES
```

- 11** Press the [No/C] key to finish programming.

The FAX REGISTRATION menu appears again.

```
-SELECT REGIST.KEY-
      (COMPLETE=NO)
```

To change/delete a programmed one-touch dial key

- 1 Select the **ONE-TOUCH DIAL** in the FAX REGISTRATION menu.
For details, refer to page 7-27.




- 2 Press the one-touch dial key that you wish to change or delete.




- 3 Press the [No/C] key.

- If a one-touch dial key programmed with a group of fax numbers or a transmission/reception function is pressed, the message shown at the right appears. To delete the programmed settings, press the [No/C] key. The FAX REGISTRATION menu appears again.
- To change the group dialing or program dialing settings, refer to page 7-36 and page 7-40.



- 4 Using the [◀] and [▶] keys, select either **EDIT** or **DELETE**, and then press the [Yes] key.



- If **EDIT** was selected, the name is displayed. (Continue with step 6.)
- If **DELETE** was selected, the settings programmed for the one-touch dial key are deleted and the **SELECT REGIST.KEY** screen appears again.
- If you try to change the settings for a one-touch dial number used in group dialing or program dialing, a confirmation message appears, asking whether or not to change the corresponding settings programmed in group dialing or program dialing.
 - If the [Yes] key is pressed, the corresponding settings programmed in group dialing or program dialing are changed.
 - If the [No/C] key is pressed, the corresponding settings programmed in group dialing or program dialing are deleted.
- If a one-touch dial number used in group dialing or program dialing is deleted, it is also deleted from the corresponding group dialing or program dialing.

- 5 Change the name, fax number, F codes (SUB and SID) and modem speed as desired.



NAME=AAA TOKYO_
OK=YES [1]

- For details on changing the fax number, refer to “Entering Text” on page 3-23.
- For details on changing the F codes (SUB and SID) or modem speed, refer to p. 7-28.

- 6 When you are finished making changes, press the [Yes] key.

To change the settings of another one-touch dial key, repeat steps 3 through 7.

- 7 Press the [No/C] key to return to the FAX REGISTRATION menu.



-SELECT REGIST.KEY-
(COMPLETE=NO)


Specifying SPEED DIAL

If speed dial numbers are programmed with fax numbers, the recipient can be specified easily and accurately without the need to manually enter the number using the 10-key pad.


A maximum of 200 fax numbers (001 to 200) can be programmed.

To program a speed dial number

- 1 Select the **SPEED DIAL** in the FAX REGISTRATION menu.
For details, refer to page 7-27.




- 2 Using the 10-key pad, enter the 3-digit speed dial number (ex. 011) that you wish to program.



- 3 Enter the name of the programmed number.


- For details on entering text, refer to "Entering Text" on page 3-23.
- Text up to 20 characters long can be entered for the name.



- 4 Press the [Yes] key.

- 5 Using the 10-key pad, enter the fax number of the recipient.

- The fax number can contain a maximum of 30 digits.
For details on the characters that can be entered. Refer to "To fax by entering the fax number directly using the 10-key pad" on page 5-3.
- To enter a SUB, continue with step 7.
- If a SUB will not be entered, press the [Yes] key after entering the fax number, and then skip to step 10.
- If you wish to change the fax number, press the [No/C] key, and then enter the correct number.
- For details on F codes (SUB and SID), refer to "Using F codes" on page 6-27.



- 6** Press the [▼] key, and then use the 10-key pad to enter the SUB.

- A number up to 20 digits long can be entered for the SUB.
- To enter an SID, continue with step 8.
- If an SID will not be entered, skip to step 9.

```
SUB=1234_
OK=YES      (SID=▼)
```

- 7** Press the [▼] key, and then use the 10-key pad to enter the SID.

- A number up to 20 digits long can be entered for the SID.

```
SID=5678_
OK=YES
```

- 8** Press the [Yes] key.

- 9** Using the [◀] and [▶] keys, select the desired modem speed.

- 10** Press the [Yes] key.

- The settings are registered.
To program another speed dial number, repeat steps 3 through 11.

```
SET MODEM SPEED
```

```
*33.6      14.4      9.6
◀,▶ & YES
```

- 11** Press the [No/C] key to finish programming.

- The FAX REGISTRATION menu appears again.


```
SPEED DIAL=_
(COMPLETE=NO)
```

To change/delete a programmed speed dial number

- 1** Select the **SPEED DIAL** in the FAX REGISTRATION menu.
For details, refer to page 7-27.




- 2** Using the 10-key pad, enter the speed dial number that you wish to change or delete.



- 3** Press the [No/C] key.




- 4** Using the [◀] and [▶] keys, select either **EDIT** or **DELETE**, and then press the [Yes] key.



- If **EDIT** was selected, the name is displayed. (Continue with step 6.)
- If **DELETE** was selected, the settings programmed for the speed dial number are deleted and the speed dial input screen appears again.
- If you try to change the settings for a speed dial number used in group dialing or program dialing, a confirmation message appears, asking whether or not to change the corresponding settings programmed in group dialing or program dialing.
If the [Yes] key is pressed, the corresponding settings programmed in group dialing or program dialing are changed.
If the [No/C] key is pressed, the corresponding settings programmed in group dialing or program dialing are deleted.
- If a speed dial number used in group dialing or program dialing is deleted, it is also deleted from the corresponding group dialing or program dialing.

- 5 Change the fax number, F codes (SUB and SID), and modem speed as desired.




```
NAME=AAA OSAKA_  
OK=YES [1]
```

- For details on making changes, refer to “Entering Text” on page 3-23.
- For details on changing the F codes (SUB and SID) or modem speed, refer to p. 7-28.

- 6 When you are finished making changes, press the [Yes] key.

- To change the settings of another speed dial number, repeat steps 3 through 7.

- 7 Press the [No/C] key to return to the FAX REGISTRATION menu.



```
SPEED DIAL=_  
(COMPLETE=NO)
```

Specifying GROUP DIAL

A single one-touch dial key can be programmed with a maximum of 50 different fax numbers as one group. Programming a one-touch dial key with a group of fax numbers is convenient when documents are frequently sent to a set group of multiple recipients.

To program a group of fax numbers


- 1 Select the **GROUP DIAL** in the FAX REGISTRATION menu.
For details, refer to page 7-27.




- 2 Press the one-touch dial key that you wish to program.



- 3 Enter the name of the group, and then press the [Yes] key.
 - For details on entering text, refer to "Entering Text" on page 3-23.
 - Text up to 20 characters long can be entered for the name.




- 4 By using the one-touch dial keys or the speed dial numbers, specify the recipients.



- ? Do you wish to cancel the current selection?


→ Press the [No/C] key, and then specify the correct recipient.

- 5 Press the [Yes] key, and then specify another recipient.



- Repeat steps 5 and 6 until all recipients have been specified.
- A maximum of 50 different fax numbers can be specified as one group.
- With group dialing, a one-touch dial key programmed with a group can be specified. In that case, the number of fax numbers programmed in the specified one-touch dial key (group dial key) is added.

- 6** When you are finished specifying recipients, press the [Start] key.
The settings are registered.
To program another group, repeat steps 3 through 7.



NO.005=_
(Fin.=START)

- 7** Press the [No/C] key to finish programming.
The FAX REGISTRATION menu appears again.



-SELECT REGIST.KEY-
(COMPLETE=NO)

To change/delete a programmed group of fax numbers


- 1** Select the **GROUP DIAL** in the FAX REGISTRATION menu.
For details, refer to page 7-27.




- 2** Press the one-touch dial key that you wish to change or delete.



- 3** Press the [No/C] key.




- 4** Using the [◀] and [▶] keys, select either **EDIT** or **DELETE**, and then press the [Yes] key.



- If **EDIT** was selected, the group name is displayed. (Continue with step 6.)
- If **DELETE** was selected, the group dialing settings are deleted and the **SELECT REGIST.KEY** screen appears again.

- 5** If you wish to change the name of the group, enter the new name, and then press the [Yes] key.



- For details on making changes, refer to "Entering Text" on page 3-23.


The one-touch dial names are displayed in the order that they were specified.

- 6** To delete the displayed recipient, press the [No/C] key.
To keep the displayed recipient, press the [Yes] key.



The next one-touch dial name is displayed.

- 7** When you are finished making changes, press the [Start] key.
To change the settings of another group of fax numbers, repeat steps 3 through 8.



NO. 005=_
(Fin.=START)

- 8** Press the [No/C] key to return to the FAX REGISTRATION menu.



-SELECT REGIST.KEY-
(COMPLETE=NO)

Specifying PROGRAM DIAL

If one-touch dial keys have been programmed with fax numbers and a transmission/reception function, that function can be carried out by pressing just the corresponding one-touch dial key.

Transmission/reception functions that can be programmed:

- Broadcast transmission
- Timer transmission
- Mailbox transmission
- Polling reception
- Relay initiation transmission

To set program dialing


- 1 Select the **PROGRAM DIAL** in the FAX REGISTRATION menu.
For details, refer to page 7-27.



- 2 Press the one-touch dial key ([12] through [15]) programmed with the desired function.



- 3 From the 10-key pad, press the key ([1] through [3], [6] or [7]) for the desired function.



Functions that can be selected:

- 1 BROADCAST
- 2 TIMER TX
- 3 MAILBOX TX
- 6 POLLING RX
- 7 RELAY INITIATE

- 4 Follow the instructions for the selected function.
 - “To fax using broadcast transmission” on page 6-9
 - “To fax using timer transmission” on page 6-12
 - “To fax using mailbox transmission” on page 6-14
 - “To fax using relay initiation transmission” on page 6-16
 - “To receive a fax using polling reception” on page 6-25

The settings are registered.

- 5 To specify other program dialing settings, repeat steps 3 through 5.


- 6** Press the [No/C] key to finish programming.
The FAX REGISTRATION menu appears again.





-SELECT REGIST.KEY-
(COMPLETE=NO)


To change/delete a programmed broadcast transmission


- 1** Select the **PROGRAM DIAL** in the FAX REGISTRATION menu.
For details, refer to page 7-27.



- 2** Press the one-touch dial key ([12] through [15]) programmed with the broadcast transmission that you wish to change or delete.



- 3** Press the [No/C] key.


- 4** Using the [◀] and [▶] keys, select either **EDIT** or **DELETE**, and then press the [Yes] key.

 - If **EDIT** was selected, the specified recipients are displayed in order. (Continue with step 6.)
 - If **DELETE** was selected, the program dialing settings are deleted and the **SELECT REGIST.KEY** appears again.
- 5** To delete the displayed recipient, press the [No/C] key.
To keep the displayed recipient, press the [Yes] key.
The next recipient is displayed.



- 6** When you are finished making changes, press the [Start] key.


 - Other program dialing settings can be programmed or changed.
- 7** Press the [No/C] key to return to the FAX REGISTRATION menu.





To change/delete a programmed timer transmission

- 1** Select the **PROGRAM DIAL** in the FAX REGISTRATION menu.
For details, refer to page 7-27.



- 2** Press the one-touch dial key ([12] through [15]) programmed with the timer transmission that you wish to change or delete.



- 3** Press the [No/C] key.


- 4** Using the [◀] and [▶] keys, select either **EDIT** or **DELETE**, and then press the [Yes] key.

 - If **EDIT** was selected, the programmed transmission time is displayed. (Continue with step 6.)
 - If **DELETE** was selected, the program dialing settings are deleted and the **SELECT REGIST.KEY** screen appears again.
- 5** To change the transmission time, press the [No/C] key, and then use the 10-key pad to enter the correct time. If you do not wish to change the transmission time, press the [Yes] key.

The recipient is displayed.


- 6** To change the recipient, press the [No/C] key, and then by using the one-touch dial keys or the speed dial numbers, or by entering the fax number using the 10-key pad, specify a different recipient.


 - Change the F codes (SUB and SID) as desired.


- 7 Press the [Yes] key.
 - Other program dialing settings can be changed.
- 8 Press the [No/C] key to return to the FAX REGISTRATION menu.


-SELECT REGIST.KEY-
(COMPLETE=NO)


To change/delete a programmed mailbox transmission


- 1** Select the **PROGRAM DIAL** in the FAX REGISTRATION menu.
For details, refer to page 7-27.



- 2** Press the one-touch dial key ([12] through [15]) programmed with the mailbox transmission that you wish to change or delete.


- 3** Press the [No/C] key.



- 4** Using the [◀] and [▶] keys, select either **EDIT** or **DELETE**, and then press the [Yes] key.

 - If **EDIT** was selected, the specified recipient is displayed. (Continue with step 6.)
 - If **DELETE** was selected, the program dialing settings are deleted and the **SELECT REGIST.KEY** screen appears again.
- 5** To change the recipient, press the [No/C] key, and then by using the one-touch dial keys or the speed dial numbers, or by entering the fax number using the 10-key pad, specify a different recipient.


- 6** Press the [Yes] key.
The mailbox ID is displayed.
- 7** To change the mailbox ID, press the [No/C] key, and then use the 10-key pad to enter the new ID.


- 8** Press the [Yes] key.
The password is displayed.

- 9** To change the password, press the [No/C] key, and then use the 10-key pad to enter the new password.



PASSWORD=5678
OK=YES (DEL=NO)

- 10** Press the [Yes] key.

Other program dialing settings can be changed.


- 11** Press the [No/C] key to return to the FAX REGISTRATION menu.





-SELECT REGIST.KEY-
(COMPLETE=NO)


To change/delete a programmed polling reception


- 1** Select the **PROGRAM DIAL** in the FAX REGISTRATION menu.
For details, refer to page 7-27.



- 2** Press the one-touch dial key ([12] through [15]) programmed with the polling reception that you wish to change or delete.


- 3** Press the [No/C] key.


- 4** Using the [◀] and [▶] keys, select either "EDIT" or "DELETE", and then press the [Yes] key.

 - If **EDIT** was selected, the specified recipients are displayed in order. (Continue with step 6.)
 - If **DELETE** was selected, the program dialing settings are deleted and the **SELECT REGIST.KEY** screen appears again.
- 5** To delete the displayed recipient, press the [No/C] key.
To keep the displayed recipient, press the [Yes] key.

 - To add a recipient, in the screen containing **Fin.=START**, specify a recipient using the one-touch dial keys or the speed dial numbers, or by entering a fax number using the 10-key pad.
The next recipient is displayed.
- 6** When you are finished making changes, press the [Start] key.
Other program dialing settings can be changed.





- 7 Press the [No/C] key to return to the FAX REGISTRATION menu.


-SELECT REGIST. KEY -
(COMPLETE=NO)


To change/delete a programmed relay initiation transmission


- 1** Select the **PROGRAM DIAL** in the FAX REGISTRATION menu.
For details, refer to page 7-27.



- 2** Press the one-touch dial key ([12] through [15]) programmed with the relay initiation transmission that you wish to change or delete.


- 3** Press the [No/C] key.



- 4** Using the [◀] and [▶] keys, select either **EDIT** or **DELETE**, and then press the [Yes] key.

 - If **EDIT** was selected, the specified recipient is displayed. (Continue with step 6.)
 - If **DELETE** was selected, the program dialing settings are deleted and the **SELECT REGIST.KEY** screen appears again.
- 5** To change the recipient, press the [No/C] key, and then by using the one-touch dial keys or the speed dial numbers, or by entering the fax number using the 10-key pad, specify a different recipient.


- 6** Press the [Yes] key.
The relay box ID is displayed.
- 7** To change the relay box ID, press the [No/C] key, and then use the 10-key pad to enter the new ID.


- 8** Press the [Yes] key.
The password is displayed.

- 9** To change the password, press the [No/C] key, and then use the 10-key pad to enter the new password.



PASSWORD=5678
OK=YES (DEL=NO)

- 10** Press the [Yes] key.

Other program dialing settings can be changed.

- 11** Press the [No/C] key to return to the FAX REGISTRATION menu.



-SELECT REGIST.KEY-
(COMPLETE=NO)

Specifying BATCH TX

If the batch transmission setting (transmission time) is specified for a one-touch dial key programmed with recipient fax numbers, multiple documents can be stored in the memory and sent out together at the specified time.




Note

A one-touch dial key must first be programmed with the fax number of the recipient for the batch transmission.

To set batch transmitting

- 1 Select the **BATCH TX** in the FAX REGISTRATION menu.
For details, refer to page 7-27.




- 2 Press the one-touch dial key programmed with the recipient that you wish to send the batch transmission fax to.




A screen appears, allowing you to specify the transmission time.

- ? Was the one-touch dial key that was pressed one programmed for group dialing, program dialing, or not registered fax number, or not programmed at all?

→ An error message appears.



- 3 Using the 10-key pad, enter the desired transmission time, and then press the [Yes] key.



- 4 Press the [No/C] key to return to the FAX REGISTRATION menu.

-SELECT REGIST. KEY -
(COMPLETE=NO)

To change the batch transmission setting


- 1** Select the **BATCH TX** in the FAX REGISTRATION menu.
For details, refer to page 7-27.
- 2** Press the one-touch dial key programmed with the batch transmission setting that you wish to change.
- 3** Press the [No/C] key, and then use the 10-key pad to enter the new transmission time.
- 4** When you are finished making changes, press the [Yes] key.
- 5** Press the [No/C] key to return to the FAX REGISTRATION menu.




5 BATCH TX



-SELECT REGIST.KEY-



TX TIME=15:30
OK=YES (DEL=NO)






TX TIME=06:30
OK=YES (DEL=NO)



-SELECT REGIST.KEY-
(COMPLETE=NO)

To delete the batch transmission setting

- 1** Select the **BATCH TX** in the FAX REGISTRATION menu.
For details, refer to page 7-27.
- 2** Press the one-touch dial key programmed with the batch transmission setting that you wish to delete.
- 3** Press the [No/C] key.
A confirmation message appears, asking whether or not to delete the batch transmission setting.
- 4** Press the [Yes] key.
The **SELECT REGIST.KEY** screen appears again.



Specifying MAILBOX

Mailbox IDs must first be specified in order to receive faxes with mailbox reception only if the mailbox ID sent by the caller matches the mailbox ID set on this machine.





Note


A mailbox ID cannot be the same as a relay box ID.


To register a mailbox

- 1** Select the **MAILBOX** in the FAX REGISTRATION menu.
For details, refer to page 7-27.


- 2** Using the 10-key pad, enter the mailbox number.

 - The mailbox number can be set to any number between 1 and 5.
- 3** Using the 10-key pad, enter the 4-digit mailbox ID, and then press the [Yes] key.

 - The mailbox ID can be set to any number between 0000 and 9999.
 - If you wish to change the mailbox ID, press the [No/C] key, and then enter the new number.
- 4** Using the 10-key pad, enter the 4-digit password, and then press the [Yes] key.

 - The password can be set to any number between 0000 and 9999.
 - If you wish to change the password, press the [No/C] key, and then enter the new password.
 - If no password is to be specified, press the [Yes] key without entering anything.

The FAX REGISTRATION menu appears again.

To delete a mailbox

- 1** Select the **MAILBOX** in the FAX REGISTRATION menu.
For details, refer to page 7-27.



6 MAILBOX

- 2** Using the 10-key pad, enter the number of the mailbox that you wish to delete.




MAILBOX NO.=
SELECT 1-5

- 3** Press the [No/C] key.
A screen appears, allowing you to enter the mailbox ID.



REGISTERED! KEEP?
KEEP=YES (DEL=NO)

- 4** Using the 10-key pad, enter the 4-digit mailbox ID, and then press the [Yes] key.



OLD M-BOX5 ID=1234
OK=YES

- If you wish to change the ID, press the [No/C] key, and then enter the new number.
- The specified mailbox is deleted.

- 5** Press the [Panel Reset] key.
The main screen appears again.



MAILBOX NO.=
SELECT 1-5


7.7 TX operation settings

From the TX OPERATION menu, various functions for sending faxes can be set.

No.	TX OPERATION	Characteristic/Description
1	SCAN CONTRAST	This function can be used to set the default scanning contrast level to one of five settings between "LIGHT" and "DARK". For dark-colored paper (media), select a setting towards "LIGHT". For faint or colored text, select a setting toward "DARK".
2	RESOLUTION	This function can be used to set the default scanning resolution (image quality) to one of the following: "Standard", "Fine", "Super Fine", "Half Tone + Standard", "Half Tone + Fine" or "Half Tone + Super Fine". <ul style="list-style-type: none"> • Default setting: Standard.
3	DEFAULT TX	This function can be used to set the default transmission mode to "MEM.TX" or "ADF TX". MEM.TX: memory transmission ADF TX: direct transmission <ul style="list-style-type: none"> • Default setting: MEM.TX.
4	HEADER	This function can be used to set the default setting ("ON" or "OFF") for adding the header (date sent, sender's name and fax number, etc.) when sending faxes. <ul style="list-style-type: none"> • Default setting: ON.

Selecting the TX OPERATION menu

- 1 Press the [Utility] key seven times.
TX OPERATION appears.



- 2 From the 10-key pad, press the key ([1] through [4]) for the TX operation function that you wish to set.

The TX operation functions are as follows:

- 1 SCAN CONTRAST
- 2 RESOLUTION
- 3 DEFAULT TX
- 4 HEADER



Note


If, at any time, you wish to quit setting a TX operation function, press the [No/C] key. When the message STOP SETTING? appears, press the [Yes] key to quit.

Specifying SCAN CONTRAST

- 1 Select the **SCAN CONTRAST** in the TX OPERATION menu.
For details, refer to page 7-58.



- 2 Using the [◀] and [▶] keys, select one of the five settings between **LIGHT** and **DARK**, and then press the [Yes] key.



The TX OPERATION menu appears again.

Specifying RESOLUTION

- 1** Select the **RESOLUTION** in the TX OPERATION menu.
For details, refer to page 7-58.



2 RESOLUTION

- 2** Using the [◀] and [▶] keys, select the desired resolution setting, and then press the [Yes] key.



*STD FINE S/F H/T
◀, ▶ & YES

The resolution settings appear as follows.

STD: Standard
FINE: Fine
S/F: Super Fine
H/T: Half Tone

If **H/T** was selected, a screen appears, allowing you to make a detailed setting. (Continue with step 4.)

If any setting other than **H/T** was selected, the TX OPERATION menu appears again.

- 3** Using the [◀] and [▶] keys, select the desired halftone setting, and then press the [Yes] key.



*STD FINE S/F
◀, ▶ & YES


The halftone settings appear as follows.

STD: Standard
FINE: Fine
S/F: Super Fine

The TX OPERATION menu appears again.


Specifying DEFAULT TX

- 1 Select the **DEFAULT TX** in the TX OPERATION menu.
For details, refer to page 7-58.




- 2 Using the [◀] and [▶] keys, select either **MEM.TX** or **ADF TX**, and then press the [Yes] key.

The TX OPERATION menu appears again.




Specifying HEADER

- 1 Select the **HEADER** in the TX OPERATION menu.
For details, refer to page 7-58.



- 2 Using the [◀] and [▶] keys, select either **ON** or **OFF**, and then press the [Yes] key.

The TX OPERATION menu appears again.



7.8 RX operation settings

From the RX OPERATION menu, various functions for receiving faxes can be set.

No.	RX OPERATION	Characteristic/Description
1	MEMORY RX MODE	<p>This function can be used to set whether to allow ("ON") memory reception or not ("OFF"). In cases when confidential faxes are being received, the received document can be stored in the memory and printed at a specified time or when memory reception is set to "OFF".</p> <p>A password can be set to specify the starting time or ending time of memory reception, or to cancel the function. The set starting time and ending time are valid every day until memory reception is turned off.</p> <ul style="list-style-type: none"> • Default setting: OFF.
2	NO. of RINGS	<p>This function can be used to set the number of rings between 1 and 16 until the call is answered.</p>
3	REDUCTION RX	<p>This function can be used to set whether documents longer than the paper are printed reduced ("ON"), split ("OFF"), or discarded ("CUT").</p> <p>However, when sending a document more than 24 mm (1 inch) longer than the paper, "CUT" is not available. (In this case, the document is split.)</p> <ul style="list-style-type: none"> • Default setting: ON.
4	RX PRINT	<p>This function can be used to set whether the fax is only printed after all document pages have been received ("MEMORY RX") or printing begins as soon as the first page of the document is received ("PRINT RX").</p> <ul style="list-style-type: none"> • Default setting is MEMORY RX.
5	RX MODE	<p>This function can be used to set the reception mode to automatic reception ("AUTO RX") or manual reception ("MANUAL RX").</p> <p>Automatic reception: Automatically begins receiving after the set number of rings.</p> <p>Manual reception: Does not automatically receive the fax. Reception begins after making a connection by picking up the telephone receiver or pressing the [Speaker] key, then pressing the [Start] key.</p> <ul style="list-style-type: none"> • Default setting: AUTO RX.
6	FORWARD	<p>This function can be used to set whether or not the received document is forwarded.</p> <p>Forward ("ON"): The received document is forwarded to the specified fax number or e-mail address.</p> <p>Forward and print ("ON(PRINT)"): The received document is printed by this machine at the same time that it is forwarded to the specified fax number or e-mail address.</p> <p>Do not forward ("OFF"): The document is not forwarded</p> <ul style="list-style-type: none"> • Default setting: OFF. <p>*In order to forward the document to an e-mail address, the optional scanner unit SU-502 is required.</p>
7	FOOTER	<p>This function can be used to set whether or not the reception information (date received, number of pages, etc.) is printed at the bottom of each received document.</p> <ul style="list-style-type: none"> • Default setting: OFF.

No.	RX OPERATION	Characteristic/Description
8	SELECT TRAY	This function can be used to select which paper tray can be used to supply paper when printing received documents or transmission reports. (A paper tray that cannot be used for supplying paper can also be specified.)
9	CLOSED NET-WORK	This function can be used to set whether or not the fax is received if the sender's fax number does not match the fax number programmed in this machine's one-touch dial keys and speed dials. <ul style="list-style-type: none"><li data-bbox="449 331 645 355">• Default setting: OFF.

Selecting the RX OPERATION menu

- 1 Press the [Utility] key eight times.
RX OPERATION appears.
- 2 From the 10-key pad, press the key ([1] through [9]) for the RX operation function that you wish to set.

The RX operation functions are as follows:


- 1 MEMORY RX MODE
- 2 NO. of RINGS
- 3 REDUCTION RX
- 4 RX PRINT
- 5 RX MODE
- 6 FORWARD
- 7 FOOTER
- 8 SELECT TRAY
- 9 CLOSED NETWORK



Note

*If, at any time, you wish to quit setting/changing an RX operation function, press the [No/C] key. When the message **STOP SETTING?** appears, press the [Yes] key to quit.*

To exit the RX OPERATION menu, press the [Panel reset] key. The main screen appears again.



Specifying MEMORY RX MODE

- 1 Select the **MEMORY RX MODE** in the RX OPERATION menu.
For details, refer to page 7-63.



```
1 MEMORY RX MODE
```

- 2 Using the [◀] and [▶] keys, select **ON**, and then press the [Yes] key.



```
*ON OFF
◀, ▶ & YES
```


- 3 Using the 10-key pad, enter the time for memory reception to begin, and then press the [Yes] key.



```
ON TIME=20:00
OK=YES
```

- To specify that memory reception stays on from the time that it is set to **ON** until it is manually canceled, press the [Yes] without entering a start time. (Skip to step 6.)

- 4 Using the 10-key pad, enter the time for memory reception to end, and then press the [Yes] key.



```
OFF TIME=09:00
OK=YES
```

- 5 Using the 10-key pad, enter the 4-digit password used to cancel memory reception, and then press the [Yes] key.



```
PASSWORD=5678
OK=YES
```

- If no password is to be specified, press the [Yes] key without entering anything.

The RX OPERATION menu appears again.

To cancel memory reception

Memory reception is automatically canceled at the specified ending time, and the received documents are printed. If no ending time has been set or if you wish to cancel memory reception before the ending time, follow the procedure described below.

- 1 Select the **MEMORY RX MODE** in the RX OPERATION menu.
For details, refer to page 7-63.



1 MEMORY RX MODE

- 2 Using the [◀] and [▶] keys, select "OFF", and then press the [Yes] key.
 - If a password was specified, continue with step 4.
 - If a password was not specified, all received documents stored in the memory are printed, and the RX OPERATION menu appears again.



ON *OFF
◀, ▶ & YES

- 3 Using the 10-key pad, enter the 4-digit password, and then press the [Yes] key.




PASSWORD=5678
OK=YES

All received documents stored in the memory are printed, and the RX OPERATION menu appears again.


Specifying NO. of RINGS

- 1 Select the **NO. of RINGS** in the RX OPERATION menu.
For details, refer to page 7-63.



2 NO. of RINGS

- 2 Using the 10-key pad, enter the desired number of rings, and then press the [Yes] key.
 - The number of rings can be set between 1 and 16.



NO. of RINGS= 2(1-16)
OK=YES


The RX OPERATION menu appears again.

Specifying REDUCTION RX

- 1 Select the **REDUCTION RX** in the RX OPERATION menu.
For details, refer to page 7-63.



- 2 Using the [◀] and [▶] keys, select **ON** (print the document reduced), **OFF** (split the printout) or **CUT** (discard any excess), and then press the [Yes] key.




The RX OPERATION menu appears again.

Specifying RX PRINT

- 1 Select the **RX PRINT** in the RX OPERATION menu.
For details, refer to page 7-63.




- 2 Using the [◀] and [▶] keys, select either **MEMORY RX** or **PRINT RX**, and then press the [Yes] key.




The RX OPERATION menu appears again.

Specifying RX MODE

- 1 Select the **RX MODE** in the RX OPERATION menu.
For details, refer to page 7-63.



- 2 Using the [◀] and [▶] keys, select either **AUTO RX** or **MANUAL RX**, and then press the [Yes] key.



The RX OPERATION menu appears again.

Specifying FORWARD

- 1 Select the **FORWARD** in the RX OPERATION menu.
For details, refer to page 7-63.



6 FORWARD


- 2 Using the [◀] and [▶] keys, select **ON**, **ON(PRINT)** or **OFF**, and then press the [Yes] key.



ON ON(PRINT) *OFF
◀, ▶ & YES

- If **ON** or **ON(PRINT)** was selected, a screen appears, allowing you to specify the forwarding location. (Continue with step 4.)
- If **OFF** was selected, the RX OPERATION menu appears again.

- 3 Using the one-touch dial keys or the speed dial numbers, or by entering the fax number using the 10-key pad, specify a fax number, and then press the [Yes] key.



☎=0123456_
OK=YES (SUB=▼)

The RX OPERATION menu appears again.



...

Note

An e-mail address can be specified as a forwarding location only when the optional scanner unit SU-502 is installed.

For details, refer to the user manual for the scanner unit SU-502.


Specifying FOOTER

- 1 Select the **FOOTER** in the RX OPERATION menu.
For details, refer to page 7-63.




- 2 Using the [◀] and [▶] keys, select either **ON** or **OFF**, and then press the [Yes] key.

The RX OPERATION menu appears again.



Specifying SELECT TRAY

- 1 Select the **SELECT TRAY** in the RX OPERATION menu.
For details, refer to page 7-63.




- 2 Using the [▲] and [▼] keys, select a paper tray, and then press the [Yes] key.



- 3 Using the [◀] and [▶] keys, select either **DISABLE** or **ENABLE**, and then press the [Yes] key.

The RX OPERATION menu appears again.




Specifying CLOSED NETWORK

- 1 Select the **CLOSED NETWORK** in the RX OPERATION menu.
For details, refer to page 7-63.



- 2 Using the [◀] and [▶] keys, select either **ON** or **OFF**, and then press the [Yes] key.

The RX OPERATION menu appears again.



7.9 Communication settings

From the COMM.SETTING menu, various functions are available for specifying communication settings.

No.	COMM.SETTING	Characteristic/Description
1	TONE/PULSE	This function can be used to specify the dialing system. If this function is not correctly set to the type of dialing system used, faxes cannot be sent. Select the correct setting after checking which type of dialing system is used by your telephone line.
2	LINE MONITOR	This function can be used to set the volume when monitoring communication to "HIGH", "LOW" or "OFF". <ul style="list-style-type: none"> • Default setting: LOW.
3	PSTN/PBX	This function can be used to set whether the connected telephone wiring is a public switched telephone network (PSTN) or a private branch exchange (PBX). For a PBX system, the outside line access number (or extension number) must be specified.

Selecting the COMM. SETTING menu

- 1 Press the [Utility] key nine times.
COMM. SETTING appears.
- 2 From the 10-key pad, press the key ([1] through [3]) for the communication setting function that you wish to set.

The communication setting functions are as follows:


- 1 TONE/PULSE
- 2 LINE MONITOR
- 3 PSTN/PBX



Note

*If, at any time, you wish to quit setting/changing an communication setting function, press the [No/C] key. When the message **STOP SETTING?** appears, press the [Yes] key to quit.*

To exit the COMM. SETTING menu, press the [Panel reset] key. The main screen appears again.




Specifying TONE/PULSE


There are two types of telephone dialing systems: tone dialing (PB) and pulse dialing (DP10pps or DP20pps). Faxes cannot be sent if this machine is not set to the system used by your telephone line. Select the correct setting after checking which type of dialing system is used.

To specify the telephone dialing system


- 1 Select the **TONE/PULSE** in the **COMM. SETTING** menu.
For details, refer to page 7-70.



- 2 Using the [◀] and [▶] keys, select either **TONE** (for tone dialing) or **PULSE** (for pulse dialing), and then press the [Yes] key.



- 3 If **PULSE** was selected, select either **10pps** or **20pps**, and then press the [Yes] key.




The **COMM.SETTING** menu appears again.

Specifying LINE MONITOR

- 1 Select the **LINE MONITOR** in the **COMM. SETTING** menu.
For details, refer to page 7-70.



- 2 Using the [◀] and [▶] keys, select **HIGH**, **LOW** or **OFF**, and then press the [Yes] key.



The **COMM.SETTING** menu appears again.

Specifying PSTN/PBX

The connected wiring system can be set to either PSTN (Public Switched Telephone Network) or PBX (Private Branch Exchange).

For a PBX system, the outside line access number (or extension number) must be specified. The outside line access number (or extension number) is programmed in the [#] key.

To specify the telephone wiring system

- 1 Select the **PSTN/PBX** in the COMM.SETTING menu.
For details, refer to page 7-70.



3 PSTN/PBX

- 2 Using the [◀] and [▶] keys, select either **PSTN** (Public Switched Telephone Network) or **PBX** (Private Branch Exchange), and then press the [Yes] key.



*PSTN PBX
←, → & YES

- 3 If **PBX** was selected, use the 10-key pad to enter the number that should be dialed to access the outside line, and then press the [Yes] key.



PRE-FIX NO.=1_
OK=YES

The COMM.SETTING menu appears again.

7.10 Reporting settings

From the REPORTING menu, various functions are available for specifying which reports are automatically printed.

No.	REPORTING	Characteristic/Description
1	ACTIVITY REPORT	Every 60 transmissions/receptions, a report can be printed to show the results of the transmissions/receptions. This function can be used to set whether the report is printed automatically when the 60th transmission/reception is reached. <ul style="list-style-type: none"> • Default setting: ON.
2	RESERV.REPORT	If multiple recipients are specified for transmission, such as with broadcast transmission and polling reception, a report can be printed to show specified settings. This function can be used to set whether this report is printed automatically. <ul style="list-style-type: none"> • Default setting: OFF.
3	TX RESULT REPORT	This function can be used to set whether the report showing the result of a transmission is printed automatically after the transmission is finished. <ul style="list-style-type: none"> • Default setting: OFF.
4	RX RESULT REPORT	This function can be used to set whether the report showing the result of a reception is printed automatically after mailbox reception is finished. (If regular reception is not finished normally, a report will always be printed, regardless of the selected setting.) <ul style="list-style-type: none"> • Default setting: OFF.

Selecting the REPORTING menu

- 1 Press the [Utility] key ten times.
REPORTING appears.
- 2 From the 10-key pad, press the key ([1] through [4]) for the reporting function that you wish to set.

The reporting functions are as follows:


- 1 ACTIVITY REPORT
- 2 RESERV.REPORT
- 3 TX RESULT REPORT
- 4 RX RESULT REPORT



Note

*If, at any time, you wish to quit setting/changing a reporting function, press the [No/C] key. When the message **STOP SETTING?** appears, press the [Yes] key to quit.*


*To exit the **REPORTING** menu, press the [Panel reset] key. The main screen appears again.*



Specifying ACTIVITY REPORT

- 1 Select the **ACTIVITY REPORT** in the **REPORTING** menu.
For details, refer to page 7-75.
- 2 Using the [◀] and [▶] keys, select either **ON** or **OFF**, and then press the [Yes] key.

The **REPORTING** menu appears again.




Specifying RESERV.REPORT

- 1 Select the **RESERV. REPORT** in the REPORTING menu.
For details, refer to page 7-75.




- 2 Using the [◀] and [▶] keys, select either **ON** or **OFF**, and then press the [Yes] key.

The REPORTING menu appears again.




Specifying TX RESULT REPORT

- 1 Select the **TX RESULT REPORT** in the REPORTING menu.
For details, refer to page 7-75.




- 2 Using the [◀] and [▶] keys, select either **ON** or **OFF**, and then press the [Yes] key.

The REPORTING menu appears again.




Specifying RX RESULT REPORT

- 1 Select the **RX RESULT REPORT** in the REPORTING menu.
For details, refer to page 7-75.



- 2 Using the [◀] and [▶] keys, select either **ON** or **OFF**, and then press the [Yes] key.

The REPORTING menu appears again.




7.11 Initial user data settings

From the INITIAL USER DATA menu, various functions are available for specifying the machine's user data.

No.	Initial user data	Description
1	DATE&TIME	The date and time for the machine can be specified.
2	USER FAX NO.	The fax number for the machine can be specified.
3	USER NAME	The fax name for the machine can be specified.

Selecting the INITIAL USER DATA menu

- 1 Press the [Utility] key eleven times.
INITIAL USER DATA appears.
- 2 From the 10-key pad, press the key ([1] through [3]) for the initial user data function that you wish to set.
The initial user data functions are as follows:
1 DATE&TIME
2 USER FAX NO.
3 USER NAME



Note

*If, at any time, you wish to quit setting/changing a initial user data function, press the [No/C] key. When the message **STOP SETTING?** appears, press the [Yes] key to quit.*

Specifying DATE&TIME


- 1 Select the **DATE&TIME** in the INITIAL USER DATA menu.
For details, refer to page 7-77.
- 2 Using the 10-key pad, enter the current time and date.

Enter the settings in the following order: hours, minutes, year, month, and day.
- 3 Press the [Yes] key to display the time zone setting. Press the [▲] and [▼] keys to select the appropriate time zone.
- 4 Press the [Yes] key.




Specifying USER FAX NO.


- 1 Select the **USER FAX NO.** in the INITIAL USER DATA menu.
For details, refer to page 7-77.
- 2 Using the 10-key pad, enter the fax number.
- 3 Press the [Yes] key.



Specifying USER NAME

- 1 Select the **USER NAME** in the INITIAL USER DATA menu.
For details, refer to page 7-77.
- 2 Using the 10-key pad, enter the user name for the machine.
 - Each press of the [123/ABC] key switches the input mode between numbers and letters.
[1]: Numbers can be typed in.
[A]: Letters can be typed in.
- 3 Press the [Yes] key.






When a message appears

8 When a message appears


8.1 When the message PAPER EMPTY appears

PAPER EMPTY message

When the currently selected paper tray runs out of paper, the message shown below appears, and printing cannot continue.




Check the paper tray that has run out of paper, and then supply paper according to the following procedures.


Indicator	Paper tray
1	Tray 1
2	Tray 2
	Bypass tray

Loading paper into tray 1

- 1 Remove the bypass tray.




- 2 Load the paper in the tray so that the front side of the paper (the side facing up when the package was unwrapped) faces up.
- 3 Attach the bypass tray in its original position.



Loading paper into the bypass tray


The bypass tray can be loaded with a maximum of 1 envelope, 1 OHP transparency, 1 card, or 10 sheets of plain paper.

- Load the paper so that the front side of the paper (the side facing up when the package was unwrapped) faces up.




Loading paper into tray 2 (option)


- 1** Pull out the drawer for tray 2.



- 2** Remove the drawer cover, and then press down on the paper-lifting plate until it locks into place.



- 3** Load the paper into the drawer so that the front side of the paper (the side facing up when the package was unwrapped) faces up.




- 4** Attach the drawer cover, and then return the drawer for tray 2 to its original position.

8.2 When the message TONER EMPTY appears

TONER EMPTY message

When toner is about to run out, the message shown below appears, indicating that the toner is almost empty. When this message appears, replace the toner cartridge with a new one as soon as possible. If you continue making copies, the toner will be emptied, and copies can no longer be made.




CAUTION

Used toner cartridges.

- In order to prevent the used toner cartridge from dirtying anything, keep it in the box.
- Dispose of the used toner cartridge according to your local regulations.
- Use only the toner that has been manufactured specifically for this machine. Never use any other types of toner, as a malfunction could result. For details, contact your service representative.

Replacing the toner cartridge

- 1 Open the front cover.




CAUTION


Decreased image quality.

- Since the imaging cartridge can easily be damaged by light, exposing the cartridge to light for a long period of time will result in decreased image quality.

- 2 Grab the handle of the imaging cartridge, and then pull it toward you to remove the cartridge.




- 3 Move the lever in the direction of the arrow to release the lock.




CAUTION

Incorrect handling of toner cartridge.


- When separating the toner cartridge from the drum cartridge, do not tilt the cartridge, otherwise toner may spill.
- Do not touch the PC drum under the flap of the drum cartridge, otherwise decreased image quality may result.
- Do not touch any metal parts of the drum cartridge or toner cartridge, otherwise the units may be damaged by static electricity.



- 4 Remove the toner cartridge from the drum cartridge.



- 5 Shake the new toner cartridge well.




! **CAUTION**


Decreased image quality.

- Do not touch the developer roller, otherwise decreased image quality may result.

- 6 Remove the protective cover from the toner cartridge.



- 7 Align the blue parts of the drum cartridge and toner cartridge, and then attach them together.






CAUTION

Incorrect handling of image cartridge.


- Do not push in the imaging cartridge with excessive force if the cartridge is not correctly aligned on the rail, otherwise the units may be damaged.

- 8 Align the tab on the imaging cartridge with the rail in the machine, and then install the cartridge.
- 9 Close the front cover.



8.3 When the message D/C LIFE appears

When the drum cartridge has reached the end of its service life, the message shown below appears. When this message appears, replace the drum cartridge with a new one as soon as possible.




CAUTION

Used drum cartridges.

- In order to prevent the used drum cartridge from dirtying anything, keep it in the box.
- Dispose of the used drum cartridge according to your local regulations.

Replacing the drum cartridge

- 1 Open the front cover.




CAUTION


Decreased image quality.

- Since the imaging cartridge can easily be damaged by light, exposing the cartridge to light for a long period of time will result in decreased image quality.

- 2 Grab the handle of the imaging cartridge, and then pull it toward you to remove the cartridge.




- 3 Move the lever in the direction of the arrow to release the lock.




⚠ CAUTION**Incorrect handling of toner cartridge.**


- When separating the toner cartridge from the drum cartridge, do not tilt the cartridge, otherwise toner may spill.
- Do not touch the PC drum under the flap of the drum cartridge, otherwise decreased image quality may result.
- Do not touch any metal parts of the drum cartridge or toner cartridge, otherwise the units may be damaged by static electricity.



- 4** Remove the toner cartridge from the drum cartridge.



- 5** Align the blue parts of the drum cartridge and toner cartridge, and then attach them together.






CAUTION

Incorrect handling of image cartridge.

- Do not push in the imaging cartridge with excessive force if the cartridge is not correctly aligned on the rail, otherwise the units may be damaged.

- 6 Align the tab on the imaging cartridge with the rail in the machine, and then install the cartridge.
- 7 Close the front cover.



Detail


After replacing the drum cartridge, specify the necessary setting for the function on the USER MANAGEMENT menu in the utility mode. For details, refer to "Selecting the USER MANAGEMENT menu" on page 7-17.

8.4 When the message PAPER MISFEED appears

PAPER MISFEED message


If the message shown below appears during printing and the machine stops operating, a paper misfeed has occurred in a paper tray.

Follow the procedure described below to clear the misfeed paper.




Clearing a paper misfeed in the paper trays


- 1 Remove all paper from the bypass tray.



- 2 Remove the bypass tray.




- 3 Remove all paper from tray 1. Do not reuse paper that has been misfed.




- 4 Reload the paper stack in the tray.

- 5 Attach the tray removed in step 2.


- 6 Reload the paper removed in step 1.




- 7 Remove the cover of optional tray 2, and then pull out the drawer.




- 8 Remove all paper from the drawer.



- 9 Reload the paper stack into the drawer, and then slide the drawer back into the paper feed cassette.



10 Open, then close the front cover.




8.5 When the message PAPER JAM appears

PAPER JAM message

If the message shown below appears during printing and the machine stops operating, a paper misfeed has occurred in the machine.

Follow the procedure described below to clear the misfed paper.




CAUTION

The area around the fusing unit is extremely hot.


→ Touching any part other than the paper may result in burns.

Clearing a paper misfeed in the machine

- 1 Open the front cover.




- 2 Remove the imaging cartridge.




- 3 Check the paper misfeed position.

? Do you want to clear the paper misfeeds?


- When the paper misfeed has occurred at the fusing section continue with step 4.
- When the paper misfeed has occurred at the separating section continue with step 8.




- 4 Open the fuser cover at the rear side of the machine.




- 5 Grab both sides of the paper, and then pull it out upward.




- 6 Grab both sides of the paper, and then carefully pull out the sheet of paper.



- 7 Close the fuser cover.



- 8 Grab both sides of the paper, and then carefully pull the sheet of paper straight upward.




CAUTION

Incorrect handling of imaging cartridge.

- Do not push in the imaging cartridge with excessive force if the cartridge is not correctly aligned on the rail, otherwise the units may be damaged.

- 9 Align the tab on the imaging cartridge with the rail in the machine, and then install the cartridge.
- 10 Close the front cover.



Detail


If PAPER JAM remains displayed, even after the misfeed-clearing procedure is performed, refer to "What does each message mean?" on page 8-28.

8.6 When the message ORIGINAL DOC. JAM appears

ORIGINAL DOC. JAM message


If the message shown below appears while scanning an original with the automatic document feeder and the machine stops operating, a paper misfeed has occurred in the automatic document feeder.

Follow the procedure described below to clear the misfed paper.




Clearing a paper misfeed in automatic document feeder


- 1 Open the document feeder cover.




- 2 Unload the document from the document feeder tray.



- 3 Raise the automatic document feeder.



- 4 While turning the document feed knob in the direction of the arrow, gently pull out the original.




- 5 Close the document feeder cover.

- 6 Load the documents removed in step 2 back into the tray.
Replace the document page that was misfed, according to the page number indicated in the display.

8.7 When the message PAPER SIZE ERROR appears

PAPER SIZE ERROR message


If the paper size specified for a paper tray differs from the size of the paper loaded in the tray, the message shown below appears when paper is fed from that tray.




Check the message for the paper tray and the paper size to be fed, and paper according to the corresponding procedure described below.

Paper size error for tray 1

- 1 Select **TRAY1 PAPER**.
For details, refer to “Paper source settings” on page 7-13.
- 2 Press the [1] key of the 10-key pad, and then specify the correct paper size and type.
For details, refer to “Specifying TRAY1 PAPER” on page 7-14.




- 3 Remove the bypass tray, and then remove all paper from the tray 1.




- 4 Load the desired paper into the tray.

- 5 Try performing the copy cycle again.




Paper size error for the bypass tray

- 1 Remove all paper from the bypass tray.



- 2 Load the desired paper into the tray.



- 3 Select the setting for the size and type of paper that is loaded.
For details, refer to “Specifying the size and type of manually fed paper” on page 4-6.
- 4 Try performing the copy cycle again.

TEXT	x1.00	1
[A]	A4?	ReSET= NO

↓


*PLAIN	OHP	CARD
←, → & YES		

↓

* A5	B5	A4
OK=YES	(CUSTOM=)	

8.8 When the message MACHINE TROUBLE appears

If the message shown below appears, some machine malfunction has occurred. Contact your service representative. When contacting the service representative, be sure to inform them of the machine code (error code: C####) that was indicated.








8.9 What does each message mean?


Message	Cause	Action
REMOVE PAPER IN BYPASS TRAY	Paper is loaded in the bypass tray.	Remove the paper from the bypass tray.
FRONT COVER OPEN ↕ CLOSE FRONT COVER	The front cover of the main unit is open or not securely closed.	Securely close the front cover.
DOCUMENT COVER OPEN ↕ CLOSE DOCUMENT COVER	The automatic document feeder is lifted up (while a document is loaded into it).	Securely close the automatic document feeder or remove the document from the automatic document feeder.
DOC.FEED COVER OPEN ↕ CLOSE DOC.FEED COVER	The document feeder cover is open.	Securely close the document feeder cover.
MEMORY FULL ↕ PRESS ANY KEY	The size of the data for the scanned document has exceeded the capacity of the memory.	Press the [Panel reset] key, or turn the machine off, then on again. (The scanned data should be cleared from the memory.)
MACHINE TROUBLE ↕ SERVICE CALL (C####)	Some problem occurred in the machine.	Turn the machine off, then on again. If the error is still displayed, contact your service representative.
FUSER COVER OPEN ↕ CLOSE FUSER COVER	The fuser cover of the main unit is open or not securely closed.	Securely close the fuser cover.
PAPER JAM ↕ OPEN FRONT COVER	A paper misfeed occurred.	Perform the misfeed-clearing procedure. (page 8-18)
	All misfed paper was not removed from the main unit.	
	The fuser cover of the main unit is open or not securely closed.	Close the fuser cover, then open and close the front cover.
NO SUITABLE PAPER ↕ LOAD PAPER (LT)	In fax mode, plain paper of a size other than letter, legal or A4 is loaded into the paper tray.	Load plain paper of the appropriate size into tray 1 or the optional tray 2.
INCORRECT T/C TYPE ↕ CHANGE T/C	Incorrect type of toner cartridge is installed.	Install the correct type of toner cartridge. (p. 8-6)
	Toner cartridge is not installed.	Install the toner cartridge. (page 8-7)

Message	Cause	Action
LINE PROBLEM ↕ (Flashing alternately) CHECK LINE	The telephone dialing system or telephone wiring system are not set correctly.	Check the telephone dialing system or telephone wiring system and use the appropriate Utility mode function to make the correct settings.
	The telephone cable is not attached correctly.	Correctly connect the telephone cable.
COMM.ERROR (####)	Communication is not possible because of some problem in the machine.	Check the transmission results.
	Communication is not possible because of a problem with the recipient/caller's fax machine.	
REDIAL ALL FAILED	All redial attempts failed because either the recipient's line is busy or there was no answer.	Check the condition of the recipient's line, and then try sending the fax again.
MEM.FULL/TX CANCEL	While sending a fax, the size of the data for the scanned image has exceeded the capacity of the memory.	Retrieve all received faxes stored in the memory.
		Send the fax by direct transmission.
MEM.FULL/RX CANCEL	While receiving a fax, the size of the data for the received image has exceeded the capacity of the memory.	Retrieve all received faxes stored in the memory.
FILE FULL/TX CANCEL	While sending a fax, the maximum of number of managed memory file is used.	Retrieve all received faxes stored in the memory.
FILE FULL/RX CANCEL	While receiving a fax, the maximum of number of managed memory file is used.	Retrieve all received faxes stored in the memory.
HANG UP THE PHONE	The receiver of the connected telephone is lifted.	Replace the receiver of the connected telephone on the hook.
TEXT ×1.00 1 ([A]) #XXX: EMPTY	(While specifying copy settings) The selected paper tray has run out of paper. “#” indicates the paper tray, and “XXX” indicates the paper size.	Either load paper of the specified size into the specified paper tray, or press the [Paper] key and select a different paper size.
TEXT ×1.00 1 ([A]) #XXX: Fax Err	A fax error occurred while an operation was being performed in Copy mode.	Press the [Fax] key to check the error condition, and take appropriate measures.
TEXT ×1.00 1 ([A]) #XXX: Comm.Err	A fax transmission error occurred while an operation was being performed in Copy mode.	Press the [Fax] key to check the error condition, and take appropriate measures.

8.10 When incorrect copies are produced

Symptom	Possible cause	Action
The image is too light. 	The density level for the Auto setting is set to "LIGHT".	Adjust the setting for DENSITY LEVEL (A) in the utility mode. (p. 7-23) Otherwise, cancel the "Auto" density setting, and then manually select the desired density setting. (p. 4-12)
	The density level is set to light.	Press the [▶] key, and then select a darker copy density. (p. 4-12)
	Does the message TONER EMPTY appear in the display?	Change the toner cartridge with a new one. (p. 8-7)
	The paper is damp.	Change the paper.
The image is too dark. 	The density level for the Auto setting is set to dark.	Adjust the setting for DENSITY LEVEL (A) in the utility mode. (p. 7-23) Otherwise, cancel the "Auto" density setting, and then manually select the desired density setting. (p. 4-12)
	The density level is set to dark.	Press the [◀] key, and then select a lighter copy density. (p. 4-12)
	The original glass surface is dirty.	Wipe the original glass clean with a soft, dry cloth.
	The original is not held tightly against the original glass.	Place the original in position so that it is held tightly against the original glass.
The copy is blurry. 	The paper is damp.	Change the paper.

Symptom	Possible cause	Action
<p>The copy has dark specks or spots.</p> 	The original glass surface is dirty.	Wipe the original glass clean with a soft, dry cloth.
	The original pad is dirty.	Wipe the original pad clean with a soft cloth dampened with neutral detergent.
	The original is highly transparent.	Place a blank sheet of paper over the original.
	The original is 2-sided.	If a thin double-sided document is being copied, the information on the back side may be reproduced in the copy. Press the [◀] key and select a lighter copy density.
	Something is sticking to the original glass (when the automatic document feeder is used).	Wipe the original glass clean with a soft, dry cloth.
<p>The copy has lines.</p> 	The drum cartridge has reached the end of its service life.	Contact your service representative.
	The image on the copy is not aligned properly.	Place the original correctly on the original glass against the original scales. or, load it in the automatic document feeder correctly along the document guide plates.
	The original may not be suitable for use in the automatic document feeder.	Raise the automatic document feeder and place the original on the original glass correctly against the original scales.
	The paper guides are not pressed up against the paper stack in the tray.	Slide the paper guides against the edges of the paper stack.
	The paper has an excessive curl.	Smooth out curls in the paper and reload the paper stack in the tray.
<p>The printed page is curled.</p>	<p>The paper that was used curls easily (as with recycled paper).</p>	Remove the paper from the paper tray, turn it over, and then load it again.
		Change the paper.

Symptom	Possible cause	Action
<p>The edge of the copy is dirty.</p> 	<p>The original pad is dirty.</p>	<p>Wipe the original pad clean with a soft cloth dampened with neutral detergent.</p>
	<p>You have selected paper of a size larger than the original (when the zoom ratio is full size).</p>	<p>Select paper that is the same size as the document. Otherwise, enlarge the copy to the selected paper size.</p>
	<p>The original is not placed in the correct position (when the zoom ratio is full size).</p>	<p>Select the same paper size as the original. Or, reload the paper in the same direction as the original.</p>
	<p>The reduction ratio selected does not match the paper size (when the copy is made at a manually adjusted reduction ratio).</p>	<p>Select a zoom ratio that adjusts the copy size to the size of the selected paper. Otherwise, make a reduced copy with a zoom ratio that matches the paper size.</p>

* If the problem is not corrected even after the operations described above are performed, contact your service representative.

8.11 The machine is not functioning as designed

Symptom	Possible cause	Action
Nothing appears in the display.	Is only the [Start] key lit green?	The energy save mode is enabled. Press any key on the control panel to cancel energy save mode.
	Has the machine been turned on?	Check that the power cord is firmly connected and that the (on) side of the power switch has been pressed.
	Is the contrast of the display too light?	From the machine setting menu of the utility mode, adjust the display to the correct contrast. Refer to "Specifying LCD CONTRAST" on page 7-10.
The [Start] key indicator does not light up green.	The machine has just been turned on and is warming up.	It takes the machine less than 25 seconds to be ready to make copies after it has been turned on. Please wait.
The machine does not operate when it is turned on.	The power cord is left unplugged.	Plug the power cord into the power outlet.
	The room's circuit breaker is open.	Close the room's circuit breaker.

* If the problem is not corrected even after the operations described are performed, turn off the machine, unplug its power cord, and then contact the service representative.

8.12 When faxing is not performed correctly

Faxes cannot be sent

Symptom	Possible cause	Remedy
The document cannot be scanned.	The document is too thick.	Position the document on the original glass to send it. (p. 5-17)
	The document is too thin or too small.	Position the document on the original glass to send it. (p. 5-17)
The document was scanned at an angle.	The document is not positioned correctly.	Adjust the document guide plates for the size of the document. (p. 5-15)
The fax received by the recipient is not clear.	The document is not positioned correctly.	Position the document correctly. (p. 5-15 and p. 5-17)
	The original glass is dirty.	Wipe the glass with a soft, dry cloth. (p. 9-9)
	The text in the document is too faint.	Adjust the scanning contrast. (p. 7-58)
	There is a problem with the telephone connection or with the recipient's fax machine.	Check that this machine can make clean copies. If it can, try sending the fax again.
The fax received by the recipient is blank.	The document was sent with the front side facing down (while using the automatic document feeder).	Load the document with the front side facing up, and then try sending the fax again. (p. 5-15)
Faxes cannot be sent automatically.	The fax number is wrong.	Check the fax number.
	A number specifically for telephone calls is being dialed.	Check the number.
	There is a problem with the recipient's fax machine (it is out of paper, it is not set to receive faxes automatically, it is turned off, etc.).	Contact the recipient.

Faxes cannot be received

Symptom	Possible cause	Remedy
The received fax is not clear.	Paper that does not meet specifications has been used.	Use paper that meets specifications. (p. 3-26)
	The paper is damp.	Replace the paper. (p. 8-4 and p. 8-4)
	The toner is empty.	Replace the toner bottle with a new one. (p. 8-7)
	There is a problem with the telephone connection or with the caller's fax machine.	Check that the machine can make clean copies. If it can, have the caller send the fax again.
The received fax is blank.	The toner is empty.	Replace the toner bottle with a new one. (p. 8-7)
	The caller sent the back of the fax pages.	Contact the caller.
Faxes cannot be received automatically.	The machine is set to receive faxes manually.	Set the machine to automatic reception. (p. 7-64)
	The memory is full.	Load paper if it is empty, and then print the faxes stored in the memory.
	Some error occurred.	Follow the instructions in any messages that appear on the display. (p. 8-28)
Black streaks appear through the print.	There is a problem with the telephone connection or with the caller's fax machine.	Check that the machine can make clean print. If it can, have the caller send the fax again.

Calls cannot be sent

Symptom	Possible cause	Remedy
Nothing can be heard from the connected telephone.	The cord from the telephone is not connected correctly to the main unit.	Correctly connect the telephone cord to the main unit.
	The telephone cord from the wall jack is not connected correctly to the main unit.	Correctly connect the telephone cord from the wall jack to the main unit.
	Transmitting.	Check again after the transmission is finished.
After dialing, the ringing cannot be heard.	The telephone dialing system (TONE/PULSE) is not set correctly.	Correctly set the telephone dialing system. (p. 7-71)
	The telephone wiring system (PSTN/PBX) is not set correctly.	Correctly set the telephone wiring system. (p. 7-73)
After the [Speaker] key is pressed, it is difficult to hear the recipient/caller's voice.	The monitoring volume is too low.	Increase the monitoring volume. (p. 7-72)
The ringing of the telephone is too low (loud).	The ringer volume of the connected telephone is set too low (loud).	Adjust the ringer volume of the connected telephone.



Miscellaneous

9 Miscellaneous

9.1 Specifications

bizhub 160f

Specification	
Type	Desktop
Platen type	Fixed platen (unit scanning)
Photoconductor	OPC
Copying system	Electrostatic dry powdered image transfer to plain paper
Developing system	Single component developing system
Fusing system	Lamp-heated roller
Resolution	600 dpi × 600 dpi
Types of original	<ul style="list-style-type: none"> Types: Sheets, books Size: Maximum Legal L
Kinds of paper	<ul style="list-style-type: none"> Plain paper, recycled paper (60 g/m² to 90 g/m²) Exclusive paper: card (91 g/m² to 163 g/m²), OHP transparencies, envelopes
Print paper size	<p>Tray 1/Bypass tray A4 L, B5 L, A5 L, 16K L, Legal L, Letter L, Half Letter L, FLS (210 mm × 330 mm)</p> <p>Custom size Paper width: 90 mm to 216 mm Paper length: 140 mm to 356 mm</p>
Capacity	<p>Tray 1</p> <ul style="list-style-type: none"> Plain paper, recycled paper: 250 sheets (80 g/m²) Exclusive paper <ul style="list-style-type: none"> card: 10 sheets OHP transparencies: 5 sheets envelopes: 1 sheet <p>Bypass tray</p> <ul style="list-style-type: none"> Plain paper, recycled paper: 10 sheets (80 g/m²) Exclusive paper <ul style="list-style-type: none"> card: 1 sheet OHP transparencies: 1 sheet envelopes: 1 sheet
Warm-up time	Less than 25 seconds at room temperature (23°C)
First copy	Less than 13 seconds (A4 L or Letter L)
First page print time	Less than 16 seconds (A4 L or Letter L)
Copy speed	<ul style="list-style-type: none"> Print: 16 sheets/min (A4 L or Letter L) Copy: 12 sheets/min (A4 L or Letter L)

Specification	
Zoom ratios	<ul style="list-style-type: none"> • Full size: × 1.00 • Enlargement ratios: × 1.15, × 1.41, × 2.00 and × 4.00 • Reduction ratios: × 0.81, × 0.70, × 0.50 and × 0.25 • Zoom ratios: × 0.25 to × 4.00 (in × 0.01 increments)
Multiple copies	1 to 99 sheets
Density control	Auto text mode, text mode, and photo mode
Lost image	<ul style="list-style-type: none"> • Leading edge: 4 mm, Trailing edge: 4 mm • Rear edge: 4 mm, Front edge: 4 mm
Power requirements	120 V - 127 V: less than 7.2 A, 60 Hz 220 V - 240 V: less than 3.8 A, 50/60 Hz
Power consumption	120 V - 127 V: less than 840 W 220 V - 240 V: less than 850 W
Dimensions	508 mm (width) × 608 mm (depth) × 468 mm (height)
Standard memory	16 MB
Weight	17.3 kg

L: Lengthwise

Automatic document feeder

Specification	
Document feeding system	Standard mode: 1-sided original
Kinds of original	Plain paper: 35 g/m ² to 128 g/m ²
Original size	<ul style="list-style-type: none"> • A4 L, B5 L, A5 L, Legal L, Letter L, Half Letter L • Custom size Paper width: 138 mm to 216 mm, Paper length: 130 mm to 356 mm
Capacity of document feed tray	Maximum 50 sheets (80 g/m ²)
Power consumption	30 W
Dimensions	506 mm (width) × 350 mm (depth) × 90 mm (height)
Weight	3 kg

L: Lengthwise

Paper feed unit PF-501

Specification	
Kinds or paper	Plain paper, recycled paper (60 g/m ² to 90 g/m ²)
Paper sizes	A4 L, Letter L
Capacity	500 sheets (80 g/m ²)
Power consumption	Less than 7 W
Dimensions	401 mm (width) × 615 mm (depth) × 138 mm (height)
Weight	4 kg

L: Lengthwise

9.2 List of utility/function menu commands

Utility menu commands

Manufacturer's default settings appear in bold.

Menu	Function	Settings
1 MACHINE SETTING	1 AUTO PANEL RESET	ON (0.5/ 1/2/3/4/5)/OFF
	2 ENERGY SAVE MODE	TIMER=1-240 min. (Default: 15 min)
	3 DENSITY (ADF)	MODE1 /MODE2
	4 DENSITY (BOOK)	MODE1 /MODE2
	5 PRINT DENSITY	LIGHT to DARK (6 levels)
	6 LCD CONTRAST	LIGHT to DARK (4 levels)
	7 LANGUAGE	Default: ENGLISH
	8 LAMP OFF TIME	MODE1 /MODE2
	9 BUZZER VOLUME	HIGH/ LOW /OFF
	0 INITIAL MODE	COPY /FAX
2 PAPER SOURCE SETUP	1 TRAY1 PAPER	PLAIN /OHP/CARD/ENVELOPE A5 <input type="checkbox"/> /B5 <input type="checkbox"/> / A4 <input type="checkbox"/> /FLS/16K <input type="checkbox"/> /HL <input type="checkbox"/> /LT <input type="checkbox"/> /LG <input type="checkbox"/> / CUSTOM
	2 TRAY SETTING	(For each paper tray) FIXED/ CONTINUOUS
3 USER MANAGEMENT	CHANGE D/C	-
4 ADMIN. MANAGEMENT	REMOTE MONITOR	LIMITED /FULL/OFF
5 COPY SETTING	1 PAPER PRIORITY	TRAY1 /TRAY2
	2 DENSITY PRIORITY	AUTO /MANUAL/PHOTO
	3 DENSITY LEVEL(A)	LIGHT to DARK (3 levels)
	4 DENSITY LEVEL(M)	LIGHT to DARK (9 levels)
	5 OUTPUT PRIORITY	NON /SORT
	6 RESOLUTION	600 × 300 /600 × 600
6 FAX REGISTRATION	1 ONE-TOUCH DIAL	For details, refer to page 7-28.
	2 SPEED DIAL	For details, refer to page 7-32.
	3 GROUP DIAL	For details, refer to page 7-36.
	4 PROGRAM DIAL	For details, refer to page 7-40.
	5 BATCH TX	For details, refer to page 7-51.
	6 MAILBOX	For details, refer to page 7-55.

Menu	Function	Settings
7 TX OPERATION	1 SCAN CONTRAST	LIGHT to DARK (5 levels)
	2 RESOLUTION	STD /FINE/S/F/ H/T(STD/FINE/S/F)
	3 DEFAULT TX	MEM.TX /ADF TX
	4 HEADER	ON/OFF
8 RX OPERATION	1 MEMORY RX MODE	ON/ OFF
	2 NO. of RINGS	1 to 16 (Default: 2)
	3 REDUCTION RX	ON/OFF/CUT
	4 RX PRINT	MEMORY RX /PRINT RX
	5 RX MODE	AUTO RX /MANUAL RX
	6 FORWARD	ON/ON (PRINT)/ OFF
	7 FOOTER	ON/ OFF
	8 SELECT TRAY	(For each paper tray) DISABLE/ ENABLE
	9 CLOSED NETWORK	ON/ OFF
9 COMM.SETTING	1 TONE/PULSE	TONE /PULSE
	2 LINE MONITOR	HIGH/ LOW /OFF
	3 PSTN/PBX	PSTN /PBX
10 REPORTING	1 ACTIVITY REPORT	ON/OFF
	2 RESERV.REPORT	ON/ OFF
	3 TX RESULT REPORT	ON/ OFF
	4 RX RESULT REPORT	ON/ OFF
11 INITIAL USER DATA	1 DATE&TIME	For details, refer to page 7-78.
	2 USER FAX NO.	For details, refer to page 7-78.
	3 USER NAME	For details, refer to page 7-79.

Function menu commands

Menu	Settings
1 BROADCAST	Recipients
2 TIMER TX	Transmission time
3 MAILBOX TX	Recipient, mailbox ID and password
4 PRINT MAILBOX RX	Mailbox ID
5 POLLING TX	SINGLE/MULTI, polling ID and password
6 POLLING RX	Caller, polling ID and password
7 RELAY INITIATE	Recipient, relay box ID and password
8 CANCEL RESERV.	Select job


9.3 Care of the machine

Cleaning

Turn off the machine before cleaning it.


Housing cover

- Wipe the surface of the housing cover with a soft cloth dampened with a mild household detergent.




Original glass

- Wipe the surface of the original glass clean with a soft, dry cloth.



Original pad

- Wipe the surface of the original pad clean with a soft cloth dampened with a mild household detergent.



Control panel




CAUTION

Incorrectly cleaning the control panel keys may damage them.

- Never use mild household detergent or glass cleaner to clean the control panel.

- Wipe the surface of the control panel clean with a soft, dry cloth.



9.4 Function combination matrix

Conditions for combined functions

Function set last		Paper		Zoom		Density			Original		Copy		Finishing	
		Manual paper selection (tray1 or tray2)	Manual paper selection (bypass tray)	Fixed zoom	Optional zoom	Auto density	Manual density	Text	Photo	Original glass	Automatic document feeder	Single-sided	2in1	Non-sort
Function set first														
Paper	Manual paper selection (tray1 or tray2)		○	x	x	x	x	x	x	x	x	x	x	x
	Manual paper selection (bypass tray)	○		x	x	x	x	x	x	x	x	x	x	x
Zoom	Fixed zoom	x	x		○	x	x	x	x	x	x	x	x	x
	Optional zoom	x	x	○		x	x	x	x	x	x	x	x	x
Density	Auto density	x	x	x	x		○	x	○	x	x	x	x	x
	Manual density	x	x	x	x	○		x	x	x	x	x	x	x
	Text	x	x	x	x	x	x		○	x	x	x	x	x
Original	Photo	x	x	x	x	○	x	○		x	x	x	x	x
	Original glass	x	x	x	x	x	x	x		○	x	○	x	○
Copy	Automatic document feeder	x	x	x	x	x	x	x	○		x	x	x	x
	Single-sided	x	x	x	x	x	x	x	x	x		○	x	x
Finishing	2in1	x	x	x	x	x	x	x	○	x	○		x	x
	Non-sort	x	x	x	x	x	x	x	x	x	x	x		○
Sort	Sort	x	x	x	x	x	x	x	○	x	x	x	○	

Conditions for combined functions

Code	Description
x	The functions can be combined.
○	The functions cannot be combined.

9.5 Glossary

Term	Definition
Automatic redialing	If a call cannot be completed, for example if the recipient's machine is busy, the recipient is automatically called again. If a document queued in the memory to be sent contains multiple pages, until the time for redialing has been reached, it is advanced in the queue and sent.
Book document	A bound document such as a book or catalog.
F codes	F codes are mailbox functions, such as "SUB" (sub-addresses), "SEP" (selective polling), "SID" and "PWD" (passwords), regulated by the G3 standards of the ITU-T (International Telecommunication Union). Mailbox transmission/reception and relay initiation transmission are possible only with similar machines compatible with F code transmission.
Internet fax	Faxes can be transmitted via the Internet or an Intranet instead of through telephone lines. Instead of a fax number, the recipient's e-mail address is specified and the scanned image (TIFF format) can be sent as an e-mail message to a computer or Internet fax. In addition, e-mail messages from computers can be received as images.
General subscriber line	Analog telephone lines (public network)
JBIG coding method	New method of data compression/decompression, standardized by the Joint Bi-level Image Expert Working Group, a subcommittee of the International Telecommunications Union (ITU-T). Effective for transferring large amounts of data or high-resolution image data such as halftones.
Manual reception	Receiving a fax document after talking on the telephone.
Manual transmission	Sending a fax document after talking on the telephone.
Memory	Stores fax and copy image data. By installing expansion memory, much more image data can be stored in the memory.
Memory reception	When paper runs out or a paper misfeed occurs while receiving a fax, the data is automatically stored in the memory and printed out later. Even if the paper runs out during the night or when the user is away, the fax document can still be received.
Network scanner	This is a function that allows scanned images to be sent to a computer via a network. They can also be sent as e-mail messages or uploaded to FTP servers.
PBX	Abbreviation for private branch exchange Exchange equipment installed in a company or a plant to connect a number of telephone sets with multiple station lines in order to enable unrestricted communications between the telephone sets.
Protocols	The necessary rules for communication
Touch-tone signals	A signal used on the telephone line; used when calling on a push-button line or using push-button services. By pressing the [*] key in the 10-key pad, touch-tone signals are used, even if a dial phone line is connected.

9.6 Paper size and zoom ratio tables

Paper sizes

Paper format	Metric size	English size
A3 Wide	311 mm × 457 mm	12-1/4 × 18
A3	297 mm × 420 mm	11-3/4 × 16-1/2
A4	210 mm × 297 mm	8-1/4 × 11-3/4
A5	148 mm × 210 mm	5-3/4 × 8-1/4
A6	105 mm × 148 mm	4-1/4 × 5-3/4
B4	257 mm × 364 mm	10 × 14-1/4
B5	182 mm × 257 mm	7-1/4 × 10
B6	128 mm × 182 mm	5 × 7-1/4

Paper format		English size	Metric size
Ledger		11 × 17	279 mm × 432 mm
11 × 14		11 × 14	279 mm × 356 mm
Computer		10-1/8 × 14	257 mm × 356 mm
10 × 14		10 × 14	254 mm × 356 mm
9-1/4 × 14		9-1/4 × 14	236 mm × 356 mm
Legal		8-1/2 × 14	216 mm × 356 mm
Foolscap	Government Legal	8-1/2 × 13	216 mm × 330 mm
Foolscap		8 × 13	203 mm × 330 mm
Foolscap		8-2/3 × 13	220 mm × 330 mm
Foolscap	Folio	8-1/4 × 13	210 mm × 330 mm
8-1/4 × 11-3/4		8-1/4 × 11-3/4	210 mm × 301 mm
Letter		8-1/2 × 11	216 mm × 279 mm
Government Letter		8 × 10-1/2	203 mm × 267 mm
Quarto		8 × 10	203 mm × 254 mm
Statement	Invoice	5-1/2 × 8-1/2	140 mm × 216 mm
4 × 6		4 × 6	102 mm × 152 mm

Zoom ratios

Metric sizes		
Document paper size	Desired paper size	Zoom ratio
A3 297 mm × 420 mm 11-3/4 × 16-1/2	A4	× 0.70
	A5	× 0.50
	B4	× 0.86
	B5	× 0.61
A4 210 mm × 297 mm 8-1/4 × 11-3/4	A5	× 0.70
	A6	× 0.50
	B5	× 0.86
	B6	× 0.61
	A3	× 1.41
	B4	× 1.22
A5 148 mm × 210 mm 5-3/4 × 8-1/4	A6	× 0.70
	B6	× 0.86
	A4	× 1.41
	A3	× 2.00
	B4	× 1.73
	B5	× 1.22
A6 105 mm × 148 mm 4-1/4 × 5-3/4	A4	× 2.00
	A5	× 1.41
	B5	× 1.73
	B6	× 1.22
B4 257 mm × 364 mm 10 × 14-1/4	A4	× 0.81
	A5	× 0.57
	B5	× 0.70
	B6	× 0.50
	A3	× 1.15
B5 182 mm × 257 mm 7-1/4 × 10	A5	× 0.81
	A6	× 0.57
	B6	× 0.70
	A3	× 1.64
	A4	× 1.15
	B4	× 1.41

Metric sizes		
Document paper size	Desired paper size	Zoom ratio
B6 128 mm × 182 mm 5 × 7-1/4	A6	× 0.81
	A4	× 1.64
	A5	× 1.15
	B4	× 2.00
	B5	× 1.41

English sizes		
Document paper size	Desired paper size	Zoom ratio
Ledger 11 × 17 279.4 mm × 431.8 mm	11 × 14	× 0.82
	Legal	× 0.72
	Foolscap	× 0.76
	Letter	× 0.64
	Invoice	× 0.50
11 × 15 279.4 mm × 381 mm	11 × 14	× 0.93
	Legal	× 0.77
	Foolscap	× 0.77
	Letter	× 0.73
	Invoice	× 0.50
11 × 14 279.4 mm × 355.6 mm	Legal	× 0.77
	Foolscap	× 0.77
	Letter	× 0.77
	Invoice	× 0.50
Legal 8-1/2 × 14 215.9 mm × 355.6 mm	Foolscap	× 0.92
	Letter	× 0.78
	Invoice	× 0.60
	11 × 17	× 1.21
Foolscap 8-1/2 × 13 215.9 mm × 330.2 mm	Letter	× 0.84
	Invoice	× 0.64
	11 × 17	× 1.29
	11 × 14	× 1.07
Letter 8-1/2 × 11 215.9 mm × 279.4 mm	Invoice	× 0.64
	11 × 17	× 1.29
	11 × 14	× 1.27

English sizes		
Document paper size	Desired paper size	Zoom ratio
Invoice 5-1/2 × 8-1/2 139.7 mm × 215.9 mm	11 × 17	× 2.00
	11 × 14	× 1.64
	Legal	× 1.54
	Foolscap	× 1.52
	Letter	× 1.29

Zoom ratio = Paper size/document size

1 inch = 25.4 mm

1 mm = 0.0394 inch

10

Index

10 Index

Numerics

2in1 copies 4-14

A

Activity report 7-75

Administrative setting 7-18

Auto 3-22

Auto panel reset 3-21

Auto print start 3-22

Auto tray switching 3-22

Automatic document feeder 9-4

B

Basic copy operation 4-3

Batch transmission 6-8

 Setup 7-51

Broadcast transmission 6-9

C

Canceling queued document . 6-21

Care of the machine 9-9

Chain dialing 5-8

Communication settings

 Monitoring volume 7-72

Control panel 3-12

Copy paper 3-26

Copy settings 7-21

Copy tray

 Angle 3-9

D

Default settings 3-20

Dialing 5-3

Direct transmission 6-5

E

Energy save mode 3-22

F

F codes 6-27

Fax resolution 5-14

Fax transmission

 Basic faxing 5-15

 Dialing 5-3

 Loading documents

 into the automatic

 document feeder 5-15

 Positioning documents

 on the Original Glass 5-17

Finishing copies 4-15

Function combination matrix . 9-11

G

Group dialing 5-7

 Setup 7-36

I

Image density 4-12

Installation site 2-3

L

Legal restrictions on copying .. 2-7

Loading original

 Automatic document

 feeder 3-33, 3-34

 Precautions 3-33

 Specific types of originals 3-33

Loading paper 3-28

 Bypass tray 3-31, 8-4

 Precautions 3-27

 Tray1 3-30, 8-4

 Tray2 3-32, 8-5

M

- Machine settings 7-4
- Machine status 3-40
- Mailbox reception 6-24
- Mailbox setup 7-55
- Mailbox transmission 6-14
- Manual reception 6-23
- Manual transmission 6-6
- Memory full 5-18
- Memory reception 6-23
- Messages
 - D/C life 8-11
 - Machine trouble 8-27
 - Original document jam 8-22
 - Paper empty 8-3
 - Paper jam 8-18
 - Paper misfeed 8-15
 - Paper size error 8-24
 - Toner empty 8-6

O

- One-touch dialing 5-5
 - Setup 7-28
- Operating environment 2-5

P

- Paper
 - Paper specifications 3-26
 - Unsuitable paper 3-27
- Paper feed cassette PF-125 9-5
- Paper feeding 1-27
- Paper length 1-28
- Paper selection 4-5
- Paper sizes 9-13
- Paper source settings 7-13
- Paper width 1-28
- Phone book 5-10
- Placing original
 - Original glass 3-35
 - Precautions 3-33
 - Specific types of originals 3-33

- Polling reception 6-25
- Polling transmission 6-18
- Positioning
 - Books 3-38
 - Highly transparent originals 3-37
 - Sheet original 3-36
- Power source 2-3
- Print area 3-47
- Program dialing 5-9
 - Setup 7-40
- Programming fax settings 7-26

Q

- Queued jobs report 7-76

R

- Reception result report 7-76
- Reception settings
 - Footer printing 7-68
 - Forwarding setup 7-67
 - Memory reception mode .. 7-64
 - Number of rings 7-65
 - Printing mode 7-66
 - Reception mode 7-66
 - Reduced printing 7-66
 - Tray selection 7-68
- Regulation notices 1-15
- Relay initiation transmission ... 6-16
- Replacing
 - Toner cartridge 8-7
- Resetting
 - Auto panel reset 3-21
 - Panel 3-21

S

- Sorting 4-16
- Space requirements 2-4
- Specifications 9-3
- Speed dialing 5-6
 - Setup 7-32

T

- Timer transmission6-12
- Transmission result report7-76
- Transmission results5-19
- Transmission settings
 - Default transmission mode 7-60
 - Resolution7-59
 - Scanning contrast7-58
- Turning
 - Off3-19
 - On3-18

U

- User management settings7-17
- Utility mode7-3

Z

- Zoom ratio4-10, 9-14

